



BLACK & VEATCH Waste Science, Inc.

29010

The Curtis Center, Suite 705, 601 Walnut Street, Philadelphia, Pennsylvania 19106-3307, (215) 928-0700, Fax: (215) 928-1780

U.S. Environmental Protection Agency
Treatment Plant/Oil Services Company
Work Assignment 12

BVWS Project 52012.545
April 17, 1995

Mr. Narindar Kumar, Chief
Site Assessment Section
U.S. Environmental Protection Agency
345 Courtland Street, N.E.
Atlanta, Georgia 30365

REC'D.

SEP 21 1995

9/21/95
NFGAO
U.S. EPA

GM

Subject: Site Inspection Prioritization
Treatment Plant/Oil Services Company
Columbia, Maury County, TN
EPA ID TND980515779
with 3840

Dear Mr. Kumar:

BLACK & VEATCH Waste Science, Inc. (Black & Veatch) has been tasked by the U.S. Environmental Protection Agency (EPA) to conduct a Site Inspection Prioritization (SIP) for the Treatment Plant/Oil Services Company (Treatment Plant) site in Columbia, Maury County, Tennessee. In accordance with the scope of work, a preliminary Hazard Ranking System (HRS) score was prepared to determine the need for future activities at the site.

The Treatment Plant site is located on Santa Fe Pike in the northern section of the city of Columbia, Tennessee (Refs. 1; 2; 3). The Duck River is located approximately 0.1 mile to the east of the onsite waste sources (Ref. 1). The facility is the former City of Columbia Sewage Treatment Plant. The Treatment Plant site operated as a wastewater treatment plant for soluble oil, and is no longer an active facility; however, records vary regarding the property ownership and the duration of the operational period at the facility (Refs. 4; 5). Site Assessments performed by EPA in 1983 and 1984 indicate that the site began operations in 1980 (Refs. 2; 3). However, a letter dated in 1979 indicates that the Oil Services Company was cited in 1979 for violation of the city's sewer use ordinance for discharging untreated waste materials into the sewage treatment plant (Refs. 4; 6; 7).

Operations at the facility consisted of treatment of soluble waste oil, which included the processing of a waste sludge, and treatment of waste water which was discharged into the municipal water system. The Treatment Plant facility accepted waste oil from a wide variety of customers, with a large volume of their waste generated from electroplating and degreasing operations (Ref. 4). The waste products were initially run through a series of settling tanks and treatment systems to separate the oil and water, remove metals, and eliminate organics through biodegradation (Refs. 4; 8). The resulting sludges were contained in drums and disposed of offsite. Non-hazardous sludge was disposed of in licensed landfills, and hazardous sludges were disposed of in permitted hazardous waste landfills (Refs. 4; 8). The facility conducted its own periodic testing of the wastestreams, and possessed a National Pollution Discharge Elimination System (NPDES) permit which allowed for the treated wastewater to be discharged into the municipal water system (Ref. 4). Records indicate that this effluent was periodically tested, but it is not known how often testing was performed (Refs. 3, p. 5; 9). Wastes contained at the facility include wastewater and oil sludges which commonly contain cadmium, chrome, copper, lead, nickel, silver, zinc, benzene, toluene, xylene, 1,1,1-trichloroethane, trichloroethylene, and polychlorinated biphenyls (Refs. 2; 3, p. 1; 4, pp. 2, 3; 8; 10, pp. 2-6).

File information is limited regarding previous investigations at the Treatment Plant facility. A Preliminary Assessment (PA) was conducted at the facility by the Tennessee Department of Health & Environment, Division of Solid Waste (DSWM) in December 1983. The PA indicated that of the 200,000 gallons of waste oil which were stored onsite, 100,000 gallons were treated daily (Ref. 2). A Site Inspection (SI) was conducted by DSWM personnel in April 1984. The SI reported that waste oil was contained in concrete basins onsite. No environmental samples were collected as part of the investigation (Ref. 3). Since the time of the last investigations, the facility has ceased operations (Refs. 4; 7; 11). The tanks which were previously used in the separation process have either been filled or removed, and all buildings previously onsite have been demolished (Ref. 11). No known testing has been conducted at the site since its closing. Currently, the land at the former facility is not being utilized (Ref. 11).

Potable water within a 4-mile radius of the Treatment Plant facility is supplied primarily by Columbia Power and Water (CPW), which currently serves approximately 15,500 connections in the city of Columbia and the surrounding areas. The entire CPW water supply is obtained from one intake on the Duck River, which is located approximately 1 mile upstream from the Treatment Plant site (Refs. 1; 12). Residents who are not serviced by the CPW system utilize private wells or springs in the area which tap into the shallow aquifers of the Mississippian

limestone of the Central Basin. The water table in this area is usually encountered at a depth of less than 200 feet below land surface (bls) (Refs. 13, pp. 2-10, 13; 14, pp. 5-14; 15). The estimated population within a 4-mile radius of the site that uses groundwater for drinking water is approximately 128 people, radially distributed as follows: 0 - 0.25 mile, 0 persons; 0.25 - 0.50 mile, 0 persons; 0.50 - 1 mile, 0 persons; 1 - 2 miles, 21 persons; 2 - 3 miles, 34 persons; 3 - 4 miles, 73 persons (Refs. 1; 16; 17).

Runoff from the Treatment Plant facility flows overland approximately 600 feet eastward, where it enters the Duck River (Ref. 1). The surface water pathway continues for 15 miles along the Duck River (Refs. 1; 18). There are approximately 3 miles of wetland frontage located along the surface water pathway (Ref. 18). The average annual flow for the Duck River is approximately 2,094 cubic feet per second (cfs) (Ref. 19). There are no surface water intakes along the surface water pathway (Ref. 12). The Duck River serves as a habitat for the birdwing pearly mussel (*Conradilla caelata*) and the Cumberland monkeyface pearly mussel (*Quadrula intermedia*). The ranges of other threatened or endangered species may include portions of the Duck River; however, exact locations of the habitat for these species have not been identified (Ref. 20). The Duck River is commonly used for recreational fishing and boating in the Columbia area (Ref. 12).

There are approximately 12,538 residents within a 4-mile radius of the Treatment Plant site, radially distributed as follows: 0 - 0.25 mile, 76 persons; 0.25 - 0.50 mile, 506 persons; 0.50 - 1 mile, 2,916 persons; 1 - 2 miles, 4,727 persons; 2 - 3 miles, 3,349 persons; 3 - 4 miles, 964 persons (Refs. 1; 16; 21; 22). The nearest residence is located 0.1 mile from the site. There are no known residents, schools, daycare facilities or commercial agriculture operations located within 200 feet of the waste sources onsite (Ref. 1). Approximately 74 acres of wetlands are located within the 4-mile radius of the site (Refs. 1; 18; 23). No threatened or endangered species have been positively identified within a 4-mile radius of the site (Ref. 20).

Due to the low potential for contamination and limited number of targets, no further action at the Treatment Plant/Oil Services Company site is recommended.

Attached are all references used in this evaluation. If you have any questions or comments, please contact me at (215) 928-2207 or Victor Blix at (404) 643-2320.

Very truly yours,

BLACK & VEATCH Waste Science, Inc.

A handwritten signature in cursive script, appearing to read "Michael A. Ferrari".

Michael Ferrari
Site Manager

enclosure

cc: Victor Blix, BVWS-Atlanta

REFERENCES

1. U.S. Department of the Interior, Geological Survey Topographic Maps, 7.5 minute series Topographical Quadrangle Maps of Tennessee: Godwin, TN, 1988; Carter's Creek, TN, 1982; Columbia, TN, 1989; Glendale, TN, 1981. Scale 1:24,000.
2. Environmental Protection Agency, Potential Hazardous Waste Site, Preliminary Assessment, for Oil Services Co./Treatment Plant, December 16, 1983.
3. Environmental Protection Agency, Potential Hazardous Waste Site, Site Inspection Report, for Oil Services Co./Treatment Plant, April 9, 1984.
4. Michael Ferrari, Black & Veatch Waste Science, Inc., in memorandum to Treatment Plant/Oil Services Co. File, dated February 10, 1995. Subject: Waste Treatment.
5. Memorandum; Superfund Site Master List, August 8, 1983. Subject: Three sites on Master List involve Harris'/Oil Services Company Operations.
6. Letter to Mr. Michael Stone, Director of Sewer Services, City of Columbia, dated May 22, 1979. Subject: Oil Services Company, Deposition of Waste Oil.
7. Michael Ferrari, Black & Veatch Waste Science, Inc., in memorandum to Treatment Plant/Oil Services Co. File, dated February 9, 1995. Subject: Facility Status.
8. Oil Services Company, Description of Waste Treatment Processes, undated.
9. Ruth Yates, Tennessee Department of Public Health, in office correspondence to files, dated August 4, 1980. Subject: Phone Conversation with Ken Harris, Oil Service Company.
10. N. Irving Sax and Richard J. Lewis, Sr., (eds.) Hawley's Condensed Chemical Dictionary. New York: Van Nostrand Reinhold.
11. Michael Ferrari, Black & Veatch Waste Science, Inc., in memorandum to Treatment Plant/Oil Services Co. File, dated February 10, 1995. Subject: Facility Status (2).

12. Michael Ferrari, Black & Veatch Waste Science, Inc., in memorandum to Treatment Plant/Oil Services Co. File, dated February 13, 1995. Subject: Columbia Power & Water Service Area.
13. Roy Newcome, Jr., State of Tennessee, Department of Conservation, Division of Geology, Ground Water in the Central Basin of Tennessee, Report of Investigations N^o 4, 1958.
14. Charles V. Theis, U.S. Department of the Interior and Tennessee Division of Geology, Ground Water in South-Central Tennessee, Water Supply Paper 677, 1936.
15. Tennessee Department of Environment and Conservation, Division of Water Supply, Records of Water Wells in Selected Areas of Tennessee, December 1, 1994.
16. U.S. Department of Commerce, Bureau of the Census, 1990 Census of Population and Housing, Summary Population and Housing Characteristics, Tennessee, 1991 CPH-1-44 (Washington, D.C.: GPO, 1991).
17. Michael Ferrari, Black & Veatch Waste Science, Inc., in memorandum to Treatment Plant/Oil Services Co. File, dated February 13, 1995. Subject: Population served by groundwater.
18. U.S. Department of the Interior, National Wetland Inventory Maps, 7.5 minute series, Quadrangles for Godwin, TN, 1988; Williamsport, TN, 1981.
19. U.S. Geological Survey, Water Resources Data, Tennessee, Water Year 1992, U.S. Geological Survey Water-Data Report TN-92-1.
20. U.S. Fish and Wildlife Service, Southeast Region, Endangered & Threatened Species of the Southeast United States, January 1992.
21. Environmental Protection Agency, Graphical Exposure Modeling System (GEMS) Data Base, compiled from U.S. Bureau of the Census data (1990).

22. Michael Ferrari, Black & Veatch Waste Science, Inc., in memorandum to Treatment Plant/Oil Services Co. File, dated February 13, 1995. Subject: Population within 4 mile radius.
23. Michael Ferrari, Black & Veatch Waste Science, Inc., in memorandum to Treatment Plant/Oil Services Co. File, dated February 10, 1995. Subject: Wetlands within 4 miles of site.

CONFIDENTIAL
Hazard Ranking System Preliminary Score
for
Treatment Plant/Oil Services Company
Columbia, Maury County, Tennessee
EPA ID TND980515779

The preliminary HRS score for the Treatment Plant/Oil Services Co. site was calculated using the SI Worksheets. Pathways evaluated include air migration, soil exposure, surface water migration, and groundwater migration. The score reflects a Hazardous Waste Quantity value of 100 for all pathways, based on the estimated volume of the waste onsite (200,000 gallons). The volume of onsite waste was obtained from an investigation of the site conducted in 1983. Waste characteristic values were derived based on a potential release of contaminants commonly associated with oil sludges and include the following: cadmium, chromium, copper, lead, nickel, silver, zinc, benzene, toluene, xylene, 1,1,1-trichloroethane, trichloroethylene, and PCBs.

Although no environmental samples have been collected from this site, an observed release to groundwater, surface water, and soil, and potential release to air was assumed. This assumed observed release is representative of a "worst case" scenario. The groundwater pathway was scored based on an observed release to the shallow aquifers of the Mississippian limestone of the Central Basin. There is a low number of potential targets obtaining water from this formation. The surface water migration pathway HRS score was based on an observed release to the Duck River, and a potential for contamination to fisheries. The surface water pathway was the primary influence on the site score. The soil exposure pathway HRS score was based on an observed release to soils. The soil exposure pathway score is very low due to the lack of persons on or nearby the site. The air pathway HRS score was based upon a potential to release and a target value derived from potential populations and sensitive environments.

The limited use of groundwater for drinking water and the high dilution weight for the Duck River yields a low site score. Based on the findings of this report, the site score is below the 28.5 scoring threshold; therefore, no further action at this site is recommended.

HRS SCORING SUMMARY

$$S_{gw} = 5.57$$

$$S_{sw} = 43.77$$

$$S_{so} = 0.01$$

$$S_{air} = 6.32$$

$$\text{Overall Score} = 22.29$$

HRS Scoresheets

Site Name: Treatment Plant/Oil Services Company
 Location: Columbia, TN

GROUNDWATER MIGRATION PATHWAY SCORESHEET

<u>Likelihood of Release to an Aquifer</u>	<u>Maximum Value</u>	<u>Assigned Value</u>
1. Observed Release	550	550
2. Potential to Release		
2a. Containment	10	0
2b. Net Precipitation	10	0
2c. Depth to Aquifer	5	0
2d. Travel Time	35	0
2e. Potential to Release	500	0
(lines 2a x (2b+2c+2d))		
3. Likelihood of Release (higher of lines 1 and 2e.)	550	550

Waste Characteristics

4. Toxicity/Mobility	a	10000
5. Hazardous Waste Quantity	a	100
6. Waste Characteristics	100	32

Targets

7. Nearest Well	50	20
8. Population		
8a. Level I Concentrations	b	0
8b. Level II Concentrations	b	0
8c. Potential Contamination	b	6.1
8d. Population (lines 8a+8b+8c)	b	6.1
9. Resources	5	0
10. Wellhead Protection Area	20	0
11. Targets (lines 7+8d+9+10)	b	26.1

Groundwater Migration Score for an Aquifer

12. Aquifer Score [(lines 3 x 6 x 11)/82,500]	100	5.57
--	-----	------

Groundwater Migration Pathway Score

13. Pathway Score (Sgw) - Highest value for all aquifers evaluated	100	5.57
---	-----	------

- a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c Do not round to nearest integer

Site Name: Treatment Plant/Oil Services Company
 Location: Columbia, TN

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORESHEET

DRINKING WATER THREAT

<u>Likelihood of Release</u>	<u>Maximum Value</u>	<u>Assigned Value</u>
1. Observed Release	550	550
2. Potential Release by Overland Flow		
2a. Containment	10	0
2b. Runoff	25	0
2c. Distance to Surface Water	25	0
2d. Potential to Release by Overland Flo lines 2a x (2b + 2c)	500	0
3. Potential to Release by Flood		
3a. Containment	10	0
3b. Flood Frequency	50	0
3c. Potential to Release by Flood (Lines 3a x 3b)	500	0
4. Potential to Release (lines 2d + 3c)	500	0
5. Likelihood of Release (Higher of lines 1 and 4)	550	550

Waste Characteristics

6. Toxicity/Persistence	a	1E+04
7. Hazardous Waste Quantity	a	100
8. Waste Characteristics	100	32

Targets

9. Nearest Intake	50	0
10. Population		
10a. Level I Concentrations	b	0
10b. Level II Concentrations	b	0
10c. Potential Contamination	b	0
10d. Population (lines 10a+10b+10c)	b	0
11. Resources	5	5
12. Targets (lines 9+10d+11)	b	5

Drinking Water Threat Score

13. Drinking Water Threat Score [(lines 5 x 8 x 12)/82500]	100	1.07
---	-----	------

a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c Do not round to nearest integer

Site Name: Treatment Plant/Oil Services Company
 Location: Columbia, TN

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORESHEET
 (continued)

HUMAN FOOD CHAIN THREAT

<u>Likelihood of Release</u>	<u>Maximum Value</u>	<u>Assigned Value</u>
14. Likelihood of Release (Same as line 5)	<u>550</u>	<u>550</u>

Waste Characteristics

15. Toxicity/Persistence/Bioaccumulation	<u>a</u>	<u>5E+08</u>
16. Hazardous Waste Quantity	<u>a</u>	<u>100</u>
17. Waste Characteristics	<u>1000</u>	<u>320</u>

Targets

18. Food Chain Individual	<u>50</u>	<u>0</u>
19. Population		
19a. Level I Concentrations	<u>b</u>	<u>0</u>
19b. Level II Concentrations	<u>b</u>	<u>0</u>
19c. Potential Human Food Chain Contam	<u>b</u>	<u>20</u>
19d. Population (lines 19a+19b+19c)	<u>b</u>	<u>20</u>
20. Targets (lines 18+19d)	<u>b</u>	<u>20</u>

Human Food Chain Threat Score

21. Human Food Chain Threat Score [(lines 14 x 17 x 20)/82500]	<u>100</u>	<u>42.670</u>
---	------------	---------------

a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c Do not round to nearest integer

Site Name: Treatment Plant/Oil Services Company
 Location: Columbia, TN

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORESHEET
 (continued)

ENVIRONMENTAL THREAT

<u>Likelihood of Release</u>	<u>Maximum Value</u>	<u>Assigned Value</u>
22. Likelihood of Release (Same as line 5)	<u>550</u>	<u>550</u>

Waste Characteristics

23. Ecosystem Toxicity/Persistence/Bioaccumulation	<u>a</u>	<u>5E+08</u>
24. Hazardous Waste Quantity	<u>a</u>	<u>100</u>
25. Waste Characteristics	<u>1000</u>	<u>320</u>

Targets

26. Sensitive Environments		
26a. Level I Concentrations	<u>b</u>	<u>0</u>
26b. Level II Concentrations	<u>b</u>	<u>0</u>
26c. Potential Environmental Contamination	<u>b</u>	<u>0.0175</u>
26d. Population (lines 26a+26b+26c)	<u>b</u>	<u>0.0175</u>
27. Targets (value on lines 26d)	<u>b</u>	<u>0.0175</u>

Environmental Threat Score

28. Environmental Threat Score [(lines 22 x 25 x 27)/82500]	<u>60</u>	<u>0.037</u>
--	-----------	--------------

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE - WATERSHED

29. Watershed Score (Lines 13 +21+28)	<u>100</u>	<u>43.77</u>
--	------------	--------------

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE - WATERSHED

30. Watershed Score (Highest of all watersheds)	<u>100</u>	<div style="border: 2px solid black; padding: 2px;"><u>43.77</u></div>
--	------------	--

a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c Do not round to nearest integer

Site Name: Treatment Plant/Oil Services Company
 Location: Columbia, TN

SOIL EXPOSURE PATHWAY SCORESHEET

RESIDENT POPULATION THREAT

<u>Likelihood of Exposure</u>	<u>Maximum Value</u>	<u>Assigned Value</u>
1. Likelihood of Exposure	550	550

Waste Characteristics

2. Toxicity	a	10000
3. Hazardous Waste Quantity	a	100
4. Waste Characteristics	100	32

Targets

5. Resident Individual	50	0
6. Resident Population		
6a. Level I Concentrations	b	0
6b. Level II Concentrations	b	0
6c. Resident Population (lines 6a+6b)	b	0
7. Workers	15	0
8. Resources	5	0
9. Terrestrial Sensitive Environments	c	0
10. Targets (lines 5+6c+7+8+9)	b	0

Resident Population Threat Score

11. Resident Population Threat [(lines 1 x 4 x 10)/82500]	b	0.00
--	---	------

a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c No specific maximum value applies to factor. However, pathway score based solely on sensitive environments is limited to a max of 60.

Site Name: Treatment Plant/Oil Services Company
 Location: Columbia, TN

SOIL EXPOSURE PATHWAY SCORESHEET (continued)

NEARBY POPULATION THREAT

<u>Likelihood of Exposure</u>	<u>Maximum Value</u>	<u>Assigned Value</u>
12. Attractiveness/Accessibility	100	10
13. Area of Contamination	100	40
14. Likelihood of Exposure	500	5

Waste Characteristics

15. Toxicity	a	10000
16. Hazardous Waste Quantity	a	100
17. Waste Characteristics	100	32

Targets

18. Nearby Individual	1	1
19. Population Within One Mile	b	1.8
20. Targets (lines 18+19)	b	2.8

Nearby Population Threat Score

21. Nearby Population Threat [(lines 14 x 47 x 20)/82500]	b	0.01
--	---	------

SOIL EXPOSURE PATHWAY SCORE

22. Soil Exposure Pathway Score (Ss) (Lines 11 + 21)	100	0.01
---	-----	-------------

a Maximum value applies to waste characteristics category

b Maximum value not applicable

c No specific maximum value applies to factor. However, pathway score based solely on sensitive environments is limited to a max of 60.

Site Name: Treatment Plant/Oil Services Company
 Location: Columbia, TN

AIR MIGRATION PATHWAY SCORESHEET

<u>Likelihood of Release</u>	<u>Maximum Value</u>	<u>Assigned Value</u>
1. Observed Release	550	0
2. Potential to Release		
2a. Gas Potential to Release	500	500
2b. Particulate Potential to Release	500	500
2c. Potential to Release (Higher of lines 2a and 2b)	500	500
3. Likelihood of Release (higher of lines 1 and 2c.)	a	500

Waste Characteristics

4. Toxicity/Mobility	a	10000
5. Hazardous Waste Quantity	a	100
6. Waste Characteristics	100	32

Targets

7. Nearest Individual	50	20
8. Population		
8a. Level I Concentrations	b	0
8b. Level II Concentrations	b	0
8c. Potential Contamination	b	10.67
8d. Population (lines 8a+8b+8c)	b	10.67
9. Resources	5	0
10. Sensitive Environments		
10a. Actual Contamination	c	0
10b. Potential Contamination	c	1.897
10c. Sensitive Environments (lines 10a+10b)	c	1.897
11. Targets (lines 7+8d+9+10c)	b	32.567

Air Migration Pathway Score

12. Pathway Score (Sa) [(lines 3 x 6 x 11)/82500]	100	6.32
--	-----	-------------

a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c No specific maximum value applies to factor. However, pathway score based solely on sensitive environments is limited to a max of 60.

HRS Scoresheets

Site Name: Treatment Plant/Oil Services Company
Location: Columbia, TN

SITE SCORING SUMMARY

Groundwater Migration Pathway Score	5.57
Surface Water Migration Pathway Score	43.77
Soil Exposure Migration Pathway Score	0.01
Air Migration Pathway Score	6.32
Overall Site Score	22.29

APPENDIX C

SITE INSPECTION WORKSHEETS

This appendix consists of worksheets that can be used to generate an SI site score. Completion of these worksheets is not required, but the SI investigator must evaluate an SI score, either by these worksheets, *PREscore*, or other Regional scoring tools.

The worksheets consist of instructions and data tables to be filled in with scores from HRS reference tables. The data tables may also call for Data Type and References.

DATA TYPE: The Data Type columns should be filled in with an H, Q, or + if the data are HRS quality and well documented. The Data Type column should be filled in with an E, X, or - if the data represent estimates, approximations, or are not fully documented. This type identifies data gaps for the expanded SI to investigate.

REFERENCES: The Reference columns should be filled in with coded reference numbers. The numbered reference list should be attached or the numbering should be cross-referenced to the SI Narrative Report.

The SI investigator will need the current Superfund Chemical Data Matrix (SCDM) OSWER Directive 9345.1-13 (revised semi-annually) to complete these worksheets.

TABLE 3-1
GROUND WATER MIGRATION PATHWAY SCORESHEET

Factor Categories and Factors

<u>Likelihood of Release to an Aquifer</u>	<u>Maximum Value</u>	<u>Value Assigned</u>
1. Observed Release	550	<u>550</u>
2. Potential to Release		
2a. Containment	10	_____
2b. Net Precipitation	10	_____
2c. Depth to Aquifer	5	_____
2d. Travel Time	35	_____
2e. Potential to Release [lines 2a x (2b + 2c + 2d)]	500	_____
3. Likelihood of Release (higher of lines 1 and 2e)	550	<u>550</u>
<u>Waste Characteristics</u>		
4. Toxicity/Mobility	^a	_____
5. Hazardous Waste Quantity	^a	_____
6. Waste Characteristics	100	_____
<u>Targets</u>		
7. Nearest Well	50	_____
8. Population		
8a. Level I Concentrations	^b	_____
8b. Level II Concentrations	^b	_____
8c. Potential Contamination	^b	_____
8d. Population (lines 8a + 8b + 8c)	^b	_____
9. Resources	5	_____
10. Wellhead Protection Area	20	_____
11. Targets (lines 7 + 8d + 9 + 10)	^b	_____
<u>Ground Water Migration Score for an Aquifer</u>		
12. Aquifer Score [(lines 3 x 6 x 11) / 82,500] ^c	100	_____
<u>Ground Water Migration Pathway Score</u>		
13. Pathway Score (S_{gw}). (highest value from line 12 for all aquifers evaluated) ^c	100	_____

^aMaximum value applies to waste characteristics category.

^bMaximum value not applicable.

^cDo not round to nearest integer.

TABLE 3-2
CONTAINMENT FACTOR VALUES FOR GROUND WATER MIGRATION PATHWAY

<u>All Sources (except surface impoundments, land treatment, containers, and tanks)</u>	<u>Assigned Value</u>
Evidence of hazardous substance migration from source area (i.e., source area includes source and any associated containment structures).	10
No liner.	10
No evidence of hazardous substance migration from source area, a liner, and:	
(a) None of the following present: (1) maintained engineered cover, or (2) functioning and maintained run-on control system and runoff management system, or (3) functioning leachate collection and removal system immediately above liner.	10
(b) Any one of the three items in (a) present.	9
(c) Any two of the items in (a) present.	7
(d) All three items in (a) present plus a functioning ground water monitoring system.	5
(e) All items in (d) present, plus no bulk or non-containerized liquids nor materials containing free liquids deposited in source area.	3
No evidence of hazardous substance migration from source area, double liner with functioning leachate collection and removal system above and between liners, functioning ground water monitoring system, and:	
(f) Only one of the following deficiencies present in containment: (1) bulk or noncontainerized liquids or materials containing free liquids deposited in source area, or (2) no or nonfunctioning or nonmaintained run-on control system and runoff management system, or (3) no or nonmaintained engineered cover.	3

C-15A.1

TABLE 3-2 (Continued)

<u>All Sources (Concluded)</u>	<u>Assigned Value</u>
(g) None of the deficiencies in (f) present.	0
Source area inside or under maintained intact structure that provides protection from precipitation so that neither runoff nor leachate is generated, liquids or materials containing free liquids not deposited in source area, ... and functioning and maintained run-on control present.	0

C-15A.2
2

C-15B




FIGURE 3-2
NET-PRECIPITATION FACTOR VALUES

CONFIDENTIAL

TABLE 3-5
DEPTH TO AQUIFER FACTOR VALUES

<u>Depth To Aquifer¹</u> <u>(feet)</u>	<u>Assigned</u> <u>Value</u>
Less than or equal to 25	5
Greater than 25 to 250	3
Greater than 250	1

¹Use depth of all layers between the hazardous substances and aquifer. Assign a thickness of 0 feet to any karst aquifer that underlies any portion of the sources at the site.

TABLE 3-6
HYDRAULIC CONDUCTIVITY OF GEOLOGIC MATERIALS

Type of Material	Assigned Hydraulic Conductivity ¹ (cm/sec)
Clay; low permeability till (compact unfractured till); shale; unfractured metamorphic and igneous rocks	10 ⁻⁸
Silt; loesses; silty clays; sediments that are predominantly silts; moderately permeable till (fine-grained, unconsolidated till, or compact till with some fractures); low permeability limestones and dolomites (no karst); low permeability sandstone; low permeability fractured igneous and metamorphic rocks	10 ⁻⁶
Sands; sandy silts; sediments that are predominantly sand; highly permeable till (coarse-grained, unconsolidated or compact and highly fractured); peat; moderately permeable limestones and dolomites (no karst); moderately permeable sandstone; moderately permeable fractured igneous and metamorphic rocks	10 ⁻⁴
Gravel; clean sand; highly permeable fractured igneous and metamorphic rocks; permeable basalt; karst limestones and dolomites	10 ⁻²

¹Do not round to nearest integer.

TABLE 3-7
TRAVEL TIME FACTOR VALUES^a

Hydraulic Conductivity (cm/sec)	Thickness of Lowest Hydraulic Conductivity Layer(s) ^b (feet)			
	Greater than 3 to 5	Greater than 5 to 100	Greater than 100 to 500	Greater than 500
Greater than or equal to 10^{-3}	35	35	35	25
Less than 10^{-3} to 10^{-5}	35	25	15	15
Less than 10^{-5} to 10^{-7}	15	15	5	5
Less than 10^{-7}	5	5	1	1

^aIf depth to aquifer is 10 feet or less or if, for the interval being evaluated, all layers that underlie a portion of the sources at the site are karst, assign a value of 35.

^bConsider only layers at least 3 feet thick. Do not consider layers or portions of layers within the first 10 feet of the depth to the aquifer.

TABLE 4-1
SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SUBSHEET

<u>Factor Categories and Factors</u>	<u>Maximum Value</u>	<u>Value Assigned</u>
DRINKING WATER THREAT		
<u>Likelihood of Release</u>		
1. Observed Release	550	<u>550</u>
2. Potential to Release by Overland Flow		
2a. Containment	10	_____ from p. C-23A 1/2
2b. Runoff	25	_____ from p. C-23 E
2c. Distance to Surface Water	25	_____ from p. C-23 F
2d. Potential to Release by Overland Flow (lines 2a x [2b + 2c])	500	_____
3. Potential to Release by Flood		
3a. Containment (Flood)	10	_____ from p. C-23 F 1/2
3b. Flood Frequency	50	_____ from p. C-23 G
3c. Potential to Release by Flood (lines 3a x 3b)	500	_____
4. Potential to Release (lines 2d + 3c, subject to a maximum of 500)	500	_____
5. Likelihood of Release (higher of lines 1 and 4)	550	<u>550</u>
<u>Waste Characteristics</u>		
6. Toxicity/Persistence	a	_____
7. Hazardous Waste Quantity	a	_____
8. Waste Characteristics	100	_____
<u>Targets</u>		
9. Nearest Intake	50	_____
10. Population		
10a. Level I Concentrations	b	_____
10b. Level II Concentrations	b	_____
10c. Potential Contamination	b	_____
10d. Population (lines 10a + 10b + 10c)	b	_____
11. Resources	5	_____

C-23A

Jordan

TABLE 4-2
CONTAINMENT FACTOR VALUES
FOR SURFACE WATER MIGRATION PATHWAY

<u>All Sources</u> (except surface impoundments, land treatment, containers, and tanks)	<u>Assigned Value</u>
Evidence of hazardous substance migration from source area (i.e., source area includes source and any associated containment structures).	10
No evidence of hazardous substance migration from source area <u>and</u> :	
(a) Neither of the following present: (1) maintained engineered cover, or (2) functioning and maintained run-on control system and runoff management system.	10
(b) Any one of the two items in (a) present.	9
(c) Any two of the following present: (1) maintained engineered cover, or (2) functioning and maintained run-on control system and runoff management system, or (3) liner with functioning leachate collection and removal system immediately above liner.	7
(d) All items in (c) present.	5
(e) All items in (c) present, plus no bulk or non-containerized liquids nor materials containing free liquids deposited in source area.	3
No evidence of hazardous substance migration from source area, double liner with functioning leachate collection and removal system above and between liners, <u>and</u> :	
(f) Only one of the following deficiencies present in containment: (1) bulk or noncontainerized liquids or materials containing free liquids deposited in source area, or (2) no or nonfunctioning or nonmaintained run-on control system and runoff management system, or (3) no or nonmaintained engineered cover.	3
(g) None of the deficiencies in (f) present.	0

C-23A 1/2

TABLE 4-3
DRAINAGE AREA VALUES

<u>Drainage Area (acres)</u>	<u>Assigned Value</u>
Less than 50	1
50 to 250	2
Greater than 250 to 1,000	3
Greater than 1,000	4

* drainage area is area that contributes to overland flow across a source based on observing topographic map of the area.

TABLE 4-4
SOIL GROUP DESIGNATIONS

<u>Surface Soil Description</u>	<u>Soil Group Designation</u>
Coarse-textured soils with high infiltration rates (for example, sands, loamy sands)	A
Medium-textured soils with moderate infiltration rates (for example, <u>sandy loams</u> , loams)	B
Moderately fine-textured soils with low infiltration rates (for example, silty loams, silts, sandy clay loams)	C
✓ Fine-textured soils with very low infiltration rates (for example, clays, sandy clays, silty clay loams, clay loams, silty clays); or impermeable surfaces (for example, pavement)	D

get info from
Soil Survey

CONFIDENTIAL

TABLE 4-5
RAINFALL/RUNOFF VALUES

2-Year, 24-Hour Rainfall (inches)	Soil Group Designation			
	A	B	C	D
Less than 1.0	0	0	2	3
1.0 to less than 1.5	0	1	2	3
1.5 to less than 2.0	0	2	3	4
2.0 to less than 2.5	1	2	3	4
2.5 to less than 3.0	2	3	4	4
3.0 to less than 3.5	2	3	4	5
3.5 or greater	3	4	5	6

Rainfall frequency atlas

TABLE 4-6
RUNOFF FACTOR VALUES

Drainage Area Value	Rainfall/Runoff Value						
	0	1	2	3	4	5	6
1	0	0	0	1	1	1	1
2	0	0	1	1	2	3	4
3	0	0	1	3	7	11	15
4	0	1	2	7	17	25	25

TABLE 4-7
DISTANCE TO SURFACE WATER FACTOR VALUES

Distance	Assigned Value
Less than 100 feet	25
100 feet to 500 feet	20
Greater than 500 feet to 1,000 feet	16
Greater than 1,000 feet to 2,500 feet	9
Greater than 2,500 feet to 1.5 miles	6
Greater than 1.5 miles to 2 miles	3

TABLE 4-8
CONTAINMENT (FLOOD) FACTOR VALUES

<u>Containment Criteria</u>	<u>Assigned Value</u>
Documentation that containment at the source is designed, constructed, operated, and maintained to prevent a washout of hazardous substances by the flood being evaluated	0
Other	10

C-23 F 1/2

~~202~~

TABLE 4-9
FLOOD FREQUENCY FACTOR VALUES

<u>Floodplain Category</u>	<u>Assigned Value</u>
Source floods annually	50
Source in 10-year floodplain	50
Source in 100-year floodplain	25
Source in 500-year floodplain	7
None of above	0



BLACK & VEATCH Waste Science, Inc.

400 Northridge Road, Suite 350, Atlanta, Georgia 30350, (404) 594-2500, Fax: (404) 587-2930

US EPA -- Region IV
Site Inspection Prioritization
Work Assignment No. 12

BVWS Project 52012.545
September 20, 1995

Mr. Robert Jourdan
Chief, North Superfund Remedial Branch
U.S. Environmental Protection Agency
345 Courtland Street, NE
Atlanta, Georgia 30365

REC'D
SEP 21 1995
WFO/CLM

Subject: Final Site Inspection Prioritization
Treatment Plant/Oil Services Company
Columbia, Maury County, TN
EPA ID No. TND980515779

Dear Mr. Jourdan:

Enclosed please find three copies of the Final Site Inspection
Prioritization for Treatment Plant/Oil Services Company in Columbia, Maury
County, Tennessee. If you have any questions, please contact me at
404/643-2320.

Very truly yours,

BLACK & VEATCH Waste Science, Inc.

Selicia Williams-Moon for
Victor Blix
Project Manager

fw
Enclosures

cc: Doug Thompson, EPA PO, w/o enclosures
Deborah Davidson, EPA CO, w/o enclosures
Earl Bozeman, EPA WAM, w/o enclosures

APPENDIX C

SITE INSPECTION WORKSHEETS

This appendix consists of worksheets that can be used to generate an SI site score. Completion of these worksheets is not required, but the SI investigator must evaluate an SI score, either by these worksheets, *PREscore*, or other Regional scoring tools.

The worksheets consist of instructions and data tables to be filled in with scores from HRS reference tables. The data tables may also call for Data Type and References.

DATA TYPE: The Data Type columns should be filled in with an H, Q, or + if the data are HRS quality and well documented. The Data Type column should be filled in with an E, X, or - if the data represent estimates, approximations, or are not fully documented. This type identifies data gaps for the expanded SI to investigate.

REFERENCES: The Reference columns should be filled in with coded reference numbers. The numbered reference list should be attached or the numbering should be cross-referenced to the SI Narrative Report.

The SI investigator will need the current Superfund Chemical Data Matrix (SCDM) OSWER Directive 9345.1-13 (revised semi-annually) to complete these worksheets.

- This page intentionally blank -

SITE INSPECTION WORKSHEETS

CERCLIS IDENTIFICATION NUMBER

TND 980515779

SITE LOCATION			
SITE NAME: LEGAL, COMMON, OR DESCRIPTIVE NAME OF SITE <i>TREATMENT PLANT / OIL SERVICES COMPANY</i>			
STREET ADDRESS, ROUTE, OR SPECIFIC LOCATION IDENTIFIER <i>408 SANTA FE PIKE</i>			
CITY <i>COLUMBIA</i>	STATE <i>TN</i>	ZIP CODE <i>38401</i>	TELEPHONE <i>() —</i>
COORDINATES: LATITUDE and LONGITUDE <i>35°37'38"N 87°02'15"W</i>		TOWNSHIP, RANGE, AND SECTION <i>Maury County</i>	

OWNER/OPERATOR IDENTIFICATION					
OWNER <i>No Longer in operation —</i>			OPERATOR <i>—————</i>		
OWNER ADDRESS			OPERATOR ADDRESS		
CITY			CITY		
STATE	ZIP CODE	TELEPHONE ()	STATE	ZIP CODE	TELEPHONE ()

SITE EVALUATION		
AGENCY/ORGANIZATION <i>U.S. EPA</i>		
INVESTIGATOR <i>MICHAEL FERRARI</i>		
CONTACT <i>ROBERT MORRIS</i>		
ADDRESS <i>345 COURTLAND ST. NE</i>		
CITY <i>ATLANTA</i>	STATE <i>GEORGIA</i>	ZIP CODE <i>30365</i>
TELEPHONE <i>(404) 347-5065</i>		

GENERAL INFORMATION

Site Description and Operational History: Provide a brief description of the site and its operational history. State the site name, owner, operator, type of facility and operations, size of property, active or inactive status, and years of waste generation. Summarize waste treatment, storage, or disposal activities that have or may have occurred at the site; note whether these activities are documented or alleged. Identify all source types and prior spills, floods, or fires. Summarize highlights of the PA and other investigations. Cite references.

PLEASE SEE SITE
INSPECTION PRIORITIZATION

GENERAL INFORMATION (continued)

Site Sketch: Provide a sketch of the site. Indicate all pertinent features of the site and nearby environments including sources of wastes, areas of visible and buried wastes, buildings, residences, access roads, parking areas, fences, fields, drainage patterns, water bodies, vegetation, wells, sensitive environments, and other features.

PLEASE SEE SITE

INSPECTION PRIORITIZATION

GENERAL INFORMATION (continued)

Source Descriptions: Describe all sources at the site. Identify source type and relate to waste disposal operations. Provide source dimensions and the best available waste quantity information. Describe the condition of sources and all containment structures. Cite references.

SOURCE TYPES

Landfill: A man-made (by excavation or construction) or natural hole in the ground into which wastes have come to be disposed by backfilling, or by contemporaneous soil deposition with waste disposal.

Surface Impoundment: A natural topographic depression, man-made excavation, or diked area, primarily formed from earthen materials (lined or unlined) and designed to hold an accumulation of liquid wastes, wastes containing free liquids, or sludges not backfilled or otherwise covered; depression may be wet with exposed liquid or dry if deposited liquid has evaporated, volatilized or leached; structures that may be described as lagoon, pond, aeration pit, settling pond, tailings pond, sludge pit; also a surface impoundment that has been covered with soil after the final deposition of waste materials (i.e., buried or backfilled).

Drum: A portable container designed to hold a standard 55-gallon volume of wastes.

Tank and Non-Drum Container: Any device, other than a drum, designed to contain an accumulation of waste that provides structural support and is constructed primarily of fabricated materials (such as wood, concrete, steel, or plastic); any portable or mobile device in which waste is stored or otherwise handled.

Contaminated Soil: An area or volume of soil onto which hazardous substances have been spilled, spread, disposed, or deposited.

Pile: Any non-containerized accumulation above the ground surface of solid, non-flowing wastes; includes open dumps. Some types of waste piles are:

- **Chemical Waste Pile:** A pile consisting primarily of discarded chemical products, by-products, radioactive wastes, or used or unused feedstocks.
- **Scrap Metal or Junk Pile:** A pile consisting primarily of scrap metal or discarded durable goods (such as appliances, automobiles, auto parts, batteries, etc.) composed of materials containing hazardous substances.
- **Tailings Pile:** A pile consisting primarily of any combination of overburden from a mining operation and tailings from a mineral mining, beneficiation, or processing operation.
- **Trash Pile:** A pile consisting primarily of paper, garbage, or discarded non-durable goods containing hazardous substances.

Land Treatment: Landfarming or other method of waste management in which liquid wastes or sludges are spread over land and tilled, or liquids are injected at shallow depths into soils.

Other: Sources not in categories listed above.

GENERAL INFORMATION (continued)

Source Description: Include description of containment per pathway for ground water (see HRS Table 3-2), surface water (see HRS Table 4-2), and air (see HRS Tables 6-3 and 6-9).

PLEASE SEE SITE

INSPECTION PRIORITIZATION

Hazardous Waste Quantity (HWQ) Calculation: SI Tables 1 and 2 (See HRS Tables 2-5, 2-6, and 5-2).

① Tanks and non-drum containers

200,000 gallons

$$200,000 \div 500 = 400$$

Attach additional pages, if necessary

Ref. 2

HWQ =

100

SI TABLE 1: HAZARDOUS WASTE QUANTITY (HWQ) SCORES FOR SINGLE SOURCE SITES AND FORMULAS FOR MULTIPLE SOURCE SITES

		Single Source Sites (assigned HWQ scores)	
(Column 1) TIER	(Column 2) Source Type	(Column 3) HWQ = 10	(Column 4) HWQ = 100
A Hazardous Constituent Quantity	N/A	HWQ = 1 if Hazardous Constituent Quantity data are complete HWQ = 10 if Hazardous Constituent Quantity data are not complete	>100 to 10,000 lbs
B Hazardous Wastestream Quantity	N/A	≤ 500,000 lbs	>500,000 to 50 million lbs
C Volume	Landfill	≤ 6.75 million ft ³ ≤ 250,000 yd ³	>6.75 million to 675 million ft ³ >250,000 to 25 million yd ³
	Surface impoundment	≤ 6,750 ft ³ ≤ 250 yd ³	>6,750 to 675,000 ft ³ >250 to 25,000 yd ³
	Drums	≤ 1,000 drums	>1,000 to 100,000 drums
	Tanks and non-drum containers	≤ 50,000 gallons	>50,000 to 5 million gallons
	Contaminated soil	≤ 6.75 million ft ³ ≤ 250,000 yd ³	>6.75 million to 675 million ft ³ >250,000 to 25 million yd ³
	Pile	≤ 6,750 ft ³ ≤ 250 yd ³	>6,750 to 675,000 ft ³ >250 to 25,000 yd ³
	Other	≤ 6,750 ft ³ ≤ 250 yd ³	>6,750 to 675,000 ft ³ >250 to 25,000 yd ³
D Area	Landfill	≤ 340,000 ft ² ≤ 7.8 acres	>340,000 to 34 million ft ² >7.8 to 780 acres
	Surface impoundment	≤ 1,300 ft ² ≤ 0.029 acres	>1,300 to 130,000 ft ² >0.029 to 2.9 acres
	Contaminated soil	≤ 3.4 million ft ² ≤ 78 acres	> 3.4 million to 340 million ft ² > 78 to 7,800 acres
	Pile	≤ 1,300 ft ² ≤ 0.029 acres	>1,300 to 130,000 ft ² >0.029 to 2.9 acres
	Land treatment	≤ 27,000 ft ² ≤ 0.62 acres	>27,000 to 2.7 million ft ² >0.62 to 62 acres

TABLE 1 (CONTINUED)

Single Source Sites (assigned HWQ scores)		Multiple Source Sites		
(Column 5) HWQ = 10,000	(Column 6) HWQ = 1,000,000	(Column 7) Divisors for Assigning Source WQ Values	(Column 2) Source Type	(Column 1) TIER
>10,000 to 1 million lbs	> 1 million lbs	lbs / 1	N/A	A Hazardous Constituent Quantity
>50 million to 5 billion lbs	> 5 billion lbs	lbs / 5,000	N/A	B Hazardous Wastestream Quantity
>675 million to 67.5 billion ft ³ >25 million to 2.5 billion yd ³	> 67.5 billion ft ³ > 2.5 billion yd ³	ft ³ / 67,500 yd ³ / 2,500	Landfill	C Volume
>675,000 to 67.5 million ft ³ >25,000 to 2.5 million yd ³	> 67.5 million ft ³ > 2.5 million yd ³	ft ³ / 67.5 yd ³ / 2.5	Surface Impoundment	
>100,000 to 10 million drums	> 10 million drums	drums / 10	Drums	
>5 million to 500 million gallons	> 500 million gallons	gallons / 500	Tanks and non-drum containers	
>675 million to 67.5 billion ft ³ >25 million to 2.5 billion yd ³	> 67.5 billion ft ³ > 2.5 billion yd ³	ft ³ / 67,500 yd ³ / 2,500	Contaminated Soil	
>675,000 to 67.5 million ft ³ >25,000 to 2.5 million yd ³	> 67.5 million ft ³ > 2.5 million yd ³	ft ³ / 67.5 yd ³ / 2.5	Pile	
>675,000 to 67.5 million ft ³ >25,000 to 2.5 million yd ³	> 67.5 million ft ³ > 2.5 million yd ³	ft ³ / 67.5 yd ³ / 2.5	Other	
>34 million to 3.4 billion ft ² >780 to 78,000 acres	> 3.4 billion ft ² >78,000 acres	ft ² / 3,400 acres / 0.078	Landfill	D Area
>130,000 to 13 million ft ² >2.9 to 290 acres	> 13 million ft ² > 290 acres	ft ² / 13 acres / 0.00029	Surface Impoundment	
> 340 million to 34 billion ft ² > 7,800 to 780,000 acres	> 34 billion ft ² > 780,000 acres	ft ² / 34,000 acres / 0.78	Contaminated Soil	
> 130,000 to 13 million ft ² > 2.9 to 290 acres	> 13 million ft ² > 290 acres	ft ² / 13 acres / 0.00029	Pile	
>2.7 million to 270 million ft ² >62 to 6,200 acres	> 270 million ft ² > 6,200 acres	ft ² / 270 acres / 0.0062	Land Treatment	

HAZARDOUS WASTE QUANTITY (HWQ) CALCULATION

For each migration pathway, evaluate HWQ associated with sources that are available (i.e., incompletely contained) to migrate to that pathway. (Note: If *Actual Contamination Targets* exist for ground water, surface water, or air migration pathways, assign the calculated HWQ score or 100, whichever is greater, as the HWQ score for that pathway.) For each source, evaluate HWQ for one or more of the four tiers (SI Table 1; HRS Table 2-5) for which data exist: constituent quantity, wastestream quantity, source volume, and source area. Select the tier that gives the highest value as the source HWQ. Select the source volume HWQ rather than source area HWQ if data for both tiers are available.

Column 1 of SI Table 1 indicates the quantity tier. Column 2 lists source types for the four tiers. Columns 3, 4, 5, and 6 provide ranges of waste amount for sites with only one source, corresponding to HWQ scores at the tops of the columns. Column 7 provides formulas to obtain source waste quantity values at sites with multiple sources.

1. Identify each source type.
2. Examine all waste quantity data available for each source. Record constituent quantity and waste stream mass or volume. Record dimensions of each source.
3. Convert source measurements to appropriate units for each tier to be evaluated.
4. For each source, use the formulas in the last column of SI Table 1 to determine the waste quantity value for each tier that can be evaluated. Use the waste quantity value obtained from the highest tier as the quantity value for the source.
5. Sum the values assigned to each source to determine the total site waste quantity.
6. Assign HWQ score from SI Table 2 (HRS Table 2-6).

Note these exceptions to evaluate soil exposure pathway HWQ (see HRS Table 5-2):

- The divisor for the area (square feet) of a landfill is 34,000.
- The divisor for the area (square feet) of a pile is 34.
- Wet surface impoundments and tanks and non-drum containers are the only sources for which volume measurements are evaluated for the soil exposure pathway.

SI TABLE 2: HWQ SCORES FOR SITES

Site WQ Total	HWQ Score
0	0
1 ^a to 100	1 ^b
> 100 to 10,000	100
> 10,000 to 1 million	10,000
> 1 million	1,000,000

^a If the WQ total is between 0 and 1, round it to 1.

^b If the hazardous constituent quantity data are not complete, assign the score of 10.

SI TABLE 3: WASTE CHARACTERIZATION WORKSHEET

Site Name: Treatment Plant / Oil Spill Co.

References: 2; 3; 6; 8; 10

Sources:

1. TANKS & NON-DRUM CONTAINERS
2. _____
3. _____
4. _____
5. _____
6. _____
7. _____
8. _____
9. _____

C-11

SOURCE	HAZARDOUS SUBSTANCE	TOXICITY	GROUND WATER PATHWAY	SURFACE WATER PATHWAY												AIR	
				OVERLAND/FLOOD MIGRATION								GROUND WATER TO SURFACE WATER					
				GW Mobility (HRS Table 3-8)	Tox/Mobility Value (HRS Table 3-9)	Per (HRS Tables 4-10 and 4-11)	Tox/Per Value (HRS Table 4-12)	EC ₅₀ Bioacc Pot (HRS Table 4-15)	Tox/Per/Bioacc Value (HRS Table 4-16)	Ecotox (HRS Table 4-19)	Ecotox/Per (HRS Table 4-20)	Env. Ecotox/Per/Bioacc Value (HRS Table 4-21)	Tox/Mob/Per Value (HRS Table 4-26)	Tox/Mob/Per/Bioacc Value (HRS Table 4-28)	Ecotox/Mob/Per Value (HRS Table 4-29)		Ecotox/Mob/Per/Bioacc Value (HRS Table 4-30)
1	Cadmium	10,000	1	10,000	1	10,000	5,000	5x10 ⁷	1,000	1,000	5x10 ⁶						20
1	Chromium	10,000	1	10,000	1	10,000	5	50,000	10,000	10,000	50,000						2
1	Copper	No Toxicity Value	1	No Toxicity Value	1	No Toxicity Value	50,000	No Toxicity Value	100	100	5x10 ⁶						No Tox. Value
1	Lead	10,000	1	10,000	1	10,000	50	500,000	1,000	1,000	5x10 ⁶						2
1	Nickel	10,000	1	10,000	1	10,000	0.5	5,000	10	10	5,000						2
1	Silver	100	1	100	1	100	50	5,000	10,000	10,000	5x10 ⁵						100
1	Zinc	10	1	10	1	10	500	5,000	10	10	5,000						100
1	Benzene	100	1	100	0.4	40	5,000	2x10 ⁵	10,000	4,000	2x10 ⁶						100
1	Toluene	10	1	10	0.4	4	50	200	100	40	2,000						10
1	Xylene	1	1	1	0.4	0.4	500	200	100	40	20,000						1
1	Trichloroethylene	10	1	10	0.4	4	5	20	10	4	20						10
1	Trichloroethylene	10	1	10	0.4	4	50	200	100	40	2,000						10
1	PCBs	10,000	1	10,000	1	10,000	50,000	5x10 ⁸	10,000	10,000	5x10 ⁸						10,000
Highest	Value	10,000	1	10,000	1	10,000	50,000	5x10 ⁸	10,000	10,000	5x10 ⁸						10,000

Ground Water Observed Release Substances Summary Table

On SI Table 4, list the hazardous substances associated with the site detected in ground water samples for that aquifer. Include only those substances directly observed or with concentrations significantly greater than background levels. Obtain toxicity values from the Superfund Chemical Data Matrix (SCDM). Assign mobility a value of 1 for all observed release substances regardless of the aquifer being evaluated. For each substance, multiply the toxicity by the mobility to obtain the toxicity/mobility factor value; enter the highest toxicity/mobility value for the aquifer in the space provided.

Ground Water Actual Contamination Targets Summary Table

If there is an observed release at a drinking water well, enter each hazardous substance meeting the requirements for an observed release by well and sample ID on SI Table 5 and record the detected concentration. Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For MCL and MCLG benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate the population using the well as a Level I target. If these percentages are less than 100% or all are N/A, evaluate the population using the well as a Level II target for that aquifer.

No. 4410. *Stenobothrus*
Crematogaster.

[illegible]

Well ID: _____ Level I _____ Level II _____ Population Served _____ References _____

C-13

Well ID: _____ Level I _____ Level II _____ Population Served _____ References _____

Sample ID	Hazardous Substance	Conc. (µg/L)	Benchmark Conc. (MCL or MCLG)	% of Benchmark	Cancer Risk Conc.	% of Cancer Risk Conc.	RID	% of RID
Highest Percent					Sum of Percents		Sum of Percents	

GROUND WATER PATHWAY GROUND WATER USE DESCRIPTION

Describe Ground Water Use within 4 Miles of the Site:
Describe generalized stratigraphy, aquifers, municipal and private wells

Please see Site

Inspection Prioritization

Show Calculations of Ground Water Drinking Water Populations for each Aquifer:
Provide apportionment calculations for blended supply systems.
County average number of persons per household: 2.62 Reference 16

0 - $\frac{1}{4}$ mile 0

$\frac{1}{4}$ - $\frac{1}{2}$ mile 0

$\frac{1}{2}$ - 1 mile 0

1 - 2 miles 21

2 - 3 miles 34

3 - 4 miles 73

Total 128 people

Refs. 1, 16, 17

GROUND WATER PATHWAY WORKSHEET

LIKELIHOOD OF RELEASE

Score

Data Type Refs

1. OBSERVED RELEASE: If sampling data or direct observation support a release to the aquifer, assign a score of 550. Record observed release substances on SI Table 4.	550		
2. POTENTIAL TO RELEASE: Depth to aquifer: <u>200</u> feet. If sampling data do not support a release to the aquifer, and the site is in karst terrain or the depth to aquifer is 70 feet or less, assign a score of 500; otherwise, assign a score of 340. Optionally, evaluate potential to release according to HRS Section 3.			

LR = 550

TARGETS

Are any wells part of a blended system? Yes <u> </u> No <u>X</u> If yes, attach a page to show apportionment calculations.			
3. ACTUAL CONTAMINATION TARGETS: If analytical evidence indicates that any target drinking water well for the aquifer has been exposed to a hazardous substance from the site, evaluate the factor score for the number of people served (SI Table 5). Level I: <u>NONE</u> people x 10 = <u> </u> Level II: <u>NONE</u> people x 1 = <u> </u> Total = <u> </u>	0		
4. POTENTIAL CONTAMINATION TARGETS: Determine the number of people served by drinking water wells for the aquifer or overlying aquifers that are not exposed to a hazardous substance from the site; record the population for each distance category in SI Table 6a or 6b. Sum the population values and multiply by 0.1.	6.1		1,16; 17
5. NEAREST WELL: Assign a score of 50 for any Level I Actual Contamination Targets for the aquifer or overlying aquifer. Assign a score of 45 if there are Level II targets but no Level I targets. If no Actual Contamination Targets exist, assign the Nearest Well score from SI Table 6a or 6b. If no drinking water wells exist within 4 miles, assign 0.	20		3
6. WELLHEAD PROTECTION AREA (WHPA): If any source lies within or above a WHPA for the aquifer, or if a ground water observed release has occurred within a WHPA, assign a score of 20; assign 5 if neither condition applies but a WHPA is within 4 miles; otherwise assign 0.	0		
7. RESOURCES: Assign a score of 5 if one or more ground water resource applies; assign 0 if none applies. <ul style="list-style-type: none"> Irrigation (5 acre minimum) of commercial food crops or commercial forage crops Watering of commercial livestock Ingredient in commercial food preparation Supply for commercial aquaculture Supply for a major or designated water recreation area, excluding drinking water use 	0		1

Sum of Targets T = 26.1

CONTAINMENT: ^{HRS} TABLE 3-2	A	
NET PRECIPITATION: ^{HRS} TABLE 3-4	B	
DEPTH TO AQUIFER: ^{HRS} TABLE 3-5	C	
* TRAVEL TIME: ^{HRS} TABLE 3-7	D	

$$A * (B + C + D) = LR$$

C-15

* IF depth to aquifer is 10 feet or less assign a value of 35.

SI TABLE 6 (From HRS TABLE 3-12): VALUES FOR POTENTIAL CONTAMINATION GROUND WATER TARGET POPULATIONS

SI Table 6a: Other Than Karst Aquifers

Distance from Site	Pop.	Nearest Well (choose highest)	Population Served by Wells within Distance Category												Pop. Value	Ref.
			1 to 10	11 to 30	31 to 100	101 to 300	301 to 1000	1001 to 3000	3001 to 10,000	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	1,000,000 to 3,000,000		
0 to $\frac{1}{4}$ mile		20	4	17	53	164	522	1,633	5,214	16,325	52,137	163,246	521,360	1,632,455		
$> \frac{1}{4}$ to $\frac{1}{2}$ mile		18	2	11	33	102	324	1,013	3,233	10,122	32,325	101,213	323,243	1,012,122		
$> \frac{1}{2}$ to 1 mile		9	1	5	17	52	167	523	1,669	5,224	16,684	52,239	166,835	522,385		
> 1 to 2 miles		5	0.7	3	10	30	94	294	939	2,939	9,385	29,384	93,845	293,842		
> 2 to 3 miles		3	0.5	2	7	21	68	212	678	2,122	6,778	21,222	67,777	212,219		
> 3 to 4 miles		2	0.3	1	4	13	42	131	417	1,306	4,171	13,060	41,709	130,596		

Nearest Well =

Sum =

Karst Aquifers Present

Not Applicable

C-16

SI TABLE 6 (From HRS TABLE 3-12): VALUES FOR POTENTIAL CONTAMINATION GROUND WATER TARGET POPULATIONS (continued)

SI Table 6b: Karst Aquifers

Distance from Site	Pop.	Nearest Well (choose highest)	Population Served by Wells within Distance Category												Pop. Value	Rel.
			1 to 10	11 to 30	31 to 100	101 to 300	301 to 1000	1001 to 3000	3001 to 10,000	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	1,000,000 to 3,000,000		
0 to $\frac{1}{4}$ mile	0	20	4	17	53	164	522	1,633	5,214	16,325	52,137	163,246	521,360	1,632,455	0	1; 16 17
$> \frac{1}{4}$ to $\frac{1}{2}$ mile	0	20	2	11	33	102	324	1,013	3,233	10,122	32,325	101,213	323,243	1,012,122	0	
$> \frac{1}{2}$ to 1 mile	0	20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227	0	
> 1 to 2 miles	21	20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227	9	
> 2 to 3 miles	34	20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227	26	
> 3 to 4 miles	73	20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227	26	
Nearest Well =		20													Sum =	
															61	

C-17

GROUND WATER PATHWAY WORKSHEET (concluded)

WASTE CHARACTERISTICS	Score	Data Type	Does not Apply																						
8. If any Actual Contamination Targets exist for the aquifer or overlying aquifers, assign the calculated hazardous waste quantity score or a score of 100, whichever is greater; if no Actual Contamination Targets exist, assign the hazardous waste quantity score calculated for sources available to migrate to ground water.	100																								
9. Assign the highest ground water toxicity/mobility value from SI Table 3 or 4.	10,000																								
10. Multiply the ground water toxicity/mobility and hazardous waste quantity scores. Assign the Waste Characteristics score from the table below: (from HRS Table 2-7)																									
<table border="1"> <thead> <tr> <th>Product</th> <th>WC Score</th> </tr> </thead> <tbody> <tr><td>0</td><td>0</td></tr> <tr><td>>0 to <10</td><td>1</td></tr> <tr><td>10 to <100</td><td>2</td></tr> <tr><td>100 to <1,000</td><td>3</td></tr> <tr><td>1,000 to <10,000</td><td>6</td></tr> <tr><td>10,000 to <1E + 05</td><td>10</td></tr> <tr><td>1E + 05 to <1E + 06</td><td>18</td></tr> <tr><td>1E + 06 to <1E + 07</td><td>32</td></tr> <tr><td>1E + 07 to <1E + 08</td><td>56</td></tr> <tr><td>1E + 08 or greater</td><td>100</td></tr> </tbody> </table>				Product	WC Score	0	0	>0 to <10	1	10 to <100	2	100 to <1,000	3	1,000 to <10,000	6	10,000 to <1E + 05	10	1E + 05 to <1E + 06	18	1E + 06 to <1E + 07	32	1E + 07 to <1E + 08	56	1E + 08 or greater	100
Product	WC Score																								
0	0																								
>0 to <10	1																								
10 to <100	2																								
100 to <1,000	3																								
1,000 to <10,000	6																								
10,000 to <1E + 05	10																								
1E + 05 to <1E + 06	18																								
1E + 06 to <1E + 07	32																								
1E + 07 to <1E + 08	56																								
1E + 08 or greater	100																								
WC =		32																							

Multiply LR by T and by WC. Divide the product by 82,500 to obtain the ground water pathway score for each aquifer. Select the highest aquifer score. If the pathway score is greater than 100, assign 100.

GROUND WATER PATHWAY SCORE:

$$\frac{LR \times T \times WC}{82,500}$$

5.57

(Maximum of 100)

$$\frac{550 \times 26.1 \times 32}{82,500} = 5.568$$

SURFACE WATER PATHWAY

Sketch of the Surface Water Migration Route:

Label all surface water bodies. Include runoff route and drainage direction, probable point of entry, and 15-mile target distance limit. Mark sample locations, intakes, fisheries, and sensitive environments. Indicate flow directions, tidal influence, and rate.

Please See Site

Inspection

Prioritization

SURFACE WATER PATHWAY

Surface Water Observed Release Substances Summary Table

On SI Table 7, list the hazardous substances detected in surface water samples for the watershed, which can be attributed to the site. Include only those substances in observed releases (direct observation) or with concentration levels significantly above background levels. Obtain toxicity, persistence, bioaccumulation potential, and ecotoxicity values from SCDM. Enter the highest toxicity/persistence, toxicity/persistence/bioaccumulation, and ecotoxicity/persistence/ecobioaccumulation values in the spaces provided.

- TP = Toxicity x Persistence
- TPB = TP x bioaccumulation
- ETPB = EP x bioaccumulation (EP = ecotoxicity x persistence)

Drinking Water Actual Contamination Targets Summary Table

For an observed release at or beyond a drinking water intake, on SI Table 8 enter each hazardous substance by sample ID and the detected concentration. For surface water sediment samples detecting a hazardous substance at or beyond an intake, evaluate the intake as Level II contamination. Obtain benchmark, cancer risk, and reference dose concentrations for each substance from SCDM. For MCL and MCLG benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages of the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate the population served by the intake as a Level I target. If the percentages are less than 100% or all are N/A, evaluate the population served by the intake as a Level II target.

No observed Effects:

Surgeon Major

[illegible]

Intake ID: _____	Sample Type _____	Level I _____	Level II _____	Population Served _____	References _____
------------------	-------------------	---------------	----------------	-------------------------	------------------

C-21

Intake ID: _____ Sample Type _____ Level I _____ Level II _____ Population Served _____ References _____

Sample ID	Hazardous Substance	Conc. (µg/L)	Benchmark Conc. (MCL or MCLG)	% of Benchmark	Cancer Risk Conc.	% of Cancer Risk Conc.	RID	% of RID
			Highest Percent		Sum of Percents		Sum of Percents	

- This page intentionally blank -

SURFACE WATER PATHWAY LIKELIHOOD OF RELEASE AND DRINKING WATER THREAT WORKSHEET

LIKELIHOOD OF RELEASE- OVERLAND/FLOOD MIGRATION

	Score	Data Type	Refs												
1. OBSERVED RELEASE: If sampling data or direct observation support a release to surface water in the watershed, assign a score of 550. Record observed release substances on SI Table 7.	550														
2. POTENTIAL TO RELEASE: Distance to surface water: <u>600</u> (feet) If sampling data do not support a release to surface water in the watershed, use the table below to assign a score from the table below based on distance to surface water and flood frequency.															
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr><td>Distance to surface water <2500 feet</td><td style="text-align: center;">500</td></tr> <tr><td>Distance to surface water >2500 feet, and:</td><td></td></tr> <tr><td> Site in annual or 10-yr floodplain</td><td style="text-align: center;">500</td></tr> <tr><td> Site in 100-yr floodplain</td><td style="text-align: center;">400</td></tr> <tr><td> Site in 500-yr floodplain</td><td style="text-align: center;">300</td></tr> <tr><td> Site outside 500-yr floodplain</td><td style="text-align: center;">100</td></tr> </table>	Distance to surface water <2500 feet	500	Distance to surface water >2500 feet, and:		Site in annual or 10-yr floodplain	500	Site in 100-yr floodplain	400	Site in 500-yr floodplain	300	Site outside 500-yr floodplain	100			1; 13; 14; 19
Distance to surface water <2500 feet	500														
Distance to surface water >2500 feet, and:															
Site in annual or 10-yr floodplain	500														
Site in 100-yr floodplain	400														
Site in 500-yr floodplain	300														
Site outside 500-yr floodplain	100														
Optionally, evaluate surface water potential to release according to HRS Section 4.1.2.1.2															
LR =	550														

LIKELIHOOD OF RELEASE GROUND WATER TO SURFACE WATER MIGRATION

	Score	Data Type	Refs
1. OBSERVED RELEASE: If sampling data or direct observation support a release to surface water in the watershed, assign a score of 550. Record observed release substances on SI Table 7.			
NOTE: Evaluate ground water to surface water migration only for a surface water body that meets all of the following conditions:			
1) A portion of the surface water is within 1 mile of site sources having a containment factor greater than 0.			
2) No aquifer discontinuity is established between the source and the above portion of the surface water body.			
3) The top of the uppermost aquifer is at or above the bottom of the surface water.			
Elevation of top of uppermost aquifer _____			
Elevation of bottom of surface water body _____			
2. POTENTIAL TO RELEASE: Use the ground water potential to release. Optionally, evaluate surface water potential to release according to HRS Section 3.1.2.			

- OVERLAND FLOW -

LR =

A	CONTAINMENT (OVERLAND): HRS TABLE 4-1	
3	RUNOFF HRS TABLE 4-6	C
	DRAINAGE AREA: HRS TABLE 4-3	
	SOIL GROUP: HRS TABLE 4-4	
	RAINFALL/RUNOFF: HRS TABLE 4-5	
	DIST. TO SURFACE WATER: HRS TABLE 4-7	

D	CONTAINMENT (FLOOD): HRS TABLE 4-8	
E	FLOOD FREQ.: HRS TABLE 4-9	

$$[A * (B + C)] + [D * E] = LR \text{ (maximum of 500)}$$

**SURFACE WATER PATHWAY
LIKELIHOOD OF RELEASE AND DRINKING WATER THREAT WORKSHEET
(CONTINUED)**

DRINKING WATER THREAT TARGETS	Score	Data Type	Refs																
<p>Record the water body type, flow, and number of people served by each drinking water intake within the target distance limit in the watershed. If there is no drinking water intake within the target distance limit, assign 0 to factors 3, 4, and 5.</p> <table border="1" style="width: 100%; border-collapse: collapse; margin: 10px 0;"> <thead> <tr> <th style="text-align: left;">Intake Name</th> <th style="text-align: left;">Water Body Type</th> <th style="text-align: left;">Flow</th> <th style="text-align: left;">People Served</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table> <p>Are any intakes part of a blended system? Yes _____ No _____ If yes, attach a page to show apportionment calculations.</p> <p>3. ACTUAL CONTAMINATION TARGETS: If analytical evidence indicates a drinking water intake has been exposed to a hazardous substance from the site, list the intake name and evaluate the factor score for the drinking water population (SI Table 8).</p> <p>_____</p> <p>Level I: <u>None</u> people x 10 = _____ Level II: <u>None</u> people x 1 = _____ Total = _____</p>	Intake Name	Water Body Type	Flow	People Served													0		1; 12; 17; 18; 19
Intake Name	Water Body Type	Flow	People Served																
<p>4. POTENTIAL CONTAMINATION TARGETS: Determine the number of people served by drinking water intakes for the watershed that have not been exposed to a hazardous substance from the site. Assign the population values from SI Table 9. Sum the values and multiply by 0.1.</p>	0		1; 12																
<p>5. NEAREST INTAKE: Assign a score of 50 for any Level I Actual Contamination Drinking Water Targets for the watershed. Assign a score of 45 if there are Level II targets for the watershed, but no Level I targets. If no Actual Contamination Drinking Water Targets exist, assign a score for the intake nearest the PPE from SI Table 9. If no drinking water intakes exist, assign 0.</p>	0																		
<p>6. RESOURCES: Assign a score of 5 if one or more surface water resource applies; assign 0 if none applies.</p> <ul style="list-style-type: none"> • Irrigation (5 acre minimum) of commercial food crops or commercial forage crops • Watering of commercial livestock • Ingredient in commercial food preparation • Major or designated water recreation area, excluding drinking water use 	5		12																
SUM OF TARGETS T=	5																		

SI TABLE 9 (From HRS Table 4-14): DILUTION-WEIGHTED POPULATION VALUES FOR POTENTIAL CONTAMINATION FOR SURFACE WATER MIGRATION PATHWAY

Type of Surface Water Body	Pop.	Nearest Intake	Number of people									Pop. Value
			0	1 to 10	11 to 30	31 to 100	101 to 300	301 to 1,000	1,001 to 3,000	3,001 to 10,000	10,001 to 30,000	
Minimal Stream (<10 cfs)		20	0	4	17	53	164	522	1,633	5,214	16,325	
Small to moderate stream (10 to 100 cfs)		2	0	0.4	2	5	16	52	163	521	1,633	
Moderate to large stream (> 100 to 1,000 cfs)		0	0	0.04	0.2	0.5	2	5	16	52	163	
Large Stream to river (>1,000 to 10,000 cfs)		0	0	0.004	0.02	0.05	0.2	0.5	2	5	16	
Large River (> 10,000 to 100,000 cfs)		0	0	0	0.002	0.005	0.02	0.05	0.2	0.5	16	
Very Large River (>100,000 cfs)		0	0	0	0	0.001	0.002	0.005	0.02	0.05	0.2	
Shallow ocean zone or Great Lake (depth < 20 feet)		0	0	0	0.002	0.005	0.02	0.05	0.2	0.5	2	
Moderate ocean zone or Great Lake (Depth 20 to 200 feet)		0	0	0	0	0.001	0.002	0.005	0.02	0.05	0.2	
Deep ocean zone or Great Lake (depth > 200 feet)		0	0	0	0	0	0.001	0.003	0.008	0.03	0.08	
3-mile mixing zone in quiet flowing river (≥ 10 cfs)		10	0	2	9	26	82	261	817	2,607	8,163	
Nearest Intake =			Sum =									

References _____

C-25

Not Applicable
- SW intake located
downstream from site
on S. 1/12

SURFACE WATER PATHWAY

Human Food Chain Actual Contamination Targets Summary Table

On SI Table 10, list the hazardous substances detected in sediment, aqueous, sessile benthic organism tissue, or fish tissue samples (taken from fish caught within the boundaries of the observed release) by sample ID and concentration. Evaluate fisheries within the boundaries of observed releases detected by sediment or aqueous samples as Level II, if at least one observed release substance has a bioaccumulation potential factor value of 500 or greater (see SI Table 7). Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For FDAAL benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate this portion of the fishery as subject to Level I concentrations. If the percentages are less than 100% or all are N/A, evaluate the fishery as a Level II target.

Sensitive Environment Actual Contamination Targets Summary Table

On SI Table 11, list each hazardous substance detected in aqueous or sediment samples at or beyond wetlands or a surface water sensitive environment by sample ID. Record the concentration. If contaminated sediments or tissues are detected at or beyond a sensitive environment, evaluate the sensitive environment as Level II. Obtain benchmark concentrations from SCDM. For AWQC/AALAC benchmarks, determine the highest percentage of benchmark of the substances detected in aqueous samples. If benchmark concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage equals or exceeds 100%, evaluate that part of the sensitive environment subject to Level I concentrations. If the percentage is less than 100%, or all are N/A, evaluate the sensitive environment as Level II.

SI TABLE 10: HUMAN FOOD CHAIN ACTUAL CONTAMINATION TARGETS FOR WATERSHED

Fishery ID: _____ Sample Type _____ Level I _____ Level II _____ References _____

Sample ID	Hazardous Substance	Conc. (mg/kg)	Benchmark Concentration (FDAAL)	% of Benchmark	Cancer Risk Concentration.	% of Cancer Risk Concentration	RID	% of RID
			Highest Percent		Sum of Percents		Sum of Percents	

SI TABLE 11: SENSITIVE ENVIRONMENT ACTUAL CONTAMINATION TARGETS FOR WATERSHED

Environment ID: _____ Sample Type _____ Level I _____ Level II _____ Environment Value _____

Sample ID	Hazardous Substance	Conc.. (µg/L)	Benchmark Concentration (AWQC or AALAC)	% of Benchmark	References
			Highest Percent		

Environment ID: _____ Sample Type _____ Level I _____ Level II _____ Environment Value _____

Sample ID	Hazardous Substance	Conc.. (µg/L)	Benchmark Concentration (AWQC or AALAC)	% of Benchmark	References
			Highest Percent		

Not Applicable

C-27

SURFACE WATER PATHWAY (continued) HUMAN FOOD CHAIN THREAT WORKSHEET

HUMAN FOOD CHAIN THREAT TARGETS	Score	Data Type	Refs										
<p>Record the water body type and flow for each fishery within the target distance limit. If there is no fishery within the target distance limit, assign a score of 0 at the bottom of this page.</p> <div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> Fishery Name <u>Duck Creek</u> Water Body <u>Lake Erie</u> Flow <u>2,094</u> cfs Species _____ Production _____ lbs/yr Species _____ Production _____ lbs/yr </div> <div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> Fishery Name _____ Water Body _____ Flow _____ cfs Species _____ Production _____ lbs/yr Species _____ Production _____ lbs/yr </div> <div style="border: 1px solid black; padding: 5px;"> Fishery Name _____ Water Body _____ Flow _____ cfs Species _____ Production _____ lbs/yr Species _____ Production _____ lbs/yr </div>	0		19										
<p>FOOD CHAIN INDIVIDUAL</p> <p>7. ACTUAL CONTAMINATION FISHERIES:</p> <p>If analytical evidence indicates that a fishery has been exposed to a hazardous substance with a bioaccumulation factor greater than or equal to 500 (SI Table 10), assign a score of 50 if there is a Level I fishery. Assign 45 if there is a Level II fishery, but no Level I fishery.</p> <p>8. POTENTIAL CONTAMINATION FISHERIES:</p> <p>If there is a release of a substance with a bioaccumulation factor greater than or equal to 500 to a watershed containing fisheries within the target distance limit, but there are no Level I or Level II fisheries, assign a score of 20.</p> <p>If there is no observed release to the watershed, assign a value for potential contamination fisheries from the table below using the lowest flow at all fisheries within the target distance limit:</p> <table border="1" style="width: 100%; border-collapse: collapse; margin-top: 10px;"> <thead> <tr> <th style="width: 50%;">Lowest Flow</th> <th style="width: 50%;">FCI Value</th> </tr> </thead> <tbody> <tr> <td><10 cfs</td> <td style="text-align: center;">20</td> </tr> <tr> <td>10 to 100 cfs</td> <td style="text-align: center;">2</td> </tr> <tr> <td>>100 cfs, coastal tidal waters, oceans, or Great Lakes</td> <td style="text-align: center;">0</td> </tr> <tr> <td>3-mile mixing zone in quiet flowing river</td> <td style="text-align: center;">10</td> </tr> </tbody> </table> <p style="text-align: right; margin-top: 10px;">FCI Value =</p>	Lowest Flow	FCI Value	<10 cfs	20	10 to 100 cfs	2	>100 cfs, coastal tidal waters, oceans, or Great Lakes	0	3-mile mixing zone in quiet flowing river	10	20		
Lowest Flow	FCI Value												
<10 cfs	20												
10 to 100 cfs	2												
>100 cfs, coastal tidal waters, oceans, or Great Lakes	0												
3-mile mixing zone in quiet flowing river	10												
SUM OF TARGETS T =	20												

SURFACE WATER PATHWAY (continued) ENVIRONMENTAL THREAT WORKSHEET

When measuring length of wetlands that are located on both sides of a surface water body, sum both frontage lengths. For a sensitive environment that is more than one type, assign a value for each type.

ENVIRONMENTAL THREAT TARGETS

Score Data Type Refs

Record the water body type and flow for each surface water sensitive environment within the target distance (see SI Table 12). If there is no sensitive environment within the target distance limit, assign a score of 0 at the bottom of the page.

Environment Name	Water Body Type	Fbw
Wetlands	Large River	2,094 cfs
		cfs
		cfs
		cfs
		cfs

18;
19

9. ACTUAL CONTAMINATION SENSITIVE ENVIRONMENTS: If sampling data or direct observation indicate any sensitive environment has been exposed to a hazardous substance from the site, record this information on SI Table 11, and assign a factor value for the environment (SI Tables 13 and 14).

Environment Name	Environment Type and Value (SI Tables 13 & 14)	Multiplier (10 for Level I, 1 for Level II)	Product
		x	=
		x	=
		x	=
		x	=

Sum =

0

10. POTENTIAL CONTAMINATION SENSITIVE ENVIRONMENTS:

Fbw	Dilution Weight (SI Table 12)	Environment Type and Value (SI Tables 13 & 14)	Pot. Cont.	Product
cfs	0.001	x Wetland 2,094 cfs	x 0.1 =	0.01
cfs	0.001	x River 7.5	x 0.1 =	0.0075
cfs		x	x 0.1 =	
cfs		x	x 0.1 =	
cfs		x	x 0.1 =	

Sum =

0.0175

T =

0.0175

✓

SI TABLE 12 (HRS Table 4-13):
SURFACE WATER DILUTION WEIGHTS

Type of Surface Water Body		Assigned Dilution Weight
Descriptor	Flow Characteristics	
Minimal stream	< 10 cfs	1
Small to moderate stream	10 to 100 cfs	0.1
Moderate to large stream	> 100 to 1,000 cfs	0.01
Large stream to river	> 1,000 to 10,000 cfs	0.001
Large river	> 10,000 to 100,000 cfs	0.0001
Very large river	> 100,000 cfs	0.00001
Coastal tidal waters	Flow not applicable; depth not applicable	0.0001
Shallow ocean zone or Great Lake	Flow not applicable; depth less than 20 feet	0.0001
Moderate depth ocean zone or Great Lake	Flow not applicable; depth 20 to 200 feet	0.00001
Deep ocean zone or Great Lake	Flow not applicable; depth greater than 200 feet	0.000005
3-mile mixing zone in quiet flowing river	10 cfs or greater	0.5

SI TABLE 13 (HRS TABLE 4-23):
SURFACE WATER AND AIR SENSITIVE ENVIRONMENTS VALUES

SENSITIVE ENVIRONMENT	ASSIGNED VALUE
<u>Critical habitat for Federal designated endangered or threatened species</u> Marine Sanctuary National Park Designated Federal Wilderness Area Ecologically important areas identified under the Coastal Zone Wilderness Act Sensitive Areas identified under the National Estuary Program or Near Coastal Water Program of the Clean Water Act Critical Areas identified under the Clean Lakes Program of the Clean Water Act (subareas in lakes or entire small lakes) National Monument (air pathway only) National Seashore Recreation Area National Lakeshore Recreation Area	100
<u>Habitat known to be used by Federal designated or proposed endangered or threatened species</u> National Preserve National or State Wildlife Refuge Unit of Coastal Barrier Resources System Coastal Barrier (undeveloped) Federal land designated for the protection of natural ecosystems Administratively Proposed Federal Wilderness Area Spawning areas critical for the maintenance of fish/shellfish species within a river system, bay, or estuary Migratory pathways and feeding areas critical for the maintenance of anadromous fish species within river reaches or areas in lakes or coastal tidal waters in which the fish spend extended periods of time Terrestrial areas utilized by large or dense aggregations of vertebrate animals (semi-aquatic foragers) for breeding National river reach designated as recreational	75
Habitat known to be used by State designated endangered or threatened species Habitat known to be used by a species under review as to its Federal endangered or threatened status Coastal Barrier (partially developed) Federally designated Scenic or Wild River	50
State land designated for wildlife or game management State designated Scenic or Wild River State designated Natural Area Particular areas, relatively small in size, important to maintenance of unique biotic communities	25
State designated areas for the protection of maintenance of aquatic life under the Clean Water Act	5
Wetlands See SI Table 14 (Surface Water Pathway) or SI Table 23 (Air Pathway)	100

SI TABLE 14 (HRS TABLE 4-24): SURFACE WATER
WETLANDS FRONTAGE VALUES

Total Length of Wetlands	Assigned Value
Less than 0.1 mile	0
0.1 to 1 mile	25
Greater than 1 to 2 miles	50
Greater than 2 to 3 miles	75
<u>Greater than 3 to 4 miles</u>	<u>100</u>
Greater than 4 to 8 miles	150
Greater than 8 to 12 miles	250
Greater than 12 to 16 miles	350
Greater than 16 to 20 miles	450
Greater than 20 miles	500

- This page intentionally blank -

SURFACE WATER PATHWAY (concluded) **WASTE CHARACTERISTICS, THREAT, AND PATHWAY SCORE SUMMARY**

WASTE CHARACTERISTICS	Score																														
14. If an Actual Contamination Target (drinking water, human food chain, or environmental threat) exists for the watershed, assign the calculated hazardous waste quantity score, or a score of 100, whichever is greater.	100																														
15. Assign the highest value from SI Table 7 (observed release) or SI Table 3 (no observed release) for the hazardous substance waste characterization factors below. Multiply each by the surface water hazardous waste quantity score and determine the waste characteristics score for each threat.																															
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th>Substance Value</th> <th>HWQ</th> <th>Product</th> </tr> </thead> <tbody> <tr> <td>Drinking Water Threat Toxicity/Persistence</td> <td align="center">10,000 x</td> <td align="center">100 =</td> <td align="center">1×10^6</td> </tr> <tr> <td>Food Chain Threat Toxicity/Persistence Bioaccumulation</td> <td align="center">5×10^8 x</td> <td align="center">100 =</td> <td align="center">5×10^{10}</td> </tr> <tr> <td>Environmental Threat Ecotoxicity/Persistence/ Ecobioaccumulation</td> <td align="center">5×10^8 x</td> <td align="center">100 =</td> <td align="center">5×10^{10}</td> </tr> </tbody> </table>		Substance Value	HWQ	Product	Drinking Water Threat Toxicity/Persistence	10,000 x	100 =	1×10^6	Food Chain Threat Toxicity/Persistence Bioaccumulation	5×10^8 x	100 =	5×10^{10}	Environmental Threat Ecotoxicity/Persistence/ Ecobioaccumulation	5×10^8 x	100 =	5×10^{10}	WC Score (from Table) (Maximum of 1000)														
	Substance Value	HWQ	Product																												
Drinking Water Threat Toxicity/Persistence	10,000 x	100 =	1×10^6																												
Food Chain Threat Toxicity/Persistence Bioaccumulation	5×10^8 x	100 =	5×10^{10}																												
Environmental Threat Ecotoxicity/Persistence/ Ecobioaccumulation	5×10^8 x	100 =	5×10^{10}																												
		32																													
		320																													
		320																													
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Product</th> <th>WC Score</th> </tr> </thead> <tbody> <tr><td>0</td><td align="center">0</td></tr> <tr><td>>0 to <10</td><td align="center">1</td></tr> <tr><td>10 to <100</td><td align="center">2</td></tr> <tr><td>100 to <1,000</td><td align="center">3</td></tr> <tr><td>1,000 to <10,000</td><td align="center">6</td></tr> <tr><td>10,000 to <1E + 05</td><td align="center">10</td></tr> <tr><td>1E + 05 to <1E + 06</td><td align="center">18</td></tr> <tr><td>DW → 1E + 06 to <1E + 07</td><td align="center">32</td></tr> <tr><td>1E + 07 to <1E + 08</td><td align="center">56</td></tr> <tr><td>1E + 08 to <1E + 09</td><td align="center">100</td></tr> <tr><td>1E + 09 to <1E + 10</td><td align="center">180</td></tr> <tr><td>FC-ET → 1E + 10 to <1E + 11</td><td align="center">320</td></tr> <tr><td>1E + 11 to <1E + 12</td><td align="center">560</td></tr> <tr><td>1E + 12 or greater</td><td align="center">1000</td></tr> </tbody> </table>	Product	WC Score	0	0	>0 to <10	1	10 to <100	2	100 to <1,000	3	1,000 to <10,000	6	10,000 to <1E + 05	10	1E + 05 to <1E + 06	18	DW → 1E + 06 to <1E + 07	32	1E + 07 to <1E + 08	56	1E + 08 to <1E + 09	100	1E + 09 to <1E + 10	180	FC-ET → 1E + 10 to <1E + 11	320	1E + 11 to <1E + 12	560	1E + 12 or greater	1000	
Product	WC Score																														
0	0																														
>0 to <10	1																														
10 to <100	2																														
100 to <1,000	3																														
1,000 to <10,000	6																														
10,000 to <1E + 05	10																														
1E + 05 to <1E + 06	18																														
DW → 1E + 06 to <1E + 07	32																														
1E + 07 to <1E + 08	56																														
1E + 08 to <1E + 09	100																														
1E + 09 to <1E + 10	180																														
FC-ET → 1E + 10 to <1E + 11	320																														
1E + 11 to <1E + 12	560																														
1E + 12 or greater	1000																														

SURFACE WATER PATHWAY THREAT SCORES

Threat	Likelihood of Release (LR) Score	Targets (T) Score	Pathway Waste Characteristics (WC) Score (determined above)	Threat Score $\frac{LR \times T \times WC}{82,500}$
Drinking Water	550	5	32	(maximum of 100) 1.067
Human Food Chain	550	20	320	(maximum of 100) 42.67
Environmental	550	0.0175	320	(maximum of 60) 0.037

SURFACE WATER PATHWAY SCORE
 (Drinking Water Threat + Human Food Chain Threat + Environmental Threat)

(maximum of 100)
43.77

SOIL EXPOSURE PATHWAY

If there is no observed contamination (e.g., ground water plume with no known surface source), do not evaluate the soil exposure pathway. Discuss evidence for no soil exposure pathway.

Soil Exposure Resident Population Targets Summary

For each property (duplicate page 35 as necessary):

If there is an area of observed contamination on the property and within 200 feet of a residence, school, or day care center, enter on Table 15 each hazardous substance by sample ID. Record the detected concentration. Obtain cancer risk, and reference dose concentrations from SCDM. Sum the cancer risk and reference dose percentages for the substances listed. If cancer risk or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate the residents and students as Level I. If both percentages are less than 100% or all are N/A, evaluate the targets as Level II.

SI TABLE 15: SOIL EXPOSURE RESIDENT POPULATION TARGETS

Residence ID: _____ Level I _____ Level II _____ Population _____

Sample ID	Hazardous Substance	Conc. (mg/kg)	Cancer Risk Concentration	% of Cancer Risk Conc.	RID	% of RID	Toxicity Value	References
Highest Percent					Sum of Percents		Sum of Percents	

Residence ID: _____ Level I _____ Level II _____ Population _____

Sample ID	Hazardous Substance	Conc. (mg/kg)	Cancer Risk Concentration	% of Cancer Risk Conc.	RID	% of RID	Toxicity Value	References
Highest Percent					Sum of Percents		Sum of Percents	

Residence ID: _____ Level I _____ Level II _____ Population _____

Sample ID	Hazardous Substance	Conc. (mg/kg)	Cancer Risk Concentration	% of Cancer Risk Conc.	RID	% of RID	Toxicity Value	References
Highest Percent					Sum of Percents		Sum of Percents	

C-35

-No schools identified
with > 200' of site Ref. 1

Not Applicable

SOIL EXPOSURE PATHWAY WORKSHEET RESIDENT POPULATION THREAT

LIKELIHOOD OF EXPOSURE

	Score	Data Type	Refs
1. OBSERVED CONTAMINATION: If evidence indicates presence of observed contamination (depth of 2 feet or less), assign a score of 550; otherwise, assign a 0. Note that a likelihood of exposure score of 0 results in a soil exposure pathway score of 0.	550		2,3,6
LE =	550		

TARGETS

<p>2. RESIDENT POPULATION: Determine the number of people occupying residences or attending school or day care on or within 200 feet of areas of observed contamination (HRS section 5.1.3).</p> <p>Level I: _____ people x 10 = _____</p> <p>Level II: _____ people x 1 = _____</p> <p style="text-align: right;">Sum =</p>															
<p>3. RESIDENT INDIVIDUAL: Assign a score of 50 if any Level I resident population exists. Assign a score of 45 if there are Level II targets but no Level I targets. If no resident population exists (i.e., no Level I or Level II targets), assign 0 (HRS Section 5.1.3).</p>															
<p>4. WORKERS: Assign a score from the table below for the total number of workers at the site and nearby facilities with areas of observed contamination associated with the site.</p> <table border="1" style="margin: 10px auto; width: 60%;"> <thead> <tr> <th>Number of Workers</th> <th>Score</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>0</td> </tr> <tr> <td>1 to 100</td> <td>5</td> </tr> <tr> <td>101 to 1,000</td> <td>10</td> </tr> <tr> <td>>1,000</td> <td>15</td> </tr> </tbody> </table>	Number of Workers	Score	0	0	1 to 100	5	101 to 1,000	10	>1,000	15					
Number of Workers	Score														
0	0														
1 to 100	5														
101 to 1,000	10														
>1,000	15														
<p>5. TERRESTRIAL SENSITIVE ENVIRONMENTS: Assign a value for each terrestrial sensitive environment (SI Table 16) in an area of observed contamination.</p> <table border="1" style="margin: 10px auto; width: 60%;"> <thead> <tr> <th>Terrestrial Sensitive Environment Type</th> <th>Value</th> </tr> </thead> <tbody> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </tbody> </table> <p style="text-align: right;">Sum =</p>	Terrestrial Sensitive Environment Type	Value													
Terrestrial Sensitive Environment Type	Value														
<p>6. RESOURCES: Assign a score of 5 if any one or more of the following resources is present on an area of observed contamination at the site; assign 0 if none applies.</p> <ul style="list-style-type: none"> • Commercial agriculture • Commercial silviculture • Commercial livestock production or commercial livestock grazing 															
<p>Total of Targets T=</p>															

SI TABLE 16 (HRS TABLE 5-5): SOIL EXPOSURE PATHWAY
TERRESTRIAL SENSITIVE ENVIRONMENT VALUES

TERRESTRIAL SENSITIVE ENVIRONMENT	ASSIGNED VALUE
Terrestrial critical habitat for Federal designated endangered or threatened species National Park Designated Federal Wilderness Area National Monument	100
Terrestrial habitat known to be used by Federal designated or proposed threatened or endangered species National Preserve (terrestrial) National or State terrestrial Wildlife Refuge Federal land designated for protection of natural ecosystems Administratively proposed Federal Wilderness Area Terrestrial areas utilized by large or dense aggregations of animals (vertebrate species) for breeding	75
Terrestrial habitat used by State designated endangered or threatened species Terrestrial habitat used by species under review for Federal designated endangered or threatened status	50
State lands designated for wildlife or game management State designated Natural Areas Particular areas, relatively small in size, important to maintenance of unique biotic communities	25

- Not Applicable

No terrestrial sensitive
environments within 200'
of site.

Ref. 1:20

SOIL EXPOSURE PATHWAY WORKSHEET NEARBY POPULATION THREAT

LIKELIHOOD OF EXPOSURE		Score	Data Type	Ref.
7. Attractiveness/Accessibility (from SI Table 17 or HRS Table 5-6)	Value <u>10</u>			3
Area of Contamination (from SI Table 18 or HRS Table 5-7)	Value <u>40</u>			
Likelihood of Exposure (from SI Table 19 or HRS Table 5-8)				
LE =		<u>5</u>		

TARGETS		Score	Data Type	Ref.
8. Assign a score of 0 if Level I or Level II resident individual has been evaluated or if no individuals live within 1/4 mile travel distance of an area of observed contamination. Assign a score of 1 if nearby population is within 1/4 mile travel distance and no Level I or Level II resident population has been evaluated.		1		1; 16; 21; 22
9. Determine the population within 1 mile travel distance that is not exposed to a hazardous substance from the site (i.e., properties that are not determined to be Level I or Level II); record the population for each distance category in SI Table 20 (HRS Table 5-10). Sum the population values and multiply by 0.1.		1.8		↓
T =		<u>2.8</u>		

SI TABLE 17 (HRS TABLE 5-6):
ATTRACTIVENESS/ACCESSIBILITY VALUES

Area of Observed Contamination	Assigned Value
Designated recreational area	100
Regularly used for public recreation (for example, vacant lots in urban area)	75
Accessible and unique recreational area (for example, vacant lots in urban area)	75
Moderately accessible (may have some access improvements—for example, gravel road) with some public recreation use	50
Slightly accessible (for example, extremely rural area with no road improvement) with some public recreation use	25
Accessible with no public recreation use	10
Surrounded by maintained fence or combination of maintained fence and natural barriers	5
Physically inaccessible to public, with no evidence of public recreation use	0

SI TABLE 18 (HRS TABLE 5-7): AREA OF CONTAMINATION FACTOR VALUES

Total area of the areas of observed contamination (square feet)	Assigned Value
≤ to 5,000	5
> 5,000 to 125,000	20
> 125,000 to 250,000	40
> 250,000 to 375,000	60
> 375,000 to 500,000	80
> 500,000	100

Ref. 1

AREA OF CONTAMINATION FACTOR VALUE	ATTRACTIVENESS/ACCESSIBILITY FACTOR VALUE						
	100	75	50	25	10	5	0
100	500	500	375	250	125	50	0
80	500	375	250	125	50	25	0
60	375	250	125	50	25	5	0
40	250	125	50	25	5	5	0
20	125	50	25	5	5	5	0
5	50	25	5	5	5	5	0

SI TABLE 20 (HRS TABLE 5-10): DISTANCE-WEIGHTED POPULATION VALUES
FOR NEARBY POPULATION THREAT

Travel Distance Category (miles)	Pop.	Number of people within the travel distance category												Pop. Value
		0	1 to 10	11 to 30	31 to 100	101 to 300	301 to 1,000	1,001 to 3,000	3,001 to 10,001	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	
Greater than 0 to $\frac{1}{4}$	76	0	0.1	0.4	1.0	4	13	41	130	408	1,303	4,081	13,034	1
Greater than $\frac{1}{4}$ to $\frac{1}{2}$	506	0	0.05	0.2	0.7	2	7	20	65	204	652	2,041	6,517	7
Greater than $\frac{1}{2}$ to 1	2,916	0	0.02	0.1	0.3	1	3	10	33	102	326	1,020	3,258	10
Reference(s) <u>1, 16, 21, 22</u>														Sum = 18

SOIL EXPOSURE PATHWAY WORKSHEET (concluded)

WASTE CHARACTERISTICS

10. Assign the hazardous waste quantity score calculated for soil exposure	100
11. Assign the highest toxicity value from SI Table 16	10,000
12. Multiply the toxicity and hazardous waste quantity scores. Assign the Waste Characteristics score from the table below:	WC = 32

Product	WC Score
0	0
>0 to <10	1
10 to <100	2
100 to <1,000	3
1,000 to <10,000	6
10,000 to <1E + 05	10
1E + 05 to <1E + 06	18
1E + 06 to <1E + 07	32
1E + 07 to <1E + 08	56
1E + 08 or greater	100

RESIDENT POPULATION THREAT SCORE:

(Likelihood of Exposure, Question 1;
Targets = Sum of Questions 2, 3, 4, 5, 6)

$$\frac{LE \times T \times WC}{82,500}$$

0

NEARBY POPULATION THREAT SCORE:

(Likelihood of Exposure, Question 7;
Targets = Sum of Questions 8, 9)

$$\frac{LE \times T \times WC}{82,500}$$

0.31

SOIL EXPOSURE PATHWAY SCORE:

Resident Population Threat + Nearby Population Threat

0.31
(Maximum of 100)

$$\frac{RPTS}{RPTS} = \frac{550 \times 0 \times 32}{RPTS}$$

$$\frac{NPTS}{NPTS} = \frac{5 \times 2.8 \times 32}{82,500} = .00543$$

AIR PATHWAY

Air Pathway Observed Substances Summary Table

On SI Table 21, list the hazardous substances detected in air samples of a release from the site. Include only those substances with concentrations significantly greater than background levels. Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For NAAQS/NESHAPS benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate targets in the distance category from which the sample was taken and any closer distance categories as Level I. If the percentages are less than 100% or all are N/A, evaluate targets in that distance category and any closer distance categories that are not Level I as Level II.

SI TABLE 21: AIR PATHWAY OBSERVED RELEASE SUBSTANCES

Sample ID: _____ Level I _____ Level II _____ Distance from Sources (mi) _____ References _____

Hazardous Substance	Conc. ($\mu\text{g}/\text{m}^3$)	Gaseous Particulate	Benchmark Conc. (NAAQS or NESHAPS)	% of Benchmark	Cancer Risk Conc.	% of Cancer Risk Conc.	RID	% of RID
	Highest Toxicity/ Mobility		Highest Percent		Sum of Percents		Sum of Percents	

Sample ID: _____ Level I _____ Level II _____ Distance from Sources (mi) _____ References _____

Hazardous Substance	Conc. (µg/m³)	Toxicity/ Mobility	Benchmark Conc. (NAAQS or NESHAPS)	% of Benchmark	Cancer Risk Conc.	% of Cancer Risk Conc.	RID	% of RID
	Highest Toxicity/ Mobility		Highest Percent		Sum of Percents		Sum of Percents	

Sample ID: _____ Level I _____ Level II _____ Distance from Sources (mi) _____ References _____

Hazardous Substance	Conc. ($\mu\text{g}/\text{m}^3$)	Toxicity/ Mobility	Benchmark Conc. (NAAQS or NESHAPS)	% of Benchmark	Cancer Risk Conc.	% of Cancer Risk Conc.	RID	% of RID
	Highest Toxicity/ Mobility		Highest Percent		Sum of Percents		Sum of Percents	

Not a doctor?

AIR PATHWAY WORKSHEET

LIKELIHOOD OF RELEASE	Score	Data Type	Refs
1. OBSERVED RELEASE: If sampling data or direct observation support a release to air, assign a score of 550. Record observed release substances on SI Table 21.	0		
2. POTENTIAL TO RELEASE: If sampling data do not support a release to air, assign a score of 500. Optionally, evaluate air migration gaseous and particulate potential to release (HRS Section 6.1.2).	500		
LR =		500	

TARGETS

3. ACTUAL CONTAMINATION POPULATION: Determine the number of people within the target distance limit subject to exposure from a release of a hazardous substance to the air. a) Level I: _____ people x 10 = _____ b) Level II: _____ people x 1 = _____ Total = _____	0																		
4. POTENTIAL TARGET POPULATION: Determine the number of people within the target distance limit not subject to exposure from a release of a hazardous substance to the air, and assign the total population score from SI Table 22. Sum the values and multiply the sum by 0.1.	10.67		1; 21																
5. NEAREST INDIVIDUAL: Assign a score of 50 if there are any Level I targets. Assign a score of 45 if there are Level II targets but no Level I targets. If no Actual Contamination Population exists, assign the Nearest Individual score from SI Table 22.	20		↓																
6. ACTUAL CONTAMINATION SENSITIVE ENVIRONMENTS: Sum the sensitive environment values (SI Table 13) and wetland acreage values (SI Table 23) for environments subject to exposure from the release of a hazardous substance to the air. <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Sensitive Environment Type</th> <th style="text-align: center;">Value</th> </tr> </thead> <tbody> <tr><td>_____</td><td style="text-align: center;">_____</td></tr> <tr><td>_____</td><td style="text-align: center;">_____</td></tr> <tr><td>_____</td><td style="text-align: center;">_____</td></tr> </tbody> </table> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Wetland Acreage</th> <th style="text-align: center;">Value</th> </tr> </thead> <tbody> <tr><td>_____</td><td style="text-align: center;">_____</td></tr> <tr><td>_____</td><td style="text-align: center;">_____</td></tr> <tr><td>_____</td><td style="text-align: center;">_____</td></tr> </tbody> </table>	Sensitive Environment Type	Value	_____	_____	_____	_____	_____	_____	Wetland Acreage	Value	_____	_____	_____	_____	_____	_____	0		
Sensitive Environment Type	Value																		
_____	_____																		
_____	_____																		
_____	_____																		
Wetland Acreage	Value																		
_____	_____																		
_____	_____																		
_____	_____																		
7. POTENTIAL CONTAMINATION SENSITIVE ENVIRONMENTS: Use SI Table 24 to evaluate sensitive environments not subject to exposure from a release.	1.897		20; 23																
8. RESOURCES: Assign a score of 5 if one or more air resources apply within 1/2 mile of a source; assign a 0 if none applies. <ul style="list-style-type: none"> • Commercial agriculture • Commercial silviculture • Major or designated recreation area 	0																		
T =		32.57																	

SI TABLE 22 (From HRS TABLE 6-17): VALUES FOR POTENTIAL CONTAMINATION AIR TARGET POPULATIONS

Distance from Site	Pop.	Nearest Individual (choose highest)	Number of People within the Distance Category												Pop. Value
			1 to 10	11 to 30	31 to 100	101 to 300	301 to 1,000	1,001 to 3,000	3,001 to 10,000	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	1,000,000 to 3,000,000	
On a source	0	20	4	17	53	164	522	1,633	5,214	16,325	52,137	163,246	521,360	1,632,455	0
0 to $\frac{1}{4}$ mile	76	*	1	4	13	41	131	408	1,304	4,081	13,034	40,812	130,340	408,114	13
$> \frac{1}{4}$ to $\frac{1}{2}$ mile	506	2	0.2	0.9	3	9	28	88	282	882	2,815	8,815	28,153	88,153	23
$> \frac{1}{2}$ to 1 mile	2,916	1	0.06	0.3	0.9	3	8	26	83	261	834	2,612	8,342	26,119	24
> 1 to 2 miles	4,727	0	0.02	0.09	0.3	0.8	3	8	27	83	266	833	2,659	8,326	0
> 2 to 3 miles	3,347	0	0.009	0.04	0.1	0.4	1	4	12	38	120	375	1,199	3,755	12
> 3 to 4 miles	964	0	0.005	0.02	0.07	0.2	0.7	2	7	23	73	229	730	2,285	0.7
Nearest Individual =		20													Sum = 106.7

References 1, 2

* Score = 20 if the Nearest Individual is within $\frac{1}{8}$ mile of a source; score = 7 if the Nearest Individual is between $\frac{1}{8}$ and $\frac{1}{4}$ mile of a source.

SI TABLE 23 (HRS TABLE 6-18): AIR PATHWAY VALUES FOR WETLAND AREA

Wetland Area	Assigned Value
< 1 acre	0
1 to 50 acres	25
> 50 to 100 acres	75
> 100 to 150 acres	125
> 150 to 200 acres	175
> 200 to 300 acres	250
> 300 to 400 acres	350
> 400 to 500 acres	450
> 500 acres	500

SI TABLE 24: DISTANCE WEIGHTS AND CALCULATIONS FOR AIR PATHWAY POTENTIAL CONTAMINATION SENSITIVE ENVIRONMENTS

Distance	Distance Weight	Sensitive Environment Type and Value (from SI Tables 13 and 20)	Product
On a Source	0.10	x	
		x	
0 to 1/4 mile	0.025	x 75 Habitat PAF	1.875
		x	
		x	
		x	
1/4 to 1/2 mile	0.0054	x	
		x	
		x	
1/2 to 1 mile	0.0016	x	
		x	
		x	
1 to 2 miles	0.0005	x 25 wetlands	0.0125
		x	
		x	
2 to 3 miles	0.00023	x 25 wetlands	0.00575
		x	
		x	
3 to 4 miles	0.00014	x 25 wetlands	0.0035
		x	
		x	
> 4 miles	0	x	
Total Environments Score =			1.8975

C-46

0-1/4 0

1/4-1/2 0

1/2-1 0

1-2 11

2-3 28

3-4 39

AIR PATHWAY (concluded)

WASTE CHARACTERISTICS

<p>9. If any Actual Contamination Targets exist for the air pathway, assign the calculated hazardous waste quantity score or a score of 100, whichever is greater; if there are no Actual Contamination Targets for the air pathway, assign the calculated HWQ score for sources available to air migration.</p>	100																						
<p>10. Assign the highest air toxicity/mobility value from SI Table 3 .</p>	10,000																						
<p>11. Multiply the air pathway toxicity/mobility and hazardous waste quantity scores. Assign the Waste Characteristics score from the table below:</p> <table border="1" style="margin: 10px auto; border-collapse: collapse; font-size: 0.8em;"> <thead> <tr> <th style="text-align: left; padding: 2px;">Product</th> <th style="text-align: left; padding: 2px;">WC Score</th> </tr> </thead> <tbody> <tr><td>0</td><td>0</td></tr> <tr><td>>0 to <10</td><td>1</td></tr> <tr><td>10 to <100</td><td>2</td></tr> <tr><td>100 to <1,000</td><td>3</td></tr> <tr><td>1,000 to < 10,000</td><td>6</td></tr> <tr><td>10,000 to <1E + 05</td><td>10</td></tr> <tr><td>1E + 05 to <1E + 06</td><td>18</td></tr> <tr style="border: 2px solid black;"><td>1E + 06 to <1E + 07</td><td>32</td></tr> <tr><td>1E + 07 to <1E + 08</td><td>56</td></tr> <tr><td>1E + 08 or greater</td><td>100</td></tr> </tbody> </table>	Product	WC Score	0	0	>0 to <10	1	10 to <100	2	100 to <1,000	3	1,000 to < 10,000	6	10,000 to <1E + 05	10	1E + 05 to <1E + 06	18	1E + 06 to <1E + 07	32	1E + 07 to <1E + 08	56	1E + 08 or greater	100	<p style="font-size: 1.5em;">WC = 32</p>
Product	WC Score																						
0	0																						
>0 to <10	1																						
10 to <100	2																						
100 to <1,000	3																						
1,000 to < 10,000	6																						
10,000 to <1E + 05	10																						
1E + 05 to <1E + 06	18																						
1E + 06 to <1E + 07	32																						
1E + 07 to <1E + 08	56																						
1E + 08 or greater	100																						

AIR PATHWAY SCORE:

$$\frac{LE \times T \times WC}{82,500}$$

6.32

(maximum of 100)

$$\frac{500 \times 32.57 \times 32}{82,500} = 6.3166$$

SITE SCORE CALCULATION		S	S ²
GROUND WATER PATHWAY SCORE (S _{GW})		5.57	31.0249
SURFACE WATER PATHWAY SCORE (S _{sw})		43.77	1,915.8129
SOIL EXPOSURE (S _s)		0.01	0.001
AIR PATHWAY SCORE (S _A)		6.32	39.9424
SITE SCORE $\sqrt{\frac{S_{GW}^2 + S_{sw}^2 + S_s^2 + S_A^2}{4}} =$ $\sqrt{\frac{1982.7812}{4}} = \sqrt{496.6953} = 22.2867$			22.27

COMMENTS

REFERENCE NO. 1

OVERSIZED

DOCUMENT

REFERENCE NO. 2

POTENTIAL HAZARDOUS WASTE SITE PRELIMINARY ASSESSMENT PART 1 - SITE INFORMATION AND ASSESSMENT		I. IDENTIFICATION	
		01 STATE TN	02 SITE NUMBER D980515779
II. SITE NAME AND LOCATION			
01 SITE NAME (Legal, common, or descriptive name of site) Oil Service Co./Treatment Plant		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 408 Santa Fe Pike	
03 CITY Columbia	04 STATE TN	05 ZIP CODE 38401	06 COUNTY Maury
07 COUNTY CODE 119		08 CONG DIST 06	
09 COORDINATES LATITUDE 35 37 38. -		LONGITUDE 087 02 15. -	
10 DIRECTIONS TO SITE (Starting from nearest public road)			
III. RESPONSIBLE PARTIES			
01 OWNER (If known) President - Kenneth Harris Oil Services Co.		02 STREET (Business, mailing, residential) Box 1203	
03 CITY Columbia	04 STATE TN	05 ZIP CODE 38401	06 TELEPHONE NUMBER (615) 381-4999
07 OPERATOR (If known and different from owner)		08 STREET (Business, mailing, residential)	
09 CITY	10 STATE	11 ZIP CODE	12 TELEPHONE NUMBER
13 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL: _____ (Agency name) <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER: _____ (Specify) <input type="checkbox"/> G. UNKNOWN			
14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply) <input type="checkbox"/> A. RCRA 3001 DATE RECEIVED: _____ MONTH DAY YEAR <input type="checkbox"/> B. UNCONTROLLED WASTE SITE (CERCLA 103(c)) DATE RECEIVED: _____ MONTH DAY YEAR <input type="checkbox"/> C. NONE			
IV. CHARACTERIZATION OF POTENTIAL HAZARD			
01 ON SITE INSPECTION <input type="checkbox"/> YES DATE _____ MONTH DAY YEAR <input type="checkbox"/> NO		BY (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: _____ (Specify) CONTRACTOR NAME(S): _____	
02 SITE STATUS (Check one) <input type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input type="checkbox"/> C. UNKNOWN		03 YEARS OF OPERATION BEGINNING YEAR 1930 ENDING YEAR - <input type="checkbox"/> UNKNOWN	
04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED Water soluble oils			
05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION			
V. PRIORITY ASSESSMENT			
01 PRIORITY FOR INSPECTION (Check one, if high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents) <input type="checkbox"/> A. HIGH (Inspection required promptly) <input type="checkbox"/> B. MEDIUM (Inspection required) <input checked="" type="checkbox"/> C. LOW (Inspect on time available basis) <input type="checkbox"/> D. NONE (No further action needed, complete current disposition form)			
VI. INFORMATION AVAILABLE FROM			
01 CONTACT		02 OF (Agency, Organization)	
03 PERSON RESPONSIBLE FOR ASSESSMENT Kenneth R. Davis		04 AGENCY SWM	
05 ORGANIZATION TN. Dept of H. & E.		06 TELEPHONE NUMBER (615) 741-6237	
07 DATE 12-16-93		08 MONTH DAY YEAR	



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN D980515779

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: _____ (ACRES) 04 NARRATIVE DESCRIPTION

01 ☐ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN D980515779

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include name(s) of species)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ M. UNSTABLE CONTAINMENT OF WASTES
(Spill/runoff/standing liquids/leaking drums)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____

04 NARRATIVE DESCRIPTION

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL


☐ ALLEGED

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

06 TOTAL POPULATION POTENTIALLY AFFECTED: _____


07 COMMENTS

08 SOURCES OF INFORMATION (Cite specific references, e. g., state files, sample analyses, reports)



INTERVAL 20 FEET
 MEAN SEA LEVEL

ADDITIONAL MAP ACCURACY STANDARDS
 SURVEY, WASHINGTON, D.C. 20242,
 GEOLOGY, NASHVILLE, TENN. 37219,
 MOOGA, TENN. 37401 OR KNOXVILLE, TENN. 37902
 MAPS AND SYMBOLS IS AVAILABLE ON REQUEST



QUADRANGLE LOCATION

ROAD CLASSIFICATION

Heavy-duty	Poor motor road
Medium-duty	Wagon and jeep track
Light-duty	Foot trail
U. S. Route	State Route

In developed areas, only through roads are classified

GODWIN, TENN.
 N3537.5-W8700/7.5

1965

AMS 3155 II NE-SERIES V841

345

7 MI. TO INTERSTATE 55

3943' W. N.

35°37'30"

87°00'

3000000 E.

(GLENDALE 64-SW)
 3655 III SW

REFERENCE NO. 3



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION

01 STATE | 02 SITE NUMBER
TN | TND98051579

II. SITE NAME AND LOCATION

01 SITE NAME (Use common or descriptive name if not) Oil Service Co. / Treatment Plant		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 408 Santa Fe Pike			
03 CITY Columbia	04 STATE TN	05 ZIP CODE 38401	06 COUNTY Maury	07 COUNTY CODE	08 CONG DIST
09 COORDINATES LATITUDE -----		LONGITUDE -----		10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN	

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 4-5-84 MONTH - DAY - YEAR	02 SITE STATUS <input checked="" type="checkbox"/> ACTIVE <input type="checkbox"/> INACTIVE	03 YEARS OF OPERATION 1980 present BEGINNING YEAR ENDING YEAR	UNKNOWN
---	---	---	---------

04 AGENCY PERFORMING INSPECTION (Check all that apply)

☐ A. EPA ☐ B. EPA CONTRACTOR ☐ C. MUNICIPAL ☐ D. MUNICIPAL CONTRACTOR
☒ E. STATE ☐ F. STATE CONTRACTOR ☐ G. OTHER


05 CHIEF INSPECTOR Karen Bonner	06 TITLE Chemist	07 ORGANIZATION SWM	08 TELEPHONE NO. (615) 741-6287
09 OTHER INSPECTORS Charles Allen	10 TITLE Engineer	11 ORGANIZATION SWM	12 TELEPHONE NO. (615) 741-6287
			()
			()
			()
			()

13 SITE REPRESENTATIVES INTERVIEWED Kenneth Harris	14 TITLE President	15 ADDRESS 202 Hill St. Columbia, TN 38401	16 TELEPHONE NO. (615) 381-4999
Steve Maloney	Operator	Tri-Tech Waldron Rd. Liverside, TN	(615) 388-3448
			()
			()
			()
			()

17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION 12:30 PM	19 WEATHER CONDITIONS Cloudy, 45°F
--	-----------------------------------	---------------------------------------

IV. INFORMATION AVAILABLE FROM

01 CONTACT Steve Maloney	02 OF (Agency Organization) Tri-Tech Laboratories		03 TELEPHONE NO. (615) 793-7547	
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Karen Bonner	05 AGENCY SWM	06 ORGANIZATION	07 TELEPHONE NO. (615) 741-6287	08 DATE 4-9-84 MONTH - DAY - YEAR





POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TN09805157A

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED <small>Check all that apply:</small>	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPOES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCG PLAN				
<input type="checkbox"/> G. STATE <small>Specify:</small>				
<input type="checkbox"/> H. LOCAL <small>Specify:</small>				
<input type="checkbox"/> I. OTHER <small>Specify:</small>				
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/ DISPOSAL <small>Check all that apply:</small>	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT <small>Check all that apply:</small>	05 OTHER
<input type="checkbox"/> A. SURFACE IMPOUNDMENT			<input type="checkbox"/> A. INCINERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input checked="" type="checkbox"/> E. WASTE OIL PROCESSING	06 AREA OF SITE
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> H. OPEN DUMP			<input type="checkbox"/> H. OTHER <small>Specify:</small>	
<input checked="" type="checkbox"/> I. OTHER <small>Specify: Basins</small>	unknown			

07 COMMENTS

This is an old sewer treatment plant that Oil Services leased 3 years ago. A company by the name of Shi-Jech operates this plant for them. They treat waste oil. Waste water is discharged to the municipal system and is tested every so often. Oil Services hauls sludge and waste oil out to a licensed treatment facility.

IV. CONTAINMENT

01 CONTAINMENT OF WASTES Check one:
☒ A. ADEQUATE, SECURE ☐ B. MODERATE ☐ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

Waste oil is contained in concrete basins.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☒ YES ☐ NO
02 COMMENTS

VI. SOURCES OF INFORMATION (Cite specific references, e.g., STATE MAPS, SOIL ANALYSES, REPORTS)

4-5-84 - Site Investigation



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

TN TN0980515779

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE Check one.

☐ A. $10^{-4} - 10^{-3}$ cm/sec ☐ B. $10^{-4} - 10^{-5}$ cm/sec ☐ C. $10^{-5} - 10^{-6}$ cm/sec ☐ D. GREATER THAN 10^{-3} cm/sec

02 PERMEABILITY OF BEDROCK Check one.

☐ A. IMPERMEABLE ☐ B. RELATIVELY IMPERMEABLE ☐ C. RELATIVELY PERMEABLE ☐ D. VERY PERMEABLE
Less than 10^{-8} cm/sec. $10^{-8} - 10^{-6}$ cm/sec. $10^{-6} - 10^{-4}$ cm/sec. Greater than 10^{-4} cm/sec.

03 DEPTH TO BEDROCK

04 DEPTH OF CONTAMINATED SOIL ZONE

05 SOIL pH

(ft)

(ft)

06 NET PRECIPITATION

07 ONE YEAR 24 HOUR RAINFALL

08 SLOPE
SITE SLOPE

DIRECTION OF SITE SLOPE

TERRAIN AVERAGE SLOPE

(in)

(in)

%

%

09 FLOOD POTENTIAL

10

SITE IS IN _____ YEAR FLOODPLAIN

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

OTHER

A. _____ (mi)

B. _____ (mi)

12 DISTANCE TO CRITICAL HABITAT of endangered species.

_____ (mi)

ENDANGERED SPECIES: _____

13 LAND USE & VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS; NATIONAL STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A. _____ (mi)

B. _____ (mi)

C. _____ (mi)

D. _____ (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state map, sample analysis, reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

TN TND: 98055 725

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER			
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL			
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN


01 TYPE	02 COMMENTS

IV. PHOTOGRAPHS AND MAPS

05 TYPE <input type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	06 IN CUSTODY OF _____ <small>(Name of organization or individual)</small>
03 MAPS <input type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS _____

V. OTHER FIELD DATA COLLECTED Provide narrative descriptions

VI. SOURCES OF INFORMATION Cite specific references, e.g., State files, agency files, reports



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

C: STATE 02 SITE NUMBER
TN TN0980515779

II. CURRENT OWNER(S)

PARENT COMPANY (If applicable)

01 NAME City of Columbia	02 D-B NUMBER	08 NAME	09 D-B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD, etc.)	11 SIC CODE
05 CITY Columbia	06 STATE TN	07 ZIP CODE 38401	
01 NAME	02 D-B NUMBER	08 NAME	09 D-B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD, etc.)	11 SIC CODE
05 CITY	06 STATE	07 ZIP CODE	
01 NAME	02 D-B NUMBER	08 NAME	09 D-B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD, etc.)	11 SIC CODE
05 CITY	06 STATE	07 ZIP CODE	
01 NAME	02 D-B NUMBER	08 NAME	09 D-B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD, etc.)	11 SIC CODE
05 CITY	06 STATE	07 ZIP CODE	

III. PREVIOUS OWNER(S) (List most recent first)

IV. REALTY OWNER(S) (If applicable, list most recent first)

01 NAME	02 D-B NUMBER	01 NAME	02 D-B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE	05 CITY	06 STATE
01 NAME	02 D-B NUMBER	01 NAME	02 D-B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE	05 CITY	06 STATE
01 NAME	02 D-B NUMBER	01 NAME	02 D-B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE	05 CITY	06 STATE

V. SOURCES OF INFORMATION (List specific references, e.g., state files, owner interviews, reports)

4-5-84 - Site Investigation



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TND98054

1/29

II. CURRENT OPERATOR (Provide if different from owner)				OPERATOR'S PARENT COMPANY (If applicable)			
01 NAME TRI-TECH		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, APO, etc.) WALDRON RD		04 SIC CODE		12 STREET ADDRESS (P.O. Box, APO, etc.)		13 SIC CODE	
05 CITY LOVERBNE		06 STATE TN		14 CITY		15 STATE	
07 ZIP CODE		08 YEARS OF OPERATION		09 NAME OF OWNER		16 ZIP CODE	
III. PREVIOUS OPERATOR(S) (List most recent first; include only if different from owner)				PREVIOUS OPERATORS' PARENT COMPANIES (If applicable)			
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, APO, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, APO, etc.)		13 SIC CODE	
05 CITY		06 STATE		14 CITY		15 STATE	
07 ZIP CODE		08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD		16 ZIP CODE	
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, APO, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, APO, etc.)		13 SIC CODE	
05 CITY		06 STATE		14 CITY		15 STATE	
07 ZIP CODE		08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD		16 ZIP CODE	
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, APO, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, APO, etc.)		13 SIC CODE	
05 CITY		06 STATE		14 CITY		15 STATE	
07 ZIP CODE		08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD		16 ZIP CODE	

IV. SOURCES OF INFORMATION (Check appropriate references, e.g., State files, operator records, records)

4-5-84 - Site Investigation

10



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TN0980515779

II. ON-SITE GENERATOR

01 NAME	02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	
05 CITY	06 STATE 07 ZIP CODE	

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

V. SOURCES OF INFORMATION (Cite specific references, e.g., owner files, company records, reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TN09805157

II. PAST RESPONSE ACTIVITIES

01 <input type="checkbox"/> A. WATER SUPPLY CLOSED 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> B. TEMPORARY WATER SUPPLY PROVIDED 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> C. PERMANENT WATER SUPPLY PROVIDED 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> D. SPILLED MATERIAL REMOVED 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> E. CONTAMINATED SOIL REMOVED 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> F. WASTE REPACKAGED 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> G. WASTE DISPOSED ELSEWHERE 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> H. ON SITE BURIAL 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> I. IN SITU CHEMICAL TREATMENT 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> J. IN SITU BIOLOGICAL TREATMENT 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> K. IN SITU PHYSICAL TREATMENT 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> L. ENCAPSULATION 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> M. EMERGENCY WASTE TREATMENT 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> N. CUTOFF WALLS 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> O. EMERGENCY DRAIN/SURFACE WATER DIVERSION 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> P. CUTOFF TRENCHES/SUMP 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> Q. SUBSURFACE CUTOFF WALL 04 DESCRIPTION:	02 DATE _____	03 AGENCY _____



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

L IDENTIFICATION

01 STATE 02 SITE NUMBER

TN TND9805157A

II PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ S. CAPPING/COVERING
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ T. BULK TANKAGE REPAIRED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ U. GROUT CURTAIN CONSTRUCTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ V. BOTTOM SEALED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ W. GAS CONTROL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ X. FIRE CONTROL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ Y. LEACHATE TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ Z. AREA EVACUATED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ 1. ACCESS TO SITE RESTRICTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ 2. POPULATION RELOCATED
04 DESCRIPTION

02 DATE _____


03 AGENCY _____

01 ☐ 3. OTHER REMEDIAL ACTIVITIES
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

III. SOURCES OF INFORMATION (See specific references, e.g., SRSR files, SRSR analysis reports)



01: STATE TN	02: SITE NUMBER TNC980515779
-----------------	---------------------------------


01 PAST REGULATORY/ENFORCEMENT ACTION = YES ☐ NO ☒

32 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

1. NAME JOHN DOE
 2. ADDRESS 123 MAIN ST
 3. CITY NEW YORK
 4. STATE NY
 5. ZIP 10001
 6. PHONE 212-555-1234
 7. DATE 01/01/2020
 8. SIGNATURE [Signature]
 9. PRINT NAME JOHN DOE
 10. DATE 01/01/2020
 11. TIME 10:00 AM
 12. LOCATION NEW YORK
 13. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 14. DATE 01/01/2020
 15. TIME 10:00 AM
 16. LOCATION NEW YORK
 17. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 18. DATE 01/01/2020
 19. TIME 10:00 AM
 20. LOCATION NEW YORK
 21. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 22. DATE 01/01/2020
 23. TIME 10:00 AM
 24. LOCATION NEW YORK
 25. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 26. DATE 01/01/2020
 27. TIME 10:00 AM
 28. LOCATION NEW YORK
 29. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 30. DATE 01/01/2020
 31. TIME 10:00 AM
 32. LOCATION NEW YORK
 33. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 34. DATE 01/01/2020
 35. TIME 10:00 AM
 36. LOCATION NEW YORK
 37. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 38. DATE 01/01/2020
 39. TIME 10:00 AM
 40. LOCATION NEW YORK
 41. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 42. DATE 01/01/2020
 43. TIME 10:00 AM
 44. LOCATION NEW YORK
 45. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 46. DATE 01/01/2020
 47. TIME 10:00 AM
 48. LOCATION NEW YORK
 49. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 50. DATE 01/01/2020
 51. TIME 10:00 AM
 52. LOCATION NEW YORK
 53. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 54. DATE 01/01/2020
 55. TIME 10:00 AM
 56. LOCATION NEW YORK
 57. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 58. DATE 01/01/2020
 59. TIME 10:00 AM
 60. LOCATION NEW YORK
 61. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 62. DATE 01/01/2020
 63. TIME 10:00 AM
 64. LOCATION NEW YORK
 65. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 66. DATE 01/01/2020
 67. TIME 10:00 AM
 68. LOCATION NEW YORK
 69. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 70. DATE 01/01/2020
 71. TIME 10:00 AM
 72. LOCATION NEW YORK
 73. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 74. DATE 01/01/2020
 75. TIME 10:00 AM
 76. LOCATION NEW YORK
 77. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 78. DATE 01/01/2020
 79. TIME 10:00 AM
 80. LOCATION NEW YORK
 81. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 82. DATE 01/01/2020
 83. TIME 10:00 AM
 84. LOCATION NEW YORK
 85. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 86. DATE 01/01/2020
 87. TIME 10:00 AM
 88. LOCATION NEW YORK
 89. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 90. DATE 01/01/2020
 91. TIME 10:00 AM
 92. LOCATION NEW YORK
 93. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 94. DATE 01/01/2020
 95. TIME 10:00 AM
 96. LOCATION NEW YORK
 97. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 98. DATE 01/01/2020
 99. TIME 10:00 AM
 100. LOCATION NEW YORK
 101. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 102. DATE 01/01/2020
 103. TIME 10:00 AM
 104. LOCATION NEW YORK
 105. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 106. DATE 01/01/2020
 107. TIME 10:00 AM
 108. LOCATION NEW YORK
 109. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 110. DATE 01/01/2020
 111. TIME 10:00 AM
 112. LOCATION NEW YORK
 113. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 114. DATE 01/01/2020
 115. TIME 10:00 AM
 116. LOCATION NEW YORK
 117. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 118. DATE 01/01/2020
 119. TIME 10:00 AM
 120. LOCATION NEW YORK
 121. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 122. DATE 01/01/2020
 123. TIME 10:00 AM
 124. LOCATION NEW YORK
 125. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 126. DATE 01/01/2020
 127. TIME 10:00 AM
 128. LOCATION NEW YORK
 129. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 130. DATE 01/01/2020
 131. TIME 10:00 AM
 132. LOCATION NEW YORK
 133. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 134. DATE 01/01/2020
 135. TIME 10:00 AM
 136. LOCATION NEW YORK
 137. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 138. DATE 01/01/2020
 139. TIME 10:00 AM
 140. LOCATION NEW YORK
 141. REMARKS ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
 142. DATE 01/01/2020
 143. TIME 10:00 AM
 144

III. SOURCES OF INFORMATION

4-5-84 - Site Investigation



35° 37' 50"
87° 00'

1943 3000m N.
1946
1945
1947
1948
1949

REFERENCE NO. 4


BLACK & VEATCH Waste Science, Inc.
Philadelphia Office

MEMORANDUM

USEPA Region IV
Treatment Plant/Oil Services Co.
Waste Treatment

BVWS Project 52012.545
BVWS File N
February 10, 1995
0923

To: Treatment Plant/Oil Services Co. File

From: Michael Ferrari 

On this date I spoke with Roger LeMaster (RL) at the Tennessee Department of Health and Environment, Wastewater Treatment Division [(615) 532-0625]. The information which I obtained from RL differed from the information I received previously from Carol Shell, president of Tri-Tech Laboratories [(615) 793-7547].

According to RL, Oil Services Company (OSCO) did operate at the former Columbia Wastewater Treatment Plant, but after they moved from Columbia to Nashville, they did not go out of business. They still operate out of their Nashville office.

RL said that OSCO used to receive waste oil and grease from a number of different sources; primarily from electroplating and degreasing operations. The waste was treated to remove metals and organics. Non-hazardous sludge was disposed of in a licensed landfill, and hazardous sludge waste was taken to a permitted hazardous waste landfill. OSCO performed their own periodic testing on their wastestreams. OSCO had a NPDES permit which allowed them to discharge treated wastewater into the municipal water system.

REFERENCE NO. 5

August 8, 1983

Superfund
634 Site Master List-Public Comment
Rebecca F. Harris

Telephone call from:
Ken Harris - Oil Services Co.
Columbia, Tennessee

many Co.
60-57

Three sites on Master List involve Harris' operations:

1. Treatment Plant/Oil Services Co. 408 Santa Fe Pike
Columbia, Tennessee

This facility, an out of service municipal wastewater treatment plant, is now operated as a private wastewater treatment plant for soluble oil treatment. Sludge and skimmed oils go to a refinery for oil recovery. Clean-up residues from cleaning of tanks after sludge removal go to the Chemical Waste Management Alabama Landfill for disposal.

The Santa Fe Pike facility is owned by the City of Columbia. Harris leased it for the last (3) three years accepting only non-hazardous water soluble oil waste streams. Tri-tech Corp., run by Gerry Shell, wants to pick up the lease and operate the plant although Harris would still provide the waste streams.

2. Kenneth Harris Oil
Carter's Creek Pike
Columbia, Tennessee

This listing references a pond which was excavated behind Harris' residence off Carter's Creek Pike. The pond was used as a temporary treatment facility for waste oil streams that were scheduled to go to the Santa Fe Pike Facility. Harris apparently contracted to haul the waste to the Santa Fe Facility then ran into negotiations problems with the city. The pond was used on a one time basis for an unspecified period of time while Harris completed negotiations for the Santa Fe Facility. Harris dug the pond, treated the oily wastewater, and transported the treated water to the city WWTP. The sludge and skimmed oil were sent to a refinery for oil recovery. The pond was then filled in. Harris stated that these activities were conducted under an agreement with Water Quality Control. A letter was written that should be in Water Management Files.

3. Oil Service Co.
202 Hill Street
Columbia, Tennessee

This is the site of Harris' current operations. He has submitted a Part B application to James Spicer of the SWM Nashville Field Office. No hazardous waste disposal has been or will be conducted there.

REFERENCE NO. 6

May 22, 1979

RMJ
Dum 6-1
JTTG-6
JRS 6-13
TDH 6-29
JW 7-6
SMH 7-13
1

CERTIFIED MAIL

Mr. Michael Stone
Director, Sewer Services
City of Columbia
707 North Main Street
Columbia, Tennessee 38401

Re: Oil Service Company
Disposition of Waste Oil
Columbia, Maury County, Tennessee

Dear Mr. Stone:

This letter will confirm our telephone conversation of May 16, 1979, in which you agreed to inform Mr. Kenneth Harris, owner of Oil Service Company, that he could no longer dump any waste oils or other waste materials into the municipal sewer system in Columbia. As you know, this office has received several complaints stemming from the fact that Mr. Harris has allegedly been allowed to introduce waste materials, including water-soluble oils, in an untreated form into the old Columbia Sewage Treatment Plant, in violation of that City's sewer use ordinance. Although we have only been aware of Oil Service Company's agreement with the City of Columbia for the past few weeks, it is now obvious that past operational problems investigated by personnel from this Division, such as a "milky" substance entering and discharging from the old treatment plant, were due to water-soluble oils and other waste materials from Oil Service Company.

Furthermore, you stated in our conversation that, if Mr. Harris is successful in his efforts to lease the old sewage treatment plant for pretreatment of his waste materials, a rigid monitoring program will be set up by the City of Columbia to assure compliance with pretreatment standards before any of these treated waste materials are allowed to enter the new municipal sewer system. The new sewage treatment plant has just gone on line, of course, and every effort must be made to protect it from the operational difficulties experienced by the old plant due to the introduction of oily waste materials.

We certainly appreciate your cooperation and prompt attention to this matter. If you have any questions or comments concerning this correspondence, please contact this office at your convenience. (Telephone No. 741-7391)

REFERENCE NO. 7


BLACK & VEATCH Waste Science, Inc.
Philadelphia Office

MEMORANDUM

USEPA Region IV
Treatment Plant/Oil Services Co.
Facility Status

BVWS Project 52012.545
BVWS File N
February 9, 1995
1525

To: Treatment Plant/Oil Services Co. File

From: Michael Ferrari 

On this date I spoke with Carol Shell, president of Tri-Tech Laboratories [(615) 793-7547], to try to obtain any current information regarding the current status of the Treatment Plant facility (the most recent information available in the project files was dated 1984).

According to Ms. Shell, the Treatment Plant facility was owned by a partnership between Tri-Tech Labs and Oil Services Company, and the property was sold sometime in the 1980's. Since that time, Oil Services Company moved their office to Nashville, TN, and then went out of business (quite a few years ago). To the best of her knowledge, the facility is no longer in operation.

REFERENCE NO. 8

SOURCE

Oil Service Company will accept for treatment wastes primarily from three types of sources. It is anticipated that the total flow will amount to approximately 50,000 gallons per week. Approximately 60% of the flow will be cooling water from an aluminum rolling mill, 30% will be cooling water from a screw turning and cutting operation, and 10% will be cooling water from a metal molding and plating operation.

An analysis was performed on a composite sample of the wastewater. The results are as follows:

COD, mg/l O ₂	91,800
TSS mg/l	7,920
TDS mg/l	6,000
pH, units	7.4
T.Alk., mg/l as CaCO ₃	2,100
T.Hard., mg/l as CaCO ₃	180
Oil & Grease, mg/l	50,500

* A definition of abbreviations is in the appendix.

TREATABILITY OF THE WASTEWATER

The composite sample was tested in the lab to determine treatability using physical/chemical methods. When the composite sample was allowed to stand quiescent for three days, it separated into three zones as shown in Figure A. The middle zone contained 8,700 mg/l oil and grease. Based on this analysis, it is concluded that an oil removal efficiency of greater than 82 percent can be achieved by sedimentation alone.


Various treatment process and chemicals were investigated to treat the middle zone for further reduction of oil and grease concentration. It was found that the optimum chemical for removal by sedimentation is dry alum added at the rate of 4,000 mg/l. Floc particle size progresses from very fine (0.1 mm) to large (5 mm) particles within five minutes. The settling rate is 0.14 ft./hr. After 30 minutes of settling, the oil and grease content of the supernatant is 210 mg/l. After two hours of settling, the oil and grease content of the supernatant is approximately 100 mg/l. Polymer addition decreased settling time but did not increase the removal efficiency.

An analysis was performed on the supernatant from the settled sample. The results are as follows:

TSS,	mg/l.	2.	99% Removal
Oil & Grease,	mg/l	125	99.8% Removal

As a final treatment step, the supernatant was subjected to an air stripping process. The process reduced the oil and grease concentration to 73 mg/l after 30 minutes.

FIGURE A



A sample of the oil, following treatment by primary settling, coagulation with alum, and final settling, was analyzed for heavy metals content. The metals considered were cadmium, chrome, lead, and zinc. The results of the analyses are presented in Table 1 and compared to limiting concentrations established by regulatory agencies for discharge to municipal collection and treatment systems. The concentration of heavy metals in the Oil Service wastewater effluent seems to be well below the generally accepted maximums for discharge to the municipal sewer system.

TABLE 1

HEAVY METALS CONTENT OF TREATED OIL WASTE COMPARED TO
ACCEPTABLE LIMITS FOR DISCHARGE TO MUNICIPAL TREATMENT SYSTEMS

Metal Constituent	Oil Service Co. Treated Effluent	Concentration in mg/l		
		Tenn. Dept. of Public Health Guidelines ¹	EPA Guidelines for Activated Sludge ²	Pretreatment Regulations for Electroplaters ³
Cadmium, Cd	0.02	1.0	10 - 100	.5
Total Chromium, Cr	0.2	0.5	50	--- ⁴
Lead, Pb	<0.2	1.0	0.1	.4
Zinc, Zn	0.9	2.0	.08 - 10	1.5 ⁵

¹Tennessee Department of Public Health, "Maximum Effluent Standards for Discharge of Waste into the Municipal Sewerage System."

²"Federal Guidelines, State and Local Pretreatment Programs, Volume 1," EPA-430/9-76-017a, January, 1977.

³"Electroplating Point Source Category - Proposed Pretreatment Standards for Existing Sources," EPA Proposed Regulations, Federal Register, Tuesday, February 14, 1978, for plants discharging less than 10,000 gallons per day.

⁴No standard given for total chromium.

⁵For plants discharging more than 10,000 gallons per day.

PROPOSED TREATMENT

The waste oil will be treated in the old Columbia wastewater treatment plant utilizing existing facilities to the maximum extent possible. Waste oil will be trucked to the plant where it will be discharged to the grit chamber. From the grit chamber it will be routed to one of the two primary clarifiers for an initial settling period of several days.

The float and bottoms from the initial settling period will be removed and pumped to storage vessels to await transport to an oil reclaimer. The middlings will be held in the clarifier for further treatment by coagulation with alum. The middlings will be pumped to a mixing tank where alum will be added and sufficient mixing provided to initiate flocculation.

The mixture will be transferred to the second primary clarifier for settling. The settled sludge and any float solids will be removed and pumped to storage vessels for transport to the reclaimer. The settled wastewater will be discharged from the primary clarifier to one of the trickling filters for aeration to provide further removal of oil. Trickling filter effluent will be routed to the final clarifier.

The treated wastewater will be held in the final clarifier for purposes of sampling by city officials and oil service company. The city will be notified at this time and will be provided an opportunity to sample the wastewater. Analyses of a split sample will be conducted for oil and grease and suspended solids. If the results of this analysis indicate that the waste meets the city's pretreatment requirements, the clarifier

will be drained into the municipal collection system. If initial tests indicate that the wastewater does not meet pretreatment limits for these constituents, then further treatment will be provided until the wastewater is within the desired limits. The wastewater will not be discharged to the municipal collection system until the particular batch of wastewater is inspected and approved by representatives of the City and its discharge is authorized by the City.

DEFINITIONS

COD	Chemical Oxygen Demand
TSS	Total Suspended Solids
TDS	Total Dissolved Solids
T. Alk.	Total Alkalinity
T. Hard	Total Hardness
mg/l	Milligrams per Liter
mm	Millimeter

REFERENCE NO. 9

OFFICE CORRESPONDENCE

Columbia, Missouri Co.

FROM	TO	DATE

Mr. Harris said that he was having no problems with his treatment facility. He said that he limited incoming wastes to mainly water soluble oils and that he did not accept metal plating wastes. A recent analysis of his effluent to the sewer was described by him to be:

<u>Parameter</u>	<u>Observed Value</u>	<u>City's standard as related to me by Mr. Harris</u>
O & G	36.4-53.2 ppm	100 ppm
Cu	< 0.02 ppm	1.0 ppm
Cr	< 0.05 pm	0.5 ppm
Ni	0.26 ppm	3.0 ppm
Pb	< 0.02 ppm	1.0 ppm
Zn	0.14 ppm	2.0 ppm
Cd	< 0.005 ppm	1.0 ppm

This sample analysis did not include other organics but he had mentioned to me earlier that his contract lab has screened wastes for organics before. He said that he batch discharges about once every 3-4 weeks.

R.Y.

cc: Barry Siken

[illegible]

REFERENCE NO. 10

Hawley's Condensed Chemical Dictionary

ELEVENTH EDITION

Revised by

N. Irving Sax
and
Richard J. Lewis, Sr.



VAN NOSTRAND REINHOLD
New York

ARNDT-EISSERT SYNTHESIS

Derivation: Sulfonation of naphthalene with fuming sulfuric acid at low temperature followed by separation from the 1,6-isomer.
Use: Dye intermediate.

Arndt-Eistert synthesis. Procedure for converting an acid to its next higher homolog.

"Arnel,"³⁵² TM for an acetate fiber made from cellulose triacetate. It has a higher melting point, and is less soluble than cellulose acetate.
See acetate fiber, cellulose triacetate.

"Arnox"²⁴⁵ TM for a family of 1-component liquid and solid epoxy resins designed for compression and transfer molding, injection molding, filament winding and pultrusion.

aromatic. (arene). A major group of unsaturated cyclic hydrocarbons containing one or more rings, these are typified by benzene which has a 6-carbon ring containing three double bonds. The vast number of compounds of this important group derived chiefly from petroleum and coal tar are rather highly reactive and chemically versatile. The name is due to the strong and not unpleasant odor characteristic of most substances of this nature. Certain 5-membered cyclic compounds such as the furan group (heterocyclic) are analogous to aromatic compounds. *Note:* The term "aromatic" is often used in the perfume and fragrance industries to describe essential oils which are not aromatic in the chemical sense.

aromaticity. A stable electron shell configuration in organic molecules, especially those related to benzene.
See resonance, orbital theory.

aromatization. See hydroforming.

"Aromin,"⁵¹ TM for a highly aromatic solvent widely used as a carrier for chemical pesticides.

Arrhenius, Svante. (1859-1927) A native of Sweden, he won the Nobel prize in chemistry in 1903. He is best known for his fundamental investigations on electrolytic dissociation of compounds in water and other solvents, and for his basic equation stating the increase in the rate of a chemical reaction with rise in temperature:

$$\frac{d \ln k}{dT} = \frac{A}{RT^2}$$

in which, k is the specific reaction velocity, T is the absolute temperature, A is a constant usually referred to as the energy of activation of the reaction, and R is the gas law constant.

arsacetin. (sodium acetylarsanilate; sodium p-acetyl aminophenylarsonate).
CH3CONHC6H4AsO(OH)ONa

Properties: White, crystalline powder; odorless; tasteless; free of arsenous or arsenic acid; solutions will admit of thorough sterilization. Soluble in cold water, but more so in warm water.
Use: Medicine (antisyphilitic).

arsanilic acid. (atoxylic acid; p-aminobenzene-arsonic acid; p-aminophenylarsonic acid).
C6H4.C6H4AsNO3

Properties: White, crystalline powder; practically odorless; soluble in hot water; slightly soluble in cold water, alcohol, and acetic acid; insoluble in acetone, benzene, chloroform, and ether. Mp 232C.

Derivation: By condensing aniline with arsenic acid removing the excess of aniline by steam distillation in alkaline solution and setting the acid free by hydrochloric acid.

Hazard: Yields flammable vapors on heating above melting point. A poison.

Use: Arsanilates, manufacture of arsenical medicinal compounds such as arspenamine, etc., veterinary medicine, grasshopper bait.

arsenic. As. CAS: 7440-38-2. A non-metallic element of atomic number 33, group VA of Periodic Table, aw 74.9216, valence=2,3,5; no stable isotopes.

Properties: Silver-gray, brittle, crystalline solid that darkens in moist air. Allotropic forms: black, amorphous solid (β -arsenic), yellow, crystalline solid, d 5.72 (commercial product ranges from 5.6 to 5.9), mp 814C (36 atm), sublimes at 613C (1 atm), Mohs hardness 3.5, insoluble in water, caustic and nonoxidizing acids. Attacked by hydrochloric acid in presence of oxidant. Reacts with nitric acid. Low thermal conductivity; a semiconductor.

Derivation: Flue dust of copper and lead smelters from which it is obtained as white arsenic (arsenic trioxide) in varying degrees of purity. This is reduced with charcoal. The commercial grade is not made in US.

Grade: Technical, crude (90-95%), refined (99%), semiconductor grade 99.999%, single crystals.

Hazard: Carcinogen and mutagen. TLV OSHA standard for employee exposure is 10 $\mu\text{g}/\text{m}^3$ of air. Respirators required for worker exposure to atmospheres of over 500 $\mu\text{g}/\text{m}^3$. ACGIH TLV is 200 $\mu\text{g}/\text{m}^3$ (arsenic and soluble compounds).

Uses (metallic form): Alloying additive for metals, especially lead and copper as shot, battery grids, cable sheaths, boiler tubes. High-purity (semiconductor) grade: used to make gallium arsenide

for dipoles as agent in germicides, special. See also arsenic.

arsenic acid. (CAS: 7778-3) Arsenic pentasenic acid.

Properties: White, water, alcohol, 35.5C, bp 150C. Derivation: B acid.

Grade: Pure, Use: Manufacture of wood treating desiccant for

arsenical Babbitt

arsenical nickel

arsenic anhydride

arsenic, black.

arsenic bromide bromide.

arsenic chloride

arsenic disulfide; red arsenic; red arsenic).

AsS. Occ Properties: Oxidizing and alkalies, mp 307C.

Deviation: By nitrites and sub Grade: Techn Use: Leather industry, shot residue, taxidermy

arsenic hydride

arsenic pentafluoride -52.8C, f.p. -105C, in alcohol and Use: Doping agent

arsenic pentasulfide Properties: Yellow, nitric acid decomposes to heated.

Derivation: By a hydrochloric fide. It is flammable

and to prepare cul-
arch.

An English born
of the Nobel prize
1979. Via his work
covered new routes
is selectively. His
and disjointed as
nces and the eco-
Os. He eventually
iversity of Chicago.
pounds with dibo-
resis. The bulk of
Purdue University.

tinuous zigzag mo-
lloidal suspension,
e motion is caused
of the liquid upon
d after the British
rst noted this phe-

reaction).
ely evaluated se-
occurring without
ring heat exposure
rates (usually sug-
during storage. It
olor change of bak-
gins with an aldol
ing the carbonyl
ds with formation
e dark brown colo-
the reaction is ac-
flavor and texture
It was first noted
ard.

ed).
 $N_2 \cdot 2HOH$ or

kaloid; very bitter
p 178C; soluble in
ene; slightly solu-
and ethyl acetate.
chlonide, and ni-
ble as the sulfate.
subsequent crystal-
gnatia seeds.
on and inhalation.
ant additive, sepa-

1317-43-7.
esium hydroxide.
ay, greenish; luster
s hardness 2.5.
on, Canada.

"Brush-Rhap"²⁸⁶. TM for butyl and 2-ethylhexyl
esters or amine salts of 2,4,5-trichlorophenoxy-
acetic acid. Available in various concentrations
of active ingredient and in combination with es-
ters of 2,4-dichlorophenoxyacetic acid.
Used as a herbicide.

"BRV"⁵⁰. TM for a heavy, high-boiling coaltar
distillate.

Properties: Dark, coal-tar oil, d 1.14-1.18 (25/
25C). Engler specific viscosity 5-10 (50C), distil-
lation 26% max at 355C. Combustible.

Use: Rubber plasticizer, softener, and reclaiming
oil; dispersing agent.

"Brymul"⁵¹. TM for an emulsifiable grade of
cleaner for general use on metals, etc. Contains
Stoddard-type solvent.

Hazard: Moderate fire risk.

"Bryton"⁵⁴. TM for a series of oil-soluble petro-
leum sulfonates

Use: Detergent dispersants, rust-inhibiting agents,
and alkaline carriers and as additives to motor
oils and diesel fuels.

B-stage resin. (resitol). A thermosetting phe-
nolformaldehyde type resin which has been ther-
mally reactive beyond the A-stage so that the
product has only partial solubility in common
solvents (alcohols, ketones) and is not fully fusi-
ble even at 150-180C. The B-stage resin has lim-
ited commercial use.

BT. (*Bacillus thuringiensis*). A species of bac-
teria used as a pesticide for agricultural crops.
It is of the stomach-poison type and has been
approved for commercial use.

"BTC"³²⁸. TM for a series of cationic quaternary
ammonium chlorides generally alkyltrimeth-
ylbenzylammonium chloride.

Use: Disinfectant, deodorant, germicide, fungi-
cide, algicide, slimicide.

BTDA. See 3,3',4,4'-benzophenone tetracarbox-
ylic dianhydride.

Btu. (British thermal unit). The quantity of
heat required to raise the temperature of one
pound of water one degree Fahrenheit (usually
from 39 to 40F). This is the accepted standard
for the comparison of heating values of fuels.
For example, fuel gases range from 100 (low pro-
ducer gas) to 3200 (pure butane) Btu per cu ft.
The usual standard for a city gas is approxi-
mately 500 Btu.

BTX. Commercial abbreviation for benzene, to-
luene, xylene, the three major aromatic com-
pounds.

Bu. Informal abbreviation for butyl.

bubble cap column. See tower, distillation.

Bucherer reaction. A procedure for preparation
of β -naphthylamine by heating β -naphthol with
a water solution of ammonium sulfite. "A sulfite
solution is prepared by saturating concentrated
ammonia solution with sulfur dioxide and adding
an equal volume of concentrated ammonia solu-
tion, β -naphthol is added and the charge is
heated in an autoclave provided with a stirrer
or a shaking mechanism." (L.F. Fieser) This re-
action is also involved in the preparation of sev-
eral azo dye intermediates, e.g., Tobias acid.

Bucherer-Bergs reaction. Preparation of hydan-
toin from carbonyl compound by reaction with
potassium cyanide and ammonium carbonate, or
from the corresponding cyanohydrin and ammo-
nium carbonate.

Bucherer carbazole synthesis. Formation of car-
bazoles from naphthols, or naphthylamines, aryl
hydrazines, and sodium bisulfite.

Buchner-Curtius-Schlotterbeck reaction. For-
mation of keto compounds from aldehydes and
aliphatic diazo compounds; ethylene oxides may
also be formed.

Buchner, Eduard. (1860-1917) A German chem-
ist who was awarded the Nobel prize for chem-
istry in 1907. His works included the syn-
thesis of diiodoacetamid, alcoholic fermentation
caused by enzymes, as well as the discovery of
zymase, the first enzyme to be isolated. He re-
ceived his PhD at the University of Munich,
where he became a lecturer. Later, he taught
and performed research at Tubingen, Berlin, and
Wurzburg.

Buchner method of ring enlargement. Diazo-
acetic acid ester reacts with benzene and homo-
logs to give the corresponding esters of noncara-
dienic acid, transformed at high. temperatures
to derivatives of cycloheptatriene, phenylacetic
acid and β -phenylpropionic acid (when one or
more methyl groups are present in the initial
hydrocarbon).

bucizine hydrochloride. $C_{28}H_{33}ClN_2 \cdot 2HCl$.
1-p-chlorobenzhydryl-4-(p-(tert)-
butylbenzyl)piperazinedihydrochloride.
Use: Medicine (antihistamine).

bucket elevator. See conveyor (5).

ELECTROPLATING

sions can be filtered by means of forced flow electrophoresis.

Electrophoresis is important in the study of proteins because the molecules of such materials act like colloidal particles and their charge is positive or negative according to whether the surrounding solution is acidic or basic. Thus, the acidity of the solution can be used to control the direction in which a protein moves upon electrophoresis. It has been found that electrophoresis can be carried out more efficiently under zero gravity conditions in outer space than on Earth. See also electrodeposition.

electroplating. The deposition of a thin layer of coating of metal, (e.g., chromium, nickel, copper, silver, etc.) on an object by passing an electric current through an aqueous solution of a salt containing ions of the element being deposited, for example, Cu^{++} . The material being plated (usually a metal but often a plastic) constitutes the cathode. The anode is often composed of the metal being deposited; ideally it dissolves as the process proceeds. The thin layer deposited is sometimes composed of two or more metals, in which case it is an alloy. The solution or plating bath contains dissolved salts of all the metals being deposited. Electrolytic cells are used for this process.

The anode must be an electrical conductor but may or may not be of the same chemical composition as the material being deposited, and may or may not dissolve during the process. The purpose of electroplating is usually protection of the base metal from corrosion. Silver is electroplated on copper for economy reasons; plastics may be electroplated for decorative effects.

See also electrophoresis, protective coating, electrodeless coating, throwing power, current density.

electropolishing. A nonmechanical method of polishing metal surfaces by a method that is actually the reverse of electroplating. This is achieved by making the object to be polished the anode in an electrolytic circuit, the cathode usually being carbon. The electrolytes used are phosphoric, hydrofluoric, nitric, or sulfuric acids (sometimes called polishing acids).

electrostatic bond. Alternative name for an ionic bond.
See bond, chemical.

electrostatic coating. A metal painting technique in which electrostatically charged pigment particles are sprayed onto a substrate metal followed by baking. The electric charge attracts the particles to the metal and holds them in place until heat treatment is applied. Maintenance of the

charge is thus essential; factors affecting this are relative humidity (the lower the better) and the chemical nature of the pigment, e.g., phthalocyanine blue retains the charge much longer than titanium dioxide.

electrostatic precipitator. See Cottrell.

electrovalent bond. Alternative name for an ionic bond.

See bond, chemical.

electrowinning. The technique of extracting a metal from its soluble salt by an electrolytic cell. It is used in recovery of zinc, cobalt, chromium, and manganese, and has recently been applied to copper when in the form of a silicate ore. For any specific metal, the salt in solution is subjected to electrolysis and is electrodeposited on a cathode made of the metal being extracted.

element. One of the 109 presently known kinds of substances that comprise all matter at and above the atomic level. According to a theory that has gained acceptance, the lightest elements were formed in less than half an hour from a primordial complex called ylem, a mixture of neutrons and electromagnetic radiation. The smallest unit of any element is the atom. All the atoms of a given element are identical in nuclear charge and number of electrons and protons, but they may differ in mass, e.g., hydrogen has mass numbers of 1, 2, and 3, called hydrogen, deuterium, and tritium, respectively. These are the isotopes of hydrogen; most elements have isotopic forms which are due to the presence of one or more extra neutrons in the nucleus. The atomic number of an element indicates its position in the Periodic Table and represents the number of protons present, which is the same as the number of electrons.

All elements heavier than lead are unstable and radioactive. About 90% of the earth's crust is made up of elements with even numbers of protons and neutrons. No stable elements heavier than nitrogen have an odd number of both protons and neutrons. Elements of even atomic number normally have several isotopes while those of odd atomic number never have more than two stable isotopes. All elements beyond uranium (transuranic) were nonexistent in 1940. They are artificially created by bombardment of other elements with neutrons or other heavy particles. Research on new elements is actively carried on at the Lawrence Livermore Laboratories which reported discovery of Element 106 in 1974. Creation of Element 109 was announced in 1982. A single atom of it was made by West Germany physicists by bombarding Bi-209 with Fe-58 nu-

clei. Many more (possibly) are theoretically possible according to the laws of physics. See also Periodic Table, abundance. *Note:* For origin of elements, see cosmogenesis.

elemi. A soft, balsam-like tree in the Philippines, so called because it contains carbon, but not in petrol and ketones.

Use: Plasticizer, adhesives, inks, textile and paper, waterproofing, engraving.

"Elprene."TM for a sealer coating of the neoprene maintenance coating.

Eltekoff reaction. Production of hydrocarbons by methylation of methyl chloride or methyl iodide of lead oxide or calcium nitrate.

elutriation. A process of separating and settling which separates finely divided solid into fractions of different weight. It is especially used in the separation of pigments, clay dyes, etc.

"Elvace."TM for a sealer emulsions.

"Elvanol."TM for a sealer alcohol.

"EMA" Resins.TM for a sealer copolymers. They serve as dispersing agents, thickeners, binders, etc.

embosser. See fiber roller.

embrittlement. Hardening of steel or of an ABS plastic which impairs its strength and imparts brittleness. In metals, the process is due to hydrogen, though in plastics it is also involved. Such as ABS resins, the embrittlement of a vitreous material due to the butadiene embrittlement due to pressurized-water rupture of reactor walls or of trouble in reactor

and formaldehyde in

granular, freely flowing
odor. Insoluble in dilute
hot ether, and water.
ang resin, antacid.

D. A synthetic
ebacic acid and hydra-
nts of acetamide. Poly-
iazide is a specific ex-

TM for low molecu-
era based on butadiene
hydroxyl functionality.
omers and terpolymers.
ober products, coatings,

($C_{12}H_8N_2$).
igned for high tempera-
applications. Reputed to
up to 260°C for 1000

of diphenyl isophtha-
zidine.
hesives (high adhesion
um, and aluminum al-
materials.

in any proportion of
mers (natural or syn-
and a copolymer, or
ample of (1) is rubber-
ber and butadiene-sty-
re of butadiene-acrylo-
prene. A polyblend is
its components have
as is different from a
by chemical combina-

olymer, blend.

thermoplastic poly-
g 1,3-butadiene with
talic catalyst (butyl
lysts such as titanium
n iodide may be used.
milar to natural rub-
due to its abrasion
low heat build-up.
ed as blends in SBR
sembles gutta percha
liquid polybutadiene,
has special uses as
with organic perox-

Hazard (liquid): By ingestion and inhalation; skin
irritant.

See also polymer, stereospecific.

polybutene. See polybutylene.

polybutylene. (polybutene; polyisobutylene;
polyisobutene). Any of several thermoplastic
isotactic (stereo-regular) polymers of isobutene
of varying molecular weight, also polymers of
butene-1 and butene-2. Butyl rubber is a type
of polyisobutene to which has been added 2%
of isoprene, which provides sulfur linkage sites
for vulcanization. Isobutene can be homopoly-
merized to various degrees in chains containing
from 10 to 1000 units, the viscosity increasing
with molecular weight. Combustible.

See also "Vistanex."

Use: Lubricating-oil additive, hot-melt adhesives,
sealing tapes, special sealants, cable insulation,
polymer modifier, viscosity index improvers,
films and coatings.

polybutylene terephthalate. An engineering plas-
tic derived from 1,4-butanediol, it is a thermo-
plastic polyester with a broad spectrum of uses.

"Polycarbafil."⁵³⁹ TM for a glass fiber-reinforced
polycarbonate.

polycarbonate. $(COOC_6H_5C(CH_3)_2C_6H_5O)_n$.

A synthetic thermoplastic resin derived from bis-
phenol A and phosgene, a linear polyester of
carbonic acid: Can be formed from any dihy-
droxy compound and any carbonate diester, or
by ester interchange. Polymerization may be in
aqueous emulsion or in nonaqueous solution.

Properties: Transparent (90% light transmission),
noncorrosive, weather and ozone-resistant, non-
toxic, stain-resistant. Combustible but self-extin-
guishing, low water absorption, high impact
strength, heat-resistant, high dielectric strength,
dimensionally stable, soluble in chlorinated hy-
drocarbons and attacked by strong alkalis and
aromatic hydrocarbons, stable to mineral acids,
insoluble in aliphatic alcohols. Excellent for all
molding methods, extrusion, thermoforming etc.;
easily fabricated by all methods including ther-
moforming and fluidized bed coating.

Use: Molded products, solution-cast or extruded
film, structural parts, tubes and piping, pros-
thetic devices, meter face plates, nonbreakable
windows, street-light globes, household appli-
ances.

polycarboxylic acid. An organic acid containing
two or more carboxyl (COOH) groups.

polychlor. General name for synthetic chlori-
nated hydrocarbons.

Use: Pesticides.

polychlorinated biphenyl. (PCB).

CAS: 1336-36-3. One of several aromatic
compounds containing two benzene nuclei with
two or more substituent chlorine atoms. They
are colorless liquids with d 1.4-1.5. Because of
their persistence, toxicity, and ecological damage
via water pollution their manufacture was dis-
continued in the US in 1976.

Hazard: Highly toxic.

polychloroprene. See neoprene.

polychlorotrifluoroethylene. (PCTFE).
See chlorotrifluoroethylene polymer.

"Polycin."²⁰² TM for (1) an elastic, tacky, gel-
like solid resulting from the polymerization of
castor oil, used in rubber compounding, floor
tile manufacture, and as a polymeric plasticizer;
(2) a series of polyols used in the preparation
and curing of urethane polymers for protective
coatings, foamed insulation, and elastomers.

"Polyco."⁶⁵ TM for a series of thermoplastic
polymers in the form of water emulsions or sol-
vent solutions, applied to vinyl acetate polymers
and copolymers, butadiene-styrene copolymer
latics, polystyrenes, vinyl and vinylidene chloride
copolymers, acrylic copolymers and water-solu-
ble polyacrylates.

Use: Adhesives and coatings, in paint, leather, tex-
tiles, paper, cosmetics, and construction fields.

polycondensation. See condensation (1), polymer-
ization.

polycoumarone resin. See coumarone-indene
resin.

polycyclic. An organic compound having three
or more ring structures, which may be the same
or different, e.g., anthracene, naphthalene.
See polynuclear.

poly(1,4-cyclohexylenedimethylene)terephthalate.

TM "Kodel." A linear polyester film or fiber
obtained by condensation of terephthalic acid
with 1,4-cyclohexanedimethanol. It has good
electrical resistivity and hydrolytic stability.

Use: Carpet fibers and chemically resistant films.
See also terephthalic acid.

"Polycyclol 1222."²¹⁴ TM for an intermediate for
the preparation of alkyd-type resins used for
coatings. These are known by the coined name
"cyclodyd."

poly-1,1-dihydroperfluorobutyl acrylate.

Properties: White, rubber-like polymer. D 1.5, be-

1,1,1-TRICHLOROETHANE

Use: Bacteriostat in soaps and detergents, plastics.

1,1,1-trichloroethane. (methyl chloroform).

CAS: 71-55-6. CH_2CCl_3 .

Properties: Colorless liquid, d 1.325, bp 75C, fp -38C, insoluble in water, soluble in alcohol and ether, flash p none. Nonflammable.

Hazard: Irritant to eyes and tissue. TLV: 350 ppm in air.

Use: Solvent for cleaning precision instruments, metal degreasing, pesticide, textile processing.

1,1,2-trichloroethane. (vinyl trichloride;

β -trichloroethane). CAS: 79-00-5.

$\text{CHCl}_2\text{CH}_2\text{Cl}$.

Properties: Clear, colorless liquid, characteristic sweet odor, bp 113.7C, d 1.4432 (20C/4C), refr index 1.4458, vap press 16.7 mm (20C), bulk d 12.0 lbs/gal (20C), fp -36.4C, flash p none. Miscible with alcohols, ethers, esters and ketones; insoluble in water. Nonflammable.

Grade: Technical.

Hazard: Irritant, absorbed by skin. TLV: 10 ppm in air.

Use: Solvent for fats, oils, waxes, resins, other products; organic synthesis.

trichloroethanol. CAS: 115-20-8.

$\text{CCl}_3\text{CH}_2\text{OH}$.

Properties: Viscous liquid, ether-like odor, hygroscopic. Slightly soluble in water, miscible with alcohol, ether, and carbon tetrachloride. Bp 150C, fp 13C, d 1.541 (25/4C). Combustible.

Use: Intermediate, anesthetic.

trichloroethylene. (tri). CAS: 79-01-6.

$\text{CHCl}:\text{CCl}_2$.

Properties: Stable, low-boiling, colorless, photo-reactive liquid; chloroform-like odor; will not attack the common metals even in the presence of moisture. Bp 86.7C, fp -73C, d 1.456-1.462 (25/25C), refr index 1.4735 (27C), miscible with common organic solvents, slightly soluble in water. Nonflammable.

Derivation: From tetrachloroethane by treatment with lime or alkali in the presence of water, or by thermal decomposition, followed by steam distillation.

Grade: USP, technical, high purity, electronic, metal degreasing, extraction.

Hazard: Toxic by inhalation. Use as solvent not permitted in some states. FDA has prohibited its used in foods, drugs, and cosmetics. TLV: 50 ppm in air.

Use: Metal degreasing; extraction solvent for oils, fats, waxes; solvent dyeing; dry cleaning; refrigerant and heat exchange liquid; fumigant; cleaning and drying electronic parts; diluent in paints and adhesives; textile processing; chemical intermedi-

ate; aerospace operations (flushing liquid oxygen).

trichlorofluoromethane. (fluorotrichloromethane; fluorocarbon-11). CAS: 75-69-4.

CCl_3F .

Properties: Colorless, nearly odorless, volatile liquid. Bp 23.7C, fp -111C, d 1.494 (17.2C), critical pressure 43.2 atmospheres. Noncombustible.

Derivation: From carbon tetrachloride and hafnium, in the presence of fluorinating agents such as antimony tri- and pentafluoride.

Grade: Technical, 99.9% min.

Hazard: TLV: CL of 1000 ppm in air.

Use: Solvent, fire extinguishers, chemical intermediate, blowing agent.

trichloroisocyanuric acid. (1,3,5-trichloro-s-triazine-2,4,6-trione). CAS: 87-90-1.

$\text{OCN}(\text{Cl})\text{NC}(\text{Cl})\text{NC}(\text{Cl})$.

Properties: White, slightly hygroscopic, crystalline powder or granules; loose bulk d 31 lbs/cu ft, granular 60 lbs/cu ft; available chlorine 85%; decomposes 225C.

Hazard: Fire risk in contact with organic materials, strong oxidizing agent. Toxic by ingestion.

Use: Active ingredient in household dry bleaches, dishwashing compounds, scouring powders, detergent-sanitizers, commercial laundry bleaches, swimming pool disinfectant, bactericide, algicide, bleach, and deodorant.

trichloroisopropyl alcohol. See isopral.

trichloromelamine. ($\text{N},\text{N}',\text{N}'$ -trichloro-2,4,6-triamine-1,3,5-triazine).

$\text{NC}(\text{NHCl})\text{NC}(\text{NHCl})\text{NC}(\text{NHCl})$.

Properties: Fine, white powder, slightly soluble in water and glacial acetic acid, insoluble in carbon tetrachloride and benzene, pH of saturated aqueous solution 4, autoign temperature 320F (160C).

Derivation: By chlorination of melamine.

Grade: 89% available chlorine.

Hazard: Dangerous fire risk, can ignite spontaneously in contact with reactive organic materials.

Use: Chlorine bleach and bactericide.

trichloromethane. See chloroform.

α -(trichloromethyl)benzyl acetate. See trichloromethylphenylcarbinyl acetate.

trichloromethyl chloroformate. (diphosgene).

ClCOOCCl_3 .

Properties: Colorless liquid; odor similar to phosgene (new mown hay); decomposed by heat, po-

rous substances, action of phosgene), a soluble in alcohol, l (15C), bp 127-128C (air = 1), refr index 1.41.

Derivation: (a) By chlorination of benzene; (b) by chlorinating both methods the n is then separated by distillation.

Grade: Technical.

Hazard: Toxic by inh. irritant to tissue.

Use: Organic syntheses.

trichloromethyl ether.

Properties: Liquid; bp 130-132C; soluble in ether; insoluble in water.

Hazard: Strong irritant; lachrymatory fumes.

N-(trichloromethyl)melamine. See captan.

trichloromethylphenyl.

(α -[trichloromethyl]benzyl). CAS: 90-17-5. $\text{C}_6\text{H}_5\text{CH}_2\text{CCl}_3$.

Properties: White, crystalline solid; odor; mp 86-88C; soluble in alcohol.

Use: Perfumes, fixatives, fumes.

trichloromethylphosphite. $\text{CCl}_3\text{PO}(\text{OH})_2$.

Properties: Soluble in benzene and hexane.

Use: Catalyst and reagent.

1,1,1-trichloro-2-methylbutanol.

trichloromethylsulfur methyl mercaptan. CISCCl_3 .

Properties: Yellow, oily liquid.

Mildly decomposed by action of oxidizing agents, etc. D 1.722 (20C), vap d 6.41 (20C), insoluble in water.

Supports combustion.

Derivation: Chlorination of phosphine, or methylation of phosphoric acid.

Grade: Technical.

Hazard: Toxic by inh. irritant to eyes and skin.

Use: Organic synthesis.

6

REFERENCE NO. 11


BLACK & VEATCH Waste Science, Inc.
Philadelphia Office

MEMORANDUM

USEPA Region IV
Treatment Plant/Oil Services Co.
Facility Status (2)

BVWS Project 52012.545
BVWS File N
February 10, 1995
0935

To: Treatment Plant/Oil Services Co. File

From: Michael Ferrari 

On this date I spoke with Jim Smith (JS), Wastewater Treatment Coordinator at the City of Columbia [(615) 388-2419], regarding the past practices and the current status of the Treatment Plant facility.

The former City of Columbia Wastewater Treatment Plant has not been in operation since the late 1980's. When the facility was in operation, there were holding tanks used in the separation processes. Since the closing of the facility, the tanks have been either filled with concrete or completely removed. In addition, all buildings previously located onsite have been removed.

There has not been any testing at the site since its closing. Currently, the land at the former facility is not being used.

REFERENCE NO. 12


BLACK & VEATCH Waste Science, Inc.
Philadelphia Office

MEMORANDUM

USEPA Region IV
Treatment Plant/Oil Services Co.
Columbia Power & Water Service Area

BVWS Project 52012.545
BVWS File N
February 13, 1995
1000

To: Treatment Plant/Oil Services Co. File

From: Michael Ferrari 

On this date I spoke with Kelly Powell (KP), Water Superintendent for Columbia Power & Water (CPW) in Columbia, Tennessee [(615) 388-4833], regarding their service area and surface water intakes.

KP said that CPW currently has approximately 15,500 connections, and they obtain all of their water from one intake on the Duck River. The intake is located at mile 134 on the Duck River, which is approximately 1 mile upstream from the Treatment Plant facility. KP said that there are four suppliers of water throughout Maury County, but CPW is the only supplier for the City of Columbia and the surrounding area.

According to KP, very few people in the Columbia area obtain their drinking water from private wells. He also confirmed that recreational boating and fishing is very common in the Duck River in the Columbia area.


REFERENCE NO. 13

**STATE OF TENNESSEE
DEPARTMENT OF CONSERVATION
DIVISION OF GEOLOGY**

REPORT OF INVESTIGATIONS No. 4

**GROUND WATER IN THE CENTRAL BASIN
OF TENNESSEE**

A Progress Report
By
ROY NEWCOME, JR.



Prepared in cooperation with the U. S.
Geological Survey

**NASHVILLE, TENNESSEE
1958**

GEOLOGY

Structure of the Rocks

Physiographically, the Central Basin is the result of erosion of a low structural dome whose crest is in southern Rutherford County. The dome represents the southern end of the Cincinnati Arch, an elongated area of upwarped rocks extending northward through Central Kentucky into Ohio and Indiana. During the upwarping and doming the rocks at the crest of the dome were stretched, resulting in the formation of joints. The weakened carbonate rocks were readily subject to solution and erosion, with the result that a topographic basin now occupies the top of the structural dome.

Although jointing is a prominent feature of Central Basin rocks, there is little evidence of differential movement along the joints. The formations lie in the same relative positions in which they were deposited. Minor folding of the rocks is not unusual, but it is of a local nature only.

Rock Formations of the Central Basin

The rock formations of the Central Basin are almost entirely limestones of Ordovician age. They differ greatly in color, texture, and chemical purity. Erosion of the structural dome has resulted in the exposure of concentric rings of progressively younger rocks as distance from the center of the Central Basin increases. The formations dip away from the center at about 15 feet per mile.

The oldest rocks exposed are those of the Murfreesboro limestone, which consists of about 400 feet of fine-grained bluish-gray limestone. The upper 100 feet of the Murfreesboro has been removed at the locality of deepest erosion. The youngest rock exposed that is of hydrologic significance in the basin is the Catheys limestone. Outcrops of formations younger than the Catheys are restricted largely to the hills that remain as erosional remnants of the Highland Rim Plateau.

Between the Murfreesboro and Catheys limestones is approximately 500 feet of limestone of six formations, as represented in the accompanying columnar section. (See table 1.) C. W. Wilson, Jr., (1949) has described in detail the stratigraphy of Central Tennessee.

GROUND WATER

Occurrence

An evaluation of the water-yielding properties of the rock formations of the Central Basin should consider two important factors, depth and solubility of the rocks. Nearly all the ground water in the region is contained in cavities formed, or enlarged, by solution of the limestone. These cavities, termed "solution channels," had their origin, for the most part, in openings along joints and bedding planes, through which water was provided relatively easy access to the rocks below the land surface. With such a start, water containing carbonic and organic acids derived from the air or leached from the soil has formed by solution of the limestone a network of water-carrying subterranean channels which are common in limestone regions.

Solution of the rocks has not progressed everywhere at the same rate nor to the same extent. The composition of the rocks greatly affects the rate of solution. Generally, the purer limestones are more easily dissolved than rocks containing appreciable amounts of nearly insoluble silty and clayey material, especially those in which the insoluble material is concentrated in layers.

Solution proceeds more slowly as depth increases. Crevices, that are open and of appreciable size near the surface, become less pronounced with depth, owing both to the less severe stretching undergone by the deeper rocks at the time of uplift and to the weight of overlying rocks. In most places in the basin substantial solution has not progressed beyond a depth of 300 feet. Records of the depth or depths of occurrence of water in 650 wells, totaling 700 occurrences, show that 75 percent of the water-bearing openings occur at depths of less than 100 feet and 90 percent at depths of less than 300 feet.

Water-Yielding Properties of the Rocks

The results of this study indicate that the individual rock formations of the Central Basin differ in their ability to transmit and yield water. Information on these differences, together with information on the thickness of the rocks and the areal distribution of their outcrops and on the topography, forms the basis for a prediction of the ground-water prospects and the maximum feasible depth of drilling at any specific locality.

Many wells in the Central Basin have been drilled several hundred feet below the depth at which water could reasonably be expected.

TABLE 1.-STRATIGRAPHIC SECTION OF THE CENTRAL BASIN OF TENNESSEE

System	Group	Formation	Approx. Thickness (feet)	Remarks
ORDOVICIAN	Richmond	Squatashie, Fennelle and Mannie formations. (Orh)	0-75	Squatashie: Greenish-gray mudstone. Fennelle: Coarse-grained varicolored limestone. Mannie: Varicolored shale.
	Mayville	Leipers limestone (Ol)	0-100	Dark-gray fine- to medium-grained limestone. Thin to medium bedded. Locally phosphatic.
		Cathys limestone (Ocy)	50-200	Dark-blue fine- to coarse-grained limestone. Thin to medium bedded. Phosphatic in places.
	Nashville (Trenton)	Bigby-Cannon limestone (Oby-Ocn)*	50-100	Bigby facies and Cannon facies intergrade laterally. Bigby: Blue medium-grained phosphatic limestone. Cannon: Gray fine- to medium-grained limestone. Light-gray dense limestone termed "Dove" occurs as lentils interbedded with Bigby and Cannon facies.
		Hermitage formation (Oh)	60-100	Dark-blue fine-grained argillaceous limestone. Lower part thinly laminated with shale partings.
		Carters limestone (Oc)	65	Light-brown dense limestone. Contains thin bentonite beds. Thin bedded near top, massive below. Dolomitic in places.
	Stones River	Lebanon limestone (Olb)	115	Bluish-gray fine-grained thin- to medium-bedded limestone with thin shale partings.
		Ridley limestone (Or)	105	Light-gray dense, massive limestone.
		Pierce limestone (Op)	25	Gray medium- to coarse-grained silty limestone.
		Murfreesboro limestone (Om)	420	Blue and brown fine-grained limestone.
		Wells Creek dolomite	0-75	Silty dolomite and dolomitic limestone. Usually green owing to presence of glauconite.
		Knox dolomite (O-Clk)	5,000±	Gray and brown fine-grained to granular dolomite and dense white limestone. Chert common.

CAMBRIAN
AND
ORDOVICIAN

*The classification of the Bigby-Cannon limestone in this report is in accord with recent published reports and usage by the Tennessee Division of Geology, but it does not coincide with the classification used by the U. S. Geological Survey.

On the other hand, probably even more wells have been stopped and abandoned when there was still a good chance for obtaining water at greater depth. In situations of both types adequate geologic information might have aided in securing adequate water supplies at reasonable cost.

The following discussion of the water-yielding properties of each formation is based on the available well records and on observations made at wells for which detailed records were not available.

All chemical analyses listed in this report were made by D. F. Farrar, Chemist, Tennessee Division of Geology.

KNOX DOLOMITE (Oek)

The Knox dolomite contains the oldest sedimentary rocks underlying the Central Basin. It is not exposed, its nearest approach to the surface being to within about 300 feet in Rutherford County near Murfreesboro and Lascassas where the Murfreesboro limestone crops out. One well drilled through the Knox in Giles County penetrated approximately 5,000 feet of limestone and dolomite before reaching granite.

Records indicate that the upper 100 feet of the Knox dolomite can be depended upon to yield water to wells. A study of 88 wells penetrating the Knox dolomite shows that water was obtained in the upper 20 feet of the Knox in 52 wells. It was obtained in the upper 50 feet of the Knox in 71 wells. Thus, in more than 80 percent of the wells, water was obtained from zones in the upper 50 feet of the Knox. In many wells water was obtained at two or more levels.

It is difficult to correlate the levels at which water occurs in the Knox dolomite. In some wells water is found at the very top of the Knox, whereas in others less than a mile distant it may be necessary to drill 50 feet or more into the Knox. The upper part of the Knox contains dolomite of several types (coarse granular, silty saccharoidal, dense) along with irregularly spaced beds of very dense light-colored limestone. Water is rarely obtained from the limestone but may be found in any of the dolomitic types, apparently without regard to the lithology. The way in which the water-bearing zones originated is not known, but their existence, in many places more than 400 feet below the depth to which solution normally takes place, points to hydrologic conditions different from those encountered in the overlying formations.

Water from the Knox dolomite varies both in quantity and in quality. In many wells water from younger strata is not cased off, making it very difficult to estimate the yield of the Knox. However, a comparison of the yields of 40 wells penetrating the Knox dolomite shows that 8

TABLE 2.—CHEMICAL ANALYSES OF WATER FROM WELLS IN THE KNOX DOLOMITE (parts per million)

County	Well No.	Iron (Fe)	Calcium (Ca)	Magnesium (Mg)	Sodium (Na)	Carbonate (CO ₂)	Bicarbonate (HCO ₃)	Sulfate (SO ₄)	Chloride (Cl)	Fluoride (F)	Dissolved solids	Hardness as CaCO ₃
BEDFORD	3	0.3	132	10	51	0	254	156	78	4.0	583	370
DAVIDSON	5	.1	371	12	708	0	466	576	1,180	4.5	3,250	975
DAVIDSON	8	.2	122	12	14	0	290	95	21	4.5	576	353
DAVIDSON	17	.2	158	32	147	27	314	282	227	4.0	1,160	593
DAVIDSON	37	.3	462	32	1,450	0	390	823	2,230	2.0	5,440	1,280
DAVIDSON	61	.5	386	6	395	14	246	751	699	2.0	2,350	918
DAVIDSON	125	.2	194	8	153	0	332	242	236	2.3	1,000	517
GILES	4	.6	285	10	326	19	304	453	862	3.0	1,770	752
GILES	16	.3	746	21	1,913	0	308	1,670	2,940	3.0	7,940	1,950
JACKSON	9	.8	469	10	1,040	0	398	936	1,640	3.0	4,520	1,250
MARSHALL	3	.2	204	24	129	0	322	311	198	3.0	1,060	606
MAURY	3	.1	145	4	37	0	316	111	67	4.8	538	379
MAURY	21	1.0	114	6	6	12	208	123	10	3.8	426	309
RUTHERFORD	42-1	.2	304	12	460	0	290	529	706	4.0	2,220	808
RUTHERFORD	42-2	.1	258	5	322	18	258	457	496	3.5	1,820	665
RUTHERFORD	70	.1	94	3	18	0	253	28	23	4.0	373	247
SUMNER	1	.8	590	39	1,660	47	340	1,260	2,550	3.5	6,580	1,630
WILLIAMSON	2	.2	292	12	116	18	268	498	178	3.5	1,410	778
WILLIAMSON	3-2	.2	172	8	16	29	264	187	25	3.0	634	462
WILLIAMSON	5	.1	138	4	32	0	270	146	49	3.0	603	381
WILLIAMSON	6	.3	155	11	23	10	320	12	35	3.0	528	304
WILLIAMSON	8-1	.2	164	12	34	0	330	153	53	4.8	630	435
WILLIAMSON	8-2	.2	134	9	12	0	286	108	18	3.8	450	371
WILLIAMSON	10	.4	138	23	83	21	204	225	127	3.0	722	437
WILLIAMSON	11	.4	324	22	41	22	300	542	63	4.6	1,180	898
WILLIAMSON	12	.1	182	12	64	0	378	204	99	4.5	790	528
WILLIAMSON	13	.2	23	74	9	0	250	153	14	4.0	482	362
WILLIAMSON	14	.3	136	16	23	14	278	144	35	4.0	556	404
WILLIAMSON	32	.4	132	3	4	0	324	70	5	3.5	374	312
WILLIAMSON	50	.2	214	7	9	0	336	280	14	4.8	708	563

s yielded less than 1 gallon per minute (gpm), 25 wells yielded 1 gpm, 5 wells yielded 6 to 10 gpm, and only 2 wells yielded more than 10 gpm. Probably none of the water-bearing zones in the Knox yields more than 15 gpm to a well.

The quality of water obtained from wells in the Knox dolomite depends largely upon well location; those wells near the center of the basin yield water of better quality than do wells near the margin. The amount of dissolved mineral matter in water from the Knox is seldom more than 500 parts per million (ppm) and it often exceeds 1,000 ppm. The greatest concentration of wells yielding water from the Knox dolomite is in northern Williamson County and southern Davidson County. In that area 13 wells yield water ranging from 500 to 2,500 ppm in dissolved-solids content.

The fluoride content of water from 35 wells yielding water from the Knox dolomite in Bedford, Davidson, Giles, Marshall, Maury, Rutherford, and Williamson Counties ranged from 2 to 6.5 ppm. In view of the fact that continual use of water having fluoride in excess of 1.5 ppm may cause mottled enamel on children's teeth (Dean, 1936), it may be desirable to have fluoride tests made before using water from these wells.

WELLS CREEK DOLOMITE

Directly overlying the Knox dolomite is the easily drilled, very silty dolomite and dolomitic limestone of the Wells Creek dolomite. It is not exposed at the surface but is usually conspicuous in well cuttings because of the striking green color imparted to the rock by the mineral glauconite. In places glauconite is absent from part or all of the unit, and in those places the rock is similar in color to the underlying Knox. The Wells Creek dolomite ranges in thickness from less than 5 feet in the eastern part of the Central Basin to 80 feet in the west. It is not known to yield water to wells in the Central Basin.

MURFREESBORO LIMESTONE (Om)

Although the Murfreesboro limestone is 400 feet thick and contains many easily dissolved beds, the formation in most places is a poor source of water. This probably is due to the Murfreesboro being covered nearly everywhere by 100 to 600 feet of younger rocks. Exceptions are small areas where the formation crops out in central Rutherford County and at Wilhoite Mills in Marshall County. In the outcrops the Murfreesboro yields water to most wells. Records of 47 wells drilled into the formation in Rutherford County show that the Murfreesboro yielded water to 34 of them. However, elsewhere in the

Central Basin where the Murfreesboro is more deeply buried it yielded water to only 20 of 100 wells.

In the vicinity of Murfreesboro several industries make use of ground water in their processes. In that locality there are at least 12 wells that yield more than 100 gpm each from the Murfreesboro limestone. Most of this water is of good quality. Elsewhere in the Central Basin the Murfreesboro seldom yields water that is not highly mineralized. The formation is a poor source of water except in the areas where it crops out or is very near the land surface.

PIERCE LIMESTONE (Op)

The Pierce is a thin silty limestone overlying the Murfreesboro limestone. As it has a thickness of only 25 feet, its area of outcrop is very small, usually restricted to a thin border about the outcrops of the Murfreesboro. The rock contains 15 percent of insoluble material,* twice as much as the Murfreesboro. Most of the insoluble material is clay and shale occurring as thin partings.

The Pierce limestone is a very poor source of water. Records of 153 wells penetrating the formation show that only 9 obtained water from it.

The thinness of the formation and its high content of insoluble matter, together with its deeply buried position in most places, are probable reasons for its poor water-yielding properties. Water, when encountered in the Pierce limestone, is generally too highly mineralized to be potable.

RIDLEY LIMESTONE (Or)

Probably the most reliable water-bearing formation above the Knox dolomite is the Ridley limestone. The rocks of this formation crop out over a greater area than those of any of the other formations in the Central Basin. Large exposures of the Ridley occur in Rutherford, Bedford, Marshall, and Maury Counties. In those counties the formation is topographically expressed as extensive plains.

The Ridley limestone is a massively bedded formation about 100 feet thick. It contains the purest limestone in the Central Basin, the average content of insoluble material being only 5 percent. The large areas of exposure and the chemical purity of the rock afford favorable conditions for the development of solution channels.

Records are available for 240 wells penetrating the Ridley limestone. The formation yielded water to 113 of the wells. In 65 percent of the

*The percentages of insoluble material expressed in this report are based on a study of insoluble residues on file at the Tennessee Division of Geology, Nashville, Tenn.

yielding wells, however, the quantity of water obtained from the Ridley is less than 5 gpm. Only 5 percent of the wells yield more than 20 gpm.

Water from the Ridley limestone is usually potable, although in one-third of the wells yielding water from the formation there is a detectable odor of hydrogen sulfide.

LEBANON LIMESTONE (O1b)

The Lebanon limestone is well exposed in the Central Basin. It is about 115 feet thick. In general, the Lebanon outcrops form a border around the large exposures of the Ridley limestone. In addition, there are many outliers of the Lebanon limestone within the outcrop areas of the Ridley. The Lebanon is usually distinguished by its thin-bedded argillaceous appearance and by the abundant growth of cedar trees that it supports.

Although the content of insoluble material in the Lebanon averages only 5.5 percent, the material occurs in the form of very thin, closely bedded, shale partings. As a result, the formation has a thin-bedded appearance.

Records of 293 wells penetrating the Lebanon show that this formation yielded water to 107 of them, a somewhat lower average than that for the underlying Ridley limestone. This lower average probably is due to the resistance to solution provided by the shale partings. This is suggested by the fact that half the wells starting in the Ridley yield water from that formation, whereas only one-fifth of the wells starting in the Lebanon yield water from the Lebanon.

The quantity of water to be expected from wells in the Lebanon is about the same as that yielded by wells in the Ridley. About 60 percent of the wells yield less than 5 gpm and 5 percent yield more than 20 gpm.

Water from the Lebanon limestone is usually of good quality except that it is very hard. Hydrogen sulfide is detected in about one-fourth of the wells. It can usually be removed by aeration. Salty water has been encountered in about 5 percent of the wells yielding water from the Lebanon.

CARTERS LIMESTONE (Oc)

The Carters limestone is one of the best known formations in the Central Basin. Well drillers commonly refer to it as the "brown lime." Its light-brown color contrasts sharply with the dark-blue beds of the underlying Hermitage formation. The Carters is 65 feet thick and consists

mostly of massively bedded limestone. The outcrops are often seen as steep risers between the steps produced by erosion of the Lebanon and Hermitage formations. In the eastern part of the Central Basin the Carters contains four thin beds of altered bentonite (Wilson, 1949, p. 62-65), the uppermost bed being at or near the top of the formation. In the remainder of the Central Basin only the three lower bentonite beds are present. If the calcareous shale partings in the Lebanon limestone are disregarded, the Carters and the Lebanon contain about the same amount of insoluble material. However, the thicker bedding of the Carters makes possible a better development of solution channels where water has access to the rock.

The Carters limestone is restricted as a water-bearing formation, however, by the overlying argillaceous Hermitage formation, which acts as an almost impervious cap preventing the downward seepage of water. For this reason the Carters does not have as good a record for yielding water as its chemical purity and massive bedding would suggest. Throughout the Central Basin the Carters has yielded water to 94 of 313 wells on which records are available. In three-fourths of the yielding wells water was encountered at depths of less than 100 feet. As the Hermitage formation restricts vertical seepage, the Carters must depend upon recharge at the outcrop. It seems that the chances of obtaining a water supply from the Carters are not favorable except where the formation is close enough to the surface to crop out near the area being drilled.

The quantity of water yielded to wells in the Carters limestone is, on the average, slightly greater than that yielded by the Ridley and Lebanon limestones. About 60 percent of the wells yield less than 5 gpm, and 6 percent yield more than 20 gpm.

Water from the Carters is similar in quality to that obtained from the Lebanon limestone. About one-fourth of the wells yield water that contains some hydrogen sulfide.

HERMITAGE FORMATION (Oh)

The Hermitage formation, ranging in thickness from 60 feet in the southern part of the Central Basin to 100 feet in the northern part, contains several members which intergrade laterally. Its identification in the field must take into account the locality, as outcrops of each member have characteristics differing from those of the other members. Wilson (1949, p. 82-102) defines the limits of occurrence of each member. The members differ in their content of fossils, phosphate, silt, and clay. In general, the strata of the Hermitage are very dark blue and are

TABLE 7.—CHEMICAL ANALYSES OF WATER FROM WELLS IN THE CARTERS LIMESTONE
(parts per million)

County	Well No.	Iron (Fe)	Calcium (Ca)	Magnesium (Mg)	Sodium (Na)	Carbonate (CO ₂)	Bicarbonate (HCO ₂)	Sulfate (SO ₄)	Chloride (Cl)	Fluoride (F)	Dissolved solids	Hardness as CaCO ₃
DAVIDSON	9	0.2	179	18	27	23	242	286	42	838	519
DAVIDSON	19	.4	932	40	317	0	756	1,900	489	2.0	4,350	2,490
DAVIDSON	94	.1	121	1	5	0	232	33	7	0	330	304
WILLIAMSON	30	.1	100	1	4	0	270	30	6	0	261	254
WILLIAMSON	31	.3	116	2	2	21	270	36	3	0	335	298
WILSON	8	.3	136	1	23	0	274	107	35	0	464	344

TABLE 8.—CHEMICAL ANALYSES OF WATER FROM WELLS IN THE HERMITAGE FORMATION
(parts per million)

County	Well No.	Iron (Fe)	Calcium (Ca)	Magnesium (Mg)	Sodium (Na)	Carbonate (CO ₂)	Bicarbonate (HCO ₂)	Sulfate (SO ₄)	Chloride (Cl)	Fluoride (F)	Dissolved solids	Hardness as CaCO ₃
DAVIDSON	7	0.4	144	2	2	31	308	68	3	0	433	388
DAVIDSON	121	.1	102	1	8	0	268	39	12	0	348	259
GILES	1	.4	98	5	7	12	162	123	11	401	265
WILLIAMSON	1	.7	104	7	3	19	296	5	4	328	288
WILLIAMSON	32	.1	86	7	5	0	230	54	6	.5	260	243

easily distinguished from the light-colored underlying Carters limestone. Much of the Hermitage is thinly laminated with shale partings, particularly the lower part.

The shaly nature of the Hermitage formation makes it a poor water bearer. It also forms an effective seal, greatly restricting the downward seepage of water into the underlying formations. Acting as an impervious cap, the Hermitage is responsible for many of the areas of ground-water deficiency near the outer limits of the Central Basin.

Occasionally water is encountered in the Hermitage, usually near the top of the formation in areas where a zone of coquina made up largely of the fossil brachiopod *Dalmanella* is present. This zone is a massively bedded, very fossiliferous, limestone restricted to the western half of the Central Basin.

Available records show that the Hermitage has yielded water to 68 of 267 wells penetrating the formation. About 60 percent of the yielding wells in the Hermitage yield less than 5 gpm. Ten percent yield more than 20 gpm.

Water from the Hermitage formation is generally of good quality, although that from about one-fifth of the wells contains some hydrogen sulfide.

Because of the impervious nature of the Hermitage it is inadvisable to drill into the formation where it lies at a depth exceeding 100 feet. Of the 68 wells yielding water from the Hermitage, only 14 encountered water in the Hermitage at depths of more than 100 feet.

BIGBY-CANNON LIMESTONE (Oby-Ocn) *

The interval between the Hermitage and Catheys formations, ranging from 60 to 100 feet in the Central Basin, is occupied by the Bigby (Oby), Cannon (Ocn), and Dove-colored facies of the Bigby-Cannon limestone. West of a north-south line from Davidson County to Giles County the Hermitage-Catheys interval is occupied by the Bigby facies. East of a north-south line from Sumner County to Lincoln County, the Cannon facies occupies the interval. Between the two lines the facies intergrade.

The Bigby facies is the well-known phosphate rock horizon of Central Tennessee. It is an impure limestone containing about 20 percent of insoluble material. The rock is dark blue when fresh, weathering

*The classification of the Bigby-Cannon limestone in this report is in accord with recent published reports and usage by the Tennessee Division of Geology, but it does not coincide with the classification used by the U. S. Geological Survey.

TABLE 9.—CHEMICAL ANALYSES OF WATER FROM WELLS IN THE BIGBY FACIES
(parts per million)

County	Well No.	Iron (Fe)	Calcium (Ca)	Magnesium (Mg)	Sodium (Na)	Carbonate (CO ₃)	Bicarbonate (HCO ₃)	Sulfate (SO ₄)	Chloride (Cl)	Fluoride (F)	Dissolved solids	Hardness as CaCO ₃
DAVIDSON	6	0.7	432	41	60	21	204	942	92	1,920	1,240
DAVIDSON	35	.2	484	22	51	0	408	905	78	1.8	1,960	1,300
MAURY	22	.1	362	6	13	0	232	701	21	2.5	1,300	920
MAURY	43	.1	74	1	4	0	166	50	7	0	227	189
WILLIAMSON	24-2	.1	110	2	7	0	210	107	11	.5	465	253

TABLE 10.—CHEMICAL ANALYSES OF WATER FROM WELLS IN THE CANNON FACIES
(parts per million)

County	Well No.	Iron (Fe)	Calcium (Ca)	Magnesium (Mg)	Sodium (Na)	Carbonate (CO ₃)	Bicarbonate (HCO ₃)	Sulfate (SO ₄)	Chloride (Cl)	Fluoride (F)	Dissolved solids	Hardness as CaCO ₃
DAVIDSON	45	0.2	94	2	8	21	214	30	12	0	305	243
MAON	1	.2	101	1	14	45	154	53	21	0	310	256
MOORE	3-1	78	1	1	0	220	16	1	0	280	199
SMITH	11	.1	78	1	50	13	182	39	75	0	300	199
JOHNSON	25	.1	96	1	1	9	246	26	2	.5	293	244

GROUND WATER

to brownish gray on the outcrop. Massive bedding is noted in fresh cuts, but strong crossbedding is seen in the weathered rock.

Rocks of the Cannon facies are nonphosphatic and are in most places finer grained and lighter in color than those of the Bigby facies. The content of insoluble material is only about one-fourth that of the Bigby facies.

A very dense, silt-free limestone, termed the "Dove" because of its very light-gray color, occurs as discontinuous bodies in the Bigby and Cannon facies. It ranges up to 40 feet in thickness and may be divided into two or more beds by the intervening Bigby and Cannon. The lateral extent of the Dove-colored facies is in most places impossible to determine without extensive drilling.

Available records show that water zones were encountered in 48 of 134 wells penetrating the Bigby facies. In about 75 percent of the wells the yield is less than 5 gpm; only 2 wells yield more than 20 gpm. Hydrogen sulfide is present in the water from about one-sixth of the wells in the Bigby facies. The remainder yield water of good quality.

The Cannon facies has yielded water to about 70 of 180 wells on which records are available. The yield and quality of water are recorded for only one-half of the 70 wells. Of those wells on which the records are complete 60 percent yield less than 5 gpm and 12 percent yield more than 20 gpm. The water is similar in quality to that found in the Bigby facies, one-sixth of the wells yielding water having a noticeable content of hydrogen sulfide. Salty water was reported in four wells.

CATHEYS LIMESTONE (Ocy)

The Catheys limestone is a series of rather silty limestones divided into several facies on the basis of fossils, silt content, and bedding. The formation ranges in thickness from 50 feet in the southwestern part of the Central Basin to 200 feet at the eastern margin. Generally, the Catheys appears as a light-gray granular rock. It is exposed in the valleys of many streams in the outer parts of the Central Basin. In the interior of the Central Basin the formation caps many of the higher hills.

Records are available for 157 wells that have penetrated the Catheys limestone. The formation yielded water to 65 of the wells. Of 47 wells on which the yield is recorded, 60 percent yield less than 5 gpm; 6 percent yield more than 20 gpm. About 70 percent of the wells furnish water of good quality. Hydrogen sulfide is present in water from about one-fourth of the wells.

TABLE 11.—CHEMICAL ANALYSES OF WATER FROM WELLS IN THE CATHEYS LIMESTONE
(parts per million)

County	Well No.	Iron (Fe)	Calcium (Ca)	Magnesium (Mg)	Sodium (Na)	Carbonate (CO ₂)	Bicarbonate (HCO ₃)	Sulfate (SO ₄)	Chloride (Cl)	Fluoride (F)	Dissolved solids	Hardness as CaCO ₃
DAVIDSON	41	0.1	98	1	5	0	236	53	7	0.2	310	249
DAVIDSON	108	.1	231	3	4	0	300	335	7	.5	860	590
MAURY	46	.2	94	1	16	25	186	40	25	.5	310	239
SUMNER	15	.1	92	2	125	39	166	35	191	3.0	626	238
WILLIAMSON	29-1	.3	105	1	1	0	260	41	1	0	306	265

TABLE 12.—CHEMICAL ANALYSES OF WATER FROM WELLS IN THE LEIPERS LIMESTONE
(parts per million)

County	Well No.	Iron (Fe)	Calcium (Ca)	Magnesium (Mg)	Sodium (Na)	Carbonate (CO ₂)	Bicarbonate (HCO ₃)	Sulfate (SO ₄)	Chloride (Cl)	Fluoride (F)	Dissolved solids	Hardness as CaCO ₃
DAVIDSON	99-1	0.3	202	2	4	30	226	277	7	1.0	693	513
MACON	3	.2	83	2	62	0	218	31	96	.2	435	214
STARNER	8	.4	143	2	37	14	126	205	56	.5	663	366
ST. FER.	20	.1	118	2	18	0	270	73	28	.8	377	303

GROUND WATER

LEIPERS LIMESTONE (O1)

Outcrops of the Leipers limestone are largely restricted to the margin of the Central Basin, very near its boundary with the Highland Rim Plateau. The formation is about 75 feet thick on the perimeter and thins rapidly toward the interior. The rocks of the Leipers are granular, knotty-appearing, blue limestone. The Leipers is phosphatic in places, particularly on the western side of the Central Basin. Commonly the outcrops have a yellowish, earthy appearance.

Springs flowing from the face of the Highland Rim escarpment furnish domestic water supplies to many residents of the outer Central Basin region. Consequently, there is not as much reliance on wells as in the interior of the Central Basin.

Records show that of 55 wells drilled into the Leipers 27 obtained water from this formation. Yield and quality data are available on 18 of the wells. Eight wells yield less than 5 gpm; three wells yield more than 20 gpm. No hydrogen sulfide was reported in water from wells penetrating the Leipers, and only one well was reported to yield salty water.

RICHMOND GROUP (Orh)

In the Central Basin the Richmond group is represented by the Sequatchie, Fernvale, and Mannie formations, none of which crops out over an appreciable area. They are present along the extreme northern and southern margins of the Central Basin.

The Sequatchie, a mudstone, overlies the Leipers limestone. It is overlain by the crystalline limestone of the Fernvale formation, above which is the Mannie shale (as defined by Wilson, 1949, p. 215-218), a series of varicolored shales. The three formations together probably do not exceed 75 feet in thickness.

Little information is available on the occurrence of ground water in the three formations. Of 24 wells recorded in the rocks of Richmond age, only 5 yield water. The water from all 5 wells is of good quality.

Water Levels In Wells

Ground water, in its movement through openings in the rocks, obeys certain physical principles. Knowledge of the principal features of the laws governing the flow of liquids should serve to reduce the uncertainty and financial risk connected with the development of ground-water supplies.

TABLE 13.—CHEMICAL ANALYSIS OF WATER FROM A WELL IN THE RICHMOND GROUP
(parts per million)

County	Well No.	Iron (Fe)	Calcium (Ca)	Magnesium (Mg)	Sodium (Na)	Carbonate (CO ₃)	Bicarbonate (HCO ₃)	Sulfate (SO ₄)	Chloride (Cl)	Fluoride (F)	Dissolved solids	Hardness as CaCO ₃
DAVIDSON	1115	0.1	90	1	7	27	156	41	11	0.6	261	229

Practically all ground water in the Central Basin of Tennessee is confined under artesian pressure in solution channels in the limestone. The pressure in a given channel depends upon the difference in altitude between the channel and the water table in the outcrop area of the formation, and upon the head loss by friction as the water moves through the rocks to the channel. When a well penetrates the channel the confining pressure is released and the water rises in the well. If it so happens that the land-surface elevation at the well is lower than the elevation to which the hydrostatic pressure forces the water, a flowing well results. As water rises in a well its increasing weight acts against the pressure that is forcing water into the well. This results in a steadily decreasing rate of rise until the pressure of the water in the well equals the hydrostatic pressure, and the water is said to have reached its "static" or nonpumping level. In a given aquifer the head generally decreases with distance from the recharge area as a result of friction.

When a well is pumped the water level declines, rapidly at first and then more slowly, until it reaches a state of equilibrium or near-equilibrium. The ratio of the pump discharge to the decline in water level is the specific capacity of the well. It is usually expressed in gallons per minute per foot of drawdown. If the water level is drawn down to the well's intake, the discharge is considered the total yield or "capacity" of the well.

Water levels in wells in the Central Basin fluctuate in accordance with local differences between rates of recharge and discharge. The period of fluctuation may be a part of a day, a day, a season, a year, or several years, depending on the cause. Small diurnal or semidiurnal fluctuations are caused by changes in barometric pressure. In some wells rapid rises in the water level occur during and after nearby rainfall, indicating that the wells are recharged by infiltration, as from nearby streams or sinkholes. Seasonal water-level fluctuations are usually caused by changes in the level of ground water in the recharge area, although they may be caused also by seasonal differences in withdrawal—for example, seasonal changes in withdrawal of water for air conditioning, or seasonal changes in natural discharge of water by vegetation in the discharge area. In general, the deeper the water zone and the greater the distance from the recharge area, the smaller the natural fluctuation of the water level.

Chemical Quality of Ground Water

Generally, with an increase in depth and in distance from the recharge area there is an increase in the mineral content of the water. An exception is the water yielded by the upper part of the Knox

EXPLANATION OF WELL TABLES

In the following tabulation of wells the well number found in the first column corresponds to the well number on the accompanying county map. In the column showing the approximate yield of the wells the term "seep" is used to denote a yield of less than 5 gallons per hour. The word "dry" indicates wells that, according to the driller, yield no water from zones within the rocks. Occasionally a reportedly dry well receives water by seepage from the soil during wet weather.

An asterisk (*) denotes that a chemical analysis of the water from the well is on file at the Tennessee Division of Geology. Many of the analyses are tabulated in the chapters on rock formations in this report.

Symbols are used to indicate the various geologic units in the surface unit and source columns. These symbols and the geologic units they represent are listed below:

Ock	Knox dolomite
Om	Murfreesboro limestone
Op	Pierce limestone
Or	Ridley limestone
Olb	Lebanon limestone
Oc	Carters limestone
Oh	Hermitage formation
Oby-Ocn	Bigby-Cannon limestone *
Oby	Bigby facies
Ocn	Cannon facies
Ocy	Catheys limestone
Ol	Leipers limestone
Orh	Richmond group

Explanation of Carter Coordinate System of Well Location

In the Carter Coordinate System an area is divided into quadrangles covering five minutes of latitude and longitude. Each such quadrangle is divided into 25 equal (1-minute) quadrangles. These quadrangles, or "sections" (not to be confused with the one-mile-square sections of the General Land Office township-and-range system), are numbered starting with 1 in the northeast and ending with 25 in the southwest quadrangle. (See illustration.)

*The classification of the Bigby-Cannon limestone in this report is in accord with recent published reports and usage by the Tennessee Division of Geology, but it does not coincide with the classification used by the U. S. Geological Survey.

EXPLANATION OF WELL TABLES

Notice that locations are given in reverse order of size—that is, the smallest subdivision to the largest. For example, in the illustration, the location of the well is NE, NE, SE, 11, 2S-54E as it is in the NE quarter of the NE quarter of the SE quarter of section 11 of quadrangle 2S-54E. It is readily seen that to find a well when the location is given, it will be necessary to read the location in reverse, finding quadrangle 2S-54E first, then section 11, and finally the quarter subdivisions, SE, NE, NE.




TABLE 25.—RECORDS OF WELLS IN MAURY COUNTY

Well No.	Location	Owner	Topographic situation	Altitude (feet)	Surface unit	Depth of well (feet)	Length of casing (feet)	Depth to water source (feet)	Source	Yield (gallons per minute)	Depth to water level (feet)	Date of measurement	Remarks
1	SE, SE, 25, 12S-30E	Jerry Dowling	Valley	710	Oc	100	98	Olh	20	Flowing	1950	Overflows 3 gpm.
2	SE, SE, 22, 9S-31E	J. W. Howard	Hillside	740	Oby	130	122	Oc	30	5-49	
3	SE, NW, 5, 11S-33E	K. L. Osteen	Low hill	641	Or	530	520	O-Ck*	20	11-50	
4	SE, SW, 21, 9S-31E	Town of Spring Hill	Hillside	762	Oh	410	110	95	Oc	4	67	7-48	Hydrogen sulfide odor.
5	SE, NE, 9, 13S-30E	James Scott	Valley	900	Oh	287	18	40	Oh	Seep	
6	NW, SW, 20, 11S-28E	Hugh Patton	Hilltop	650	Oby	81	Dry	
7	NE, SW, 15, 18S-30E	R. E. Ikard	Low hill	635	Oby	100	84	Oh	25+	75	7-51	Turbid.
8	Cen., NW, 17, 11S-31E	Raymond Holcomb	Valley	680	Oc	142	5	35	Oc	Seep	
9	NW, SE, 15, 11S-30E	Preston Osborn	Hillside	610	Oby	120	120	Olh or Or	10+	40	6-51	
10	SE, SW, 2, 13S-30E	Mrs. A. B. Scott	Valley	900	Oby	252	40	Oby or Oh	1½	90	7-51	
11	SW, NE, 11, 11S-29E	R. G. Curtis	Hillside	600	Olh	48	4	35	Olh	Seep	
12	SE, SW, 21, 11S-28E	Howard Ewing	do.	650	Oh	166	11	156	Olh	1	
13	SE, NE, 11, 11S-29E	Buster Greer	do.	700	Olh	68	8	67	Olh	5	28	8-51	
14	SW, NW, 18, 12S-30E	Lester Hickman	do.	1,040	Ol	100	12	30	Oey	¾	
15	SE, SW, 11, 10S-29E	M. C. Woodall	do.	800	Oey	100	70	72	Oby	Seep	65	7-52	
16	SE, NE, 9, 11S-32E	Thomas Gooch	Low hill	620	Or	100	15	65	Or	do.	
17	SW, SE, 16, 10S-32E	B. E. Barnett	Valley	820	Oh	120	20	Oh	1/8	Hydrogen sulfide odor.
18	NW, SW, 12, 11S-27E	Cecil Cathey	do.	800	Ol	82	9	81	Oey	8	25	9-51	Do.
19	SW, NE, 12, 11S-29E	Clay Miller	Hillside	680	Oby	1,040	12	140	Oc*	1	
20	SW, SE, 15, 11S-31E	Hershel White	do.	720	Oh	340	933	O-Ck*	1½	123	10-52	Do.
								210	Olh	Seep	
								275	Or	60	9-51	
								300	Or	
21	NE, NE, 1, 10S-31E	Buck Wiley	Hilltop	765	Oh	826	815	O-Ck	4	
22	SE, SE, 23, 10S-27E	Wilae Thompson	Bluff	600	Oey	83	26	65	Oby	10	42	3-52	
23	SE, SW, 7, 11S-31E	W. H. Matheny	Hillside	695	Oh	209	19	45	Oc	Seep	
24	SE, SW, 9, 10S-32E	B. A. Neil	Rolling	780	Olh	500	15	30	Olh	do.	
..								475	Om	do.	10	1-53	

* Chemical analysis is available from the Tennessee Division of Geology.


MAURY COUNTY

12

TABLE 25.—RECORDS OF WELLS IN MAURY COUNTY—Continued

Well No.	Location	Owner	Topographic situation	Altitude (feet)	Surface unit	Depth of well (feet)	Length of casing (feet)	Depth to water (feet)	Source	Yield (gallons per minute)	Depth to water (feet)	Date of measurement	Remarks
25	NE, NW, 12, 11S-29E	R. S. Brown	Rolling	620	Oby	163	7	135	Oh or Oc	do.	40	6-52	Hydrogen sulfide odor.
26	NW, NW, 11, 11S-29E	Elbert Burgess	do.	700	Oby	200	4	110	Oh	1	70	6-52	
27	NW, NE, 21, 11S-30E	R. S. Compton	Hillside	660	Oc	350	...	145	Olb	Seep	
28	SE, SE, 13, 10S-32E	Ed Dalton	Rolling	730	Olb	218	10	32	Olb	do.	
29	NW, NW, 12, 11S-29E	Harry Napier	do.	610	Oh	70	7	52	Oh	8	37	7-52	
30	NE, SW, 11, 11S-29E	Malcolm Lewis	do.	750	Oby	41	18	35	Oh	10	23	7-52	
31	NW, NW, 17, 11S-28E	J. B. Sisk	Valley	580	Ocy	97	6	80	Oby	3/4	6	7-52	Salty. Hydrogen sulfide odor.
32	SE, SW, 1, 11S-30E	T. G. Wilkins	Rolling	700	Oh	100	21	60	Oh	10	40	7-52	
33	NW, NW, 15, 11S-30E	George Williams	Low hill	600	Olb	100	11	95	Oc or Or	1	40	7-52	
34	NE, NE, 6, 11S-29E	J. R. Baker	Rolling	700	Oby	188	27	164	Oc	10+	40	5-52	
35	NW, SW, 8, 12S-32E	N. P. Cheek	Bluff	600	Or	92	24	88	Or	8	25	7-52	
36	NE, SW, 11, 11S-29E	Will Dale	Rolling	740	Oh	142	6	134	Oc	10+	112	5-52	
37	SE, NE, 23, 10S-28E	Elmer Wise	do.	630	Oby	123	18	120	Oh or Oc	10	60	7-52	
38	SW, NW, 19, 9S-30E	M. E. Fitzgerald	do.	850	Ocy	83	...	75	Ocy or Oby	3/4	48	8-52	
39	NE, NW, 15, 11S-30E	Thomas Gray	Low hill	610	Olb	100	8	43	Olb	Seep	35	7-52	
40	NE, NW, 15, 10S-31E	W. E. Hale	Valley	640	Oc	48	4	43	Oc or Olb	3/4	27	8-52	
41	NE, NE, 6, 10S-31E	W. T. Hardison	Rolling	660	Oh	82	...	70	Oc or Olb	1+	47	8-52	
42	NW, NE, 6, 10S-31E	Hale Johnson	do.	600	Oh	62	...	60	Oc	3	
43	NW, NE, 18, 10S-28E	G. E. Ladd	do.	600	Ocy	72	24	55	Oby*	6	35	7-52	
44	NE, SE, 3, 12S-32E	L. J. Lindsey	Bluff	620	Oby	102	39	96	Oc or Op	10+	40	7-52	
45	NE, NW, 12, 11S-29E	John Luster	Rolling	630	Oby	157	5	152	Oc	10+	45	7-52	
46	SE, SW, 3, 10S-29E	Lex Potts	Valley	700	Ol	60	5	30	Ocy*	1	20	8-52	
47	SE, SW, 10, 10S-33E	George Warren	Plain	700	Or	84	6	80	Or	Seep	18	7-52	

* Chemical analysis is available from the Tennessee Division of Geology.



REFERENCE NO. 14

Please do not destroy or throw away this publication. If you have no further use for it write to the Geological Survey at Washington and ask for a frank to return it

UNITED STATES DEPARTMENT OF THE INTERIOR

Harold L. Ickes, Secretary

GEOLOGICAL SURVEY

W. C. Mendenhall, Director

Water-Supply Paper 677

GROUND WATER IN SOUTH-CENTRAL TENNESSEE

BY

CHARLES V. THEIS

Prepared in cooperation with the
TENNESSEE DIVISION OF GEOLOGY



UNITED STATES
GOVERNMENT PRINTING OFFICE
WASHINGTON : 1936

For sale by the Superintendent of Documents, Washington, D. C. - Price 50 cents (Paper cover)

CLIMATE

GROUND-WATER SUPPLY IN 1930 COMPARED WITH THAT OF OTHER DROUGHT YEARS

The flow of springs and the depths to the water levels in wells, as well as other ground-water features, vary with the current and preceding climatic phenomena. The current precipitation affects the flow of springs that are connected by relatively large underground passages with open intakes, such as sink holes. The precipitation during many preceding months has also an effect on the flow of other springs, as well as on the height of water in wells, because part of the rainfall moves very slowly downward through the soil to the ground-water level, below which it is stored in the ground-water body until it is discharged. The ground-water level, or water table, usually fluctuates seasonally to some extent, rising during the winter, when more water is contributed to it by precipitation than is discharged by springs and otherwise, and falling during the summer, when the reverse is true. As the water table falls, the flow of springs diminishes. Under conditions of drought it falls much more than normally and consequently the springs discharge much less than their normal flows for the season. Temperature has also both immediate and delayed effects, for it controls in part the rate of transpiration of plants and the rate of evaporation, so that in hot, dry weather much of the ground water is removed by these agencies. Furthermore, when soils have been drying for a long time, much of any rainfall that comes is absorbed by the soil near the surface and never descends to the zone of saturation.

The summer of 1930, in which the field work for this report was done, was characterized by a severe drought throughout the area studied, as well as generally in the central and eastern United States. Although streams in the Tennessee Valley in general did not decline as much in this year as they had in 1925,¹² or in 1931, the flows were reduced in general to much less than normal. The ground-water flow probably did not decrease in as great a ratio as the flow of the surface streams, yet undoubtedly the flows given in this report for many springs are less than normal, and the water levels in wells are probably also lower than their average position.

The exact effect of the climatic conditions upon the ground-water phenomena observed during the summer and fall of 1930 cannot be evaluated from the data collected during one field season. To do so would require an intensive study, during at least several years, of the relations between climatic factors, ground-water levels, and the flow of springs. However, the accompanying tables are given to indicate qualitatively rather than to define exactly the relation of the data acquired during 1930 to data that might have been

¹² King, W. R., Surface waters of Tennessee: Tennessee Div. Geology Bull. 40, p. 50, 1931.

CLIMATE

water companies in the area, to local geologists, and to the inhabitants in general, the writer is indebted for courteous and intelligent cooperation.

The published work of many other geologists has been used in preparing this report. Although the papers used are cited in the text, it is not out of place to note here that the section on stratigraphy is based largely on the work of Bassler,⁵ Butts,⁶ Miser,⁷ Wade,⁸ and Dunbar.⁹

The region under discussion has an area of 6,108 square miles and includes the counties of Bedford, Franklin, Giles, Hickman, Lawrence, Lewis, Lincoln, Marshall, Maury, Moore, Perry, and Wayne. It lies almost entirely within the basin of the Tennessee River and extends from that river, on the west, to the Cumberland Plateau, on the east. It is bounded on the south by the Alabama State line and extends north about to the middle latitude of the State. It is served by numerous highways and by the Louisville & Nashville Railroad and the Nashville, Chattanooga & St. Louis Railway. It is predominantly agricultural in interest, although Maury County and to a less extent Lewis County produce phosphate rock, and Wayne, Lewis, and Hickman Counties have produced brown iron ore up to the last few years and still have large reserves.

CLIMATE

GENERAL FEATURES

South-central Tennessee lies between two of the main storm tracks crossing the eastern United States but not directly upon any.¹⁰ Hence there are many comparatively gentle changes in the weather but relatively few severe ones. Its position with reference to the storm tracks conduces to a generally favorable distribution of rainfall throughout the year and a minimum of destructive storms. Iso-pluvial charts show that the greatest storms in this general area are less in intensity than in any other area in the same latitude in the eastern United States.¹¹

⁵ Bassler, R. S., The stratigraphy of the Central Basin of Tennessee: Tennessee Div. Geology Bull. 33, 1932.

⁶ Butts, Charles, Geology of Alabama; the Paleozoic rocks: Alabama Geol. Survey Special Rept. 14, 1926.

⁷ Miser, H. D., Mineral resources of the Waynesboro quadrangle: Tennessee Geol. Survey Bull. 25, 1921.

⁸ Wade, Bruce, The geology of Perry County and vicinity: Resources of Tennessee, vol. 4, no. 4, Tennessee Geol. Survey, 1914.

⁹ Dunbar, C. O., Stratigraphy and correlation of the Devonian of western Tennessee: Tennessee Geol. Survey Bull. 21, 1919.

¹⁰ Summary of the climatological data for the United States, Section 77, Middle and west Tennessee, U. S. Weather Bureau.

¹¹ Storm rainfall of eastern United States: Miami Conservancy District Tech. Repts., pt. 5, Dayton, Ohio, 1917.

GROUND WATER IN SOUTH-CENTRAL TENNESSEE

TEMPERATURE

The mean annual temperature of central Tennessee, as well as for stations within the area of this report, is 58.7° Fahrenheit. For individual stations it ranges from 59.7° at Coldwater, Lincoln County, to 58.4° at Franklin, Williamson County, just north of the Maury County line, and 57.2° at Sewanee, Franklin County. These figures indicate a general decrease toward the north and also with increasing altitude above sea level. Maximum temperatures of 110° were reached in the summer of 1930, but as a rule the temperature does not exceed 95° more than about 15 days a year. Minimum temperatures as low as 25° below zero have occurred, but on the average temperatures below zero occur only once a year. July is the hottest month and January the coldest. The average date of the last killing frost in spring is April 6, and of the first in autumn October 24.

Mean monthly temperatures for central Tennessee, as computed from records up to and including 1930, are shown in the following table:

Mean monthly temperatures (°F.) for central Tennessee

January.....	39.2	May.....	66.7	September.....	71.4
February.....	40.7	June.....	74.7	October.....	59.8
March.....	49.9	July.....	77.4	November.....	48.6
April.....	58.6	August.....	76.6	December.....	40.6

PRECIPITATION

The mean annual precipitation for all of Tennessee is about 50 inches and that for central Tennessee is about 51 inches. The figure for the stations in and adjacent to the south-central Tennessee area is about 52.5 inches. The highest mean, as computed from records up to and including 1930, is found at Sewanee, Franklin County, with 54.76 inches, and the lowest at Franklin, Williamson County, with 48.54 inches. The rainfall diminishes slightly northward and increases slightly with altitude.

The rainfall is well distributed throughout the year, reaching a minimum in October with 3.01 inches, and a maximum in March with 5.65 inches. A quantity sufficient for crop needs generally falls during the growing season, and a copious supply is also available during the winter, when recharge of ground water is most favored. The following table gives the mean monthly precipitation in central Tennessee.

Mean monthly precipitation (inches) for central Tennessee

January.....	5.00	May.....	4.26	September.....	3.18
February.....	4.21	June.....	4.31	October.....	3.01
March.....	5.65	July.....	4.58	November.....	3.47
April.....	4.68	August.....	4.18	December.....	4.65

MAURY COUNTY

Analyses of ground waters from Marshall County

[No. 329 analyzed by Margaret D. Foster, U. S. Geological Survey; the rest by D. F. Farrar, Tennessee Geological Survey. Parts per million. Numbers at heads of columns correspond to numbers in tables of well and spring data.]

	322	326	329	342	Lewisburg *
Silica (SiO ₂).....	2.8	12	11	10	6.8
Iron (Fe).....	1.4	2.1	.06	.85	.84
Calcium (Ca).....	85	122	3.2	32	24
Magnesium (Mg).....	10	16	1.5	4.0	2.0
Sodium (Na).....	5.0	17	233	3.3	3.4
Potassium (K).....	1.0	4.0	5.6		
Carbonate (CO ₃).....	0	0	57	0	0
Bicarbonate (HCO ₃).....	292	294	420	100	101
Sulphate (SO ₄).....	5.3	108	67	12	11
Chloride (Cl).....	8.5	32	18	5.5	5.5
Nitrate (NO ₃).....	.67	1.3	1.2	.15	.60
Total dissolved solids.....	^b 270	470	609	121	115
Total hardness as CaCO ₃ (calculated).....	254	370	14	96	97
Date of collection (1930).....	Oct. 30	Oct. 31	(*)	Nov. 5	Nov. 6

* Municipal water supply at Lewisburg; sample taken from private tap; impounded surface water.

^b Calculated.

* Sample analyzed July 1931.

MAURY COUNTY

[Area 582 square miles, population 24,016]

Maury County lies in the north-central part of the area discussed in this report. It is bounded on the north by Williamson County, on the east by Marshall County, on the south by Giles and Lawrence Counties, and on the west by Lewis and Hickman Counties. The largest city is the county seat, Columbia, with a population of 7,882. Mount Pleasant (population 2,010), in the southwest corner, is the center of a large phosphate industry.

The Duck River flows northwestward through the middle of the county and drains the entire area.

The Louisville & Nashville Railroad connects the centrally located city of Columbia with Nashville, to the northeast, with Pulaski, to the south, and with Mount Pleasant and Lawrenceburg, to the southwest. The Nashville, Chattanooga & St. Louis Railway connects Columbia with Lewisburg, to the southeast. Paved highways radiate from Columbia approximately along the lines of the Louisville & Nashville Railroad, and graveled highways connect Columbia with Lewisburg and Centerville.

The county is predominantly rural in character. The phosphate industry centered about Mount Pleasant and near Williamsport is the largest basic industry, aside from agriculture, in south-central Tennessee.

GEOLOGY

Maury County is a part of the Nashville Basin, although spurs from the Highland Rim plateau project into it from the northwest, west, and southwest, and remnants of the rim are found in all but the most eastern portion. The plateau in the southwest corner lies 1,000 feet above sea level, and the Duck River leaves the county at about 500

GROUND WATER IN SOUTH-CENTRAL TENNESSEE

feet, making the total relief 500 feet. The Highland Rim spurs are greatly dissected, and this portion of the county is topographically very rough. Throughout that part of the lowland lying west of Columbia the topography is rolling, but in the eastern part of the county the local relief is very small, and much of the area has the typical glade character.

Most of the high parts of the Highland Rim spurs, except along the Giles County line, are capped by the St. Louis limestone and the Warsaw formation. The maximum combined thickness of these formations in this county is probably close to 100 feet. Underneath these, making the steep slopes of the hills, are the Fort Payne chert and Ridgetop shale, reaching a maximum combined thickness of 250 feet. The Maury glauconitic member is generally present at the base of the Ridgetop shale. The Chattanooga shale crops out in the hillsides and is 10 feet or less thick. The Silurian is present in small areas in the western part of the county. It consists of shaly limestone and is thin in this area. The uppermost Ordovician, the Fernvale formation, also crops out in the western part of the county. Here it consists of light-colored shale and reddish crystalline limestone. It, too, is thin. The nodular shaly Leipers limestone is present on the lower hill slopes in the western part of the county and overlies the similar Catheys limestone. The combined thickness of these two formations ranges from a knife-edge to 200 feet.

Stratigraphically below the Catheys limestone comes the Cannon limestone. This formation is present only in the eastern part of the county, never having been deposited in the western part, in the Columbia quadrangle.⁴¹ The Cannon limestone consists of dove-colored semilithographic limestone and argillaceous limestone and shale.

Stratigraphically, the Bigby limestone underlies the Cannon limestone, but it is best developed in the western part of the county, where the Cannon is absent, and pinches out in the eastern part of the county, where the Cannon is well developed. It has a maximum thickness of about 100 feet and is predominantly a semi-oolitic or granular crystalline laminated and locally cross-bedded limestone. Its type area is on Bigby Creek, in this county, and, in its typical facies at least, it does not extend far beyond the limits of the county except to the south in Giles County. Below the Bigby limestone is the Hermitage formation, a shaly limestone from 40 to 70 feet thick.

The Hermitage formation is underlain by the Lowville limestone, consisting in most of the county of the lower or Carters limestone member, typically a thick-bedded limestone, weathering into a red soil through which unweathered limestone bosses project. Its thickness is almost 50 feet. In the eastern part of the county the

⁴¹ Bassler, R. B., *op. cit.*, p. 86.

MAURY COUNTY

thinner-bedded upper limestone member wedges in between the Carters member and the overlying Hermitage formation according to Bassler.

The thin-bedded dove-colored and gray Lebanon limestone comes in below the Carters limestone and is widely exposed from Columbia eastward. The following sections, adapted from Bassler,²² illustrate the rapid eastward change in stratigraphy:

Stratigraphic section at Columbia

[Lowville and Lebanon exposed in banks of Duck River, Hermitage, and Bigby from Santa Fe pike south west to West 7th and Armstrong Streets, remainder from that point to top of Mount Parnassus]

Leipers limestone:	<i>Feet</i>
Thin-bedded nodular blue limestone with intercalated blue and yellow shale crowded with Bryozoa and other fossils.....	15
Mostly covered, but limestone similar to underlying bed with upper layer granular, gray, and cavernous..	28
Impure thin-bedded limestone with few fossils except in top layer, which is full of broken shells and Bryozoa..	12
Shaly impure limestone in thin layers, crowded with <i>Rafinesquina alternata</i> and <i>Platystrophia ponderosa</i> ..	6
Catheys limestone:	
Rough-bedded dark thin argillaceous limestone weathering cavernous (small holes); fossils few and indeterminate.....	14
Fossiliferous shaly limestone crowded with the massive bryozoan <i>Cyphotrypa tabulosa</i>	4
Unevenly bedded granular and subgranular blue limestone; upper part contains <i>Escharopora falciformis</i> var.....	16
Blue massive subcrystalline limestone with <i>Cyclonema varicosum</i>	4
Thick-bedded fine-grained gray or blue clayey limestone with numerous gastropods and pelecypods— <i>Lophospira bowdeni</i> , <i>Orthorhynchula linneyi</i> , <i>Tetradium columnare</i> , and small <i>Stromatocentrum pustulosum</i> ..	4
Shaly nodular and subcrystalline limestone, crowded with Bryozoa, especially <i>Escharopora flabellarius</i> , <i>Heterotrypa parvulipora</i> , and <i>Homotrypa centralis</i>	16
Granular and crinoidal limestone with abundant <i>Solenopora compacta</i> from 1 to 2 inches in diameter.....	5
Nodular blue clayey limestone with two layers (one at base and other above the middle) with abundant large <i>Stromatocentrum pustulosum</i> . Many other fossils..	18
Finely granular laminated unfossiliferous phosphatic limestone.....	6
Phosphatic limestone in thin beds; top layer covered with <i>Constellaria grandis</i> and other Bryozoa.....	6
Blue granular limestone crowded with <i>Constellaria teres</i> and <i>C. emaciata</i>	2

²² Bassler, E. S., op. cit., pp. 28-29, 31-32.

GROUND WATER IN SOUTH-CENTRAL TENNESSEE

Stratigraphic section at Columbia—Continued

Catheys limestone—Continued.	
Blue to yellow shale with <i>C. teres</i> , <i>C. emaciata</i> , and other Bryozoa.....	Feet 4
Shaly limestone with few fossils.....	2
Bigby limestone:	
Gray to blue granular limestone crowded with <i>Rafinesquina</i>	1
Granular limestone with a few <i>Rafinesquina</i> and other fossils; hemispheric Bryozoa and <i>Eridotrypa briareus</i> at base.....	5
Granular gray-blue limestone with <i>Rafinesquina</i>	2
Subgranular unfossiliferous limestone.....	2
Gray granular limestone with <i>Rafinesquina</i> and several layers with <i>Ctenodonta subrotunda</i> , <i>Bellerophon clausus</i> var., <i>Lophospira</i> , <i>Rhynchotrema increbescens</i> , large <i>Dalmanella</i> , and <i>Hebertella frankfortensis</i>	5
Unfossiliferous shale.....	1
Thin-bedded subgranular gray limestone, yielding a little chert on weathering, with abundant <i>Rafinesquina</i> , rare <i>Dalmanella</i> , and cyclorid gastropods.....	17
Hermitage formation:	
Blue even-bedded subcrystalline limestone with abundant <i>Dalmanella fertilis</i>	50
Impure blue clayey limestone, fine-grained in upper half; <i>Dalmanella fertilis</i> rare, <i>Prasopora patera</i> common....	15
Lowville limestone (Carters limestone member):	
Massive magnesian limestone, easily recognized by white color of its outcrop.....	12
Mottled thick-bedded magnesian limestone, locally with <i>Maclurea bigsbyi</i> , <i>Stromatocerium rugosum</i> , <i>Columnaria halli</i> , <i>Lophospira</i> , <i>bicinda</i> , and <i>Dystactospongia minor</i>	18
Single bed of mottled fine-grained dove-colored, nearly pure limestone with yellow magnesian spots; locally fossiliferous.....	4
Massive fine-grained mottled, rather pure dove-colored limestone with fossils weathering out siliceous, particularly <i>Streptelasma profundum</i> , <i>Columnaria halli</i> , <i>Stromatocerium rugosum</i> , and <i>Maclurea bigsbyi</i>	6
Mottled yellow massive limestone, low in magnesia; no fossils seen.....	3
Massive finely granular yellow, nearly pure limestone with <i>Stromatocerium rugosum</i> , <i>Columnaria halli</i> , <i>Tetradium columnare</i> , <i>T. carterensis</i> , and <i>Lichenaria carterensis</i>	5
Fine-grained yellow limestone; no fossils.....	1 1/2
Lebanon limestone: Thin-bedded dove-colored limestone, in some places separated by shaly layers.	

MAURY COUNTY

Stratigraphic section on Bear Creek Pike, on west side of Loftus Hill, 8 miles east of
Columbia

Chattanooga shale.....	Feet
Leipers limestone:	5
Nodular earthy calcareous shale with <i>Platystrophia ponderosa</i>	13
Shaly blue limestone crowded with Bryozoa.....	4½
Impure limestone with large <i>Platystrophia ponderosa</i> and <i>Strophomena planoconvexa</i>	7
Shaly limestone, not well shown, full of <i>Tetradium fibratum</i> , <i>Platystrophia ponderosa</i> , and Mollusca.....	7
Gray-blue limestone; no recognizable fossils.....	10
Blue limestone with <i>Bucania</i> , <i>Hebertella sinuata</i> , and <i>Platystrophia ponderosa</i>	8
Catheys limestone:	
Shaly limestone with Bryozoa.....	2
Laminated granular limestone.....	4
Argillaceous limestone and shale with <i>Columnaria alveolata</i> , <i>Stromatocerium pustulosum</i> and <i>Tetradium fibratum</i>	4
Laminated granular limestone.....	4½
Gray subcrystalline limestone.....	3
Shale and clayey limestone, weathering cherty at top; <i>Stromatocerium pustulosum</i> , <i>Tetradium fibratum</i> , and <i>Columnaria alveolata</i> abundant in weathered debris..	5½
Blue subcrystalline limestone and shale, full of Bryozoa, especially <i>Constellaria emaciata</i> and <i>C. teres</i>	4
Cannon limestone:	
Laminated granocrystalline limestone weathering into thin platy phosphate.....	10
White and gray oolitic limestone, with fossils, particularly the gastropods <i>Lophospira sumnerensis</i> , <i>Bucania</i> , <i>Oxydiscus</i>	10
Granocrystalline phosphatic limestone.....	9
Dove-colored limestone.....	8
Bigby limestone: Gray subcrystalline limestone.....	2

Maury County lies on the west side of the Nashville dome. The general dip of the rocks is a little north of west, the amount about 250 feet in the 25 miles across the county. There are local folds throughout the county, and some minor faulting has occurred. Between Columbia and Williamsport an area of about 1 square mile represents a graben in which the Fort Payne chert is brought into contact with the Hermitage formation, giving a maximum displacement of about 400 feet. A fault with the northern area downthrown about 50 feet runs eastward for several miles south of Santa Fe.

GROUND WATER IN SOUTH-CENTRAL TENNESSEE

GROUND WATER

Ground water as found in Maury County conforms to the same generalizations found valid in the other basin counties. Shallow wells furnishing adequate supplies for domestic use are successfully drilled in most places in the county. In a few places, however, even a domestic supply is hard to obtain. In the vicinity of Match seven holes close together, the deepest 308 feet deep, failed to obtain any water. Deep wells in search of large supplies are sometimes successful and sometimes not. A well at the site of the old ice plant at Columbia (well 368) is reported to have yielded about 75 gallons a minute, probably from the Murfreesboro limestone. At the site of the present ice plant in Columbia six holes from 300 to 500 feet deep and one hole 1,105 feet deep (well 367) failed to strike any water, except a seep estimated at 1 gallon an hour. The deepest well should have passed through the horizon of the St. Peter sandstone, which yields water elsewhere in the basin. At the Arrow phosphate plant, near Mount Pleasant, well 360, about 700 feet deep, is reported to have furnished a continuous supply of about 300 gallons a minute. The water was obtained near the bottom of the well. This well has been abandoned because it did not satisfy the needs of the plant. Well 356 and a nearby well at the Armour Fertilizer Co.'s plant near Williamsport, both 155 feet deep, draw from 30,000 to 40,000 gallons a day from the Carters limestone at a depth of about 150 feet.

On the spurs of the Highland Rim water for domestic purposes is obtained from the weathered residue of the Mississippian limestones.

Springs are present throughout the county and vary in yield with the relief of the adjacent country. The largest spring seen is no. 390, near Southport. It issues from the Hermitage formation and was flowing about 400 gallons a minute when visited in July 1930.

The public water supply at Columbia is obtained from the Duck River. Carpenter and Kidd Springs, in Lewis County (nos. 262 and 263, p. 130) furnish the water supply of Mount Pleasant.

Records of wells in Maury County

[Nos. 353-355, 357, 380 dug; all others drilled]

No. on pl. 1	Location with respect to nearest map point	Owner or lessee	Topographic situation	Approximate altitude (feet)	Depth (feet)	Diameter (inches)
• 348	Santa Fe, 3 miles north	Will Stanfield	Ridge	880	80	5
349	Santa Fe, 4 miles north	Mrs. Maggie Wakefield	Creek terrace	715	80	
350	Theta	G. W. Barnes	Ridge	945	28	6
351	Santa Fe	J. R. Dodson	Valley	670	20	6
352	Santa Fe, 2½ miles southeast	R. Y. McKee	Ridge	925	62	6
353	Williamsport	James R. Walker	Terrace remnant	625	35	
354	do.	Dr. H. O. Anderson	do.	630	35	48
355	Williamsport, 4 miles southeast	Nick Farris	Small valley	705	24	42±
356	Williamsport, 6 miles southeast	Armour Fertilizer Co.	Rolling	700	155	6
357	Hampshire, 6¼ miles northwest	Herbert Farris	Ridge	880	62	
358	Hampshire, 1½ miles west	R. M. Patton	Hillside	700	46	6
359	Hampshire, 2 miles northeast	W. S. Parkes	Valley	690	37	8
360	Mount Pleasant, 1½ miles southeast	Arrow Mines Co.	do.	700	700±	10
361	Mount Pleasant	Mount Pleasant Ice Co.	do.	630	110	8
362	Mount Pleasant, 1¼ miles north	L. & N. R. R.	do.	635	60	
• 363	Mount Pleasant, 6 miles southeast	E. J. Gilbreath	Gentle hillside	720	85	6
• 364	Columbia, 3¼ miles southwest	W. J. Sheegog	do.	690	70	6
365	Hampshire, 6 miles northeast	Geo. P. Webster	Low hill	590	51	5
366	Columbia, 4 miles southwest	John M. Gray	do.	675	100	6
367	Columbia	Columbia Ice & Cold Storage Co.	Plain	655	1, 102	14
368	do.	do.	River terrace	600	300	6
369	Columbia, 5¼ miles northwest	J. K. P. Timmons Estate	Base of hill	585	26	8
370	Carters Creek, 3 miles north	L. Sparkman	Plain	700	82	6
• 371	Carters Creek, 1 mile east	John Armistead	Open valley	810	29	36
• 372	Spring Hill, 4 miles southeast	W. M. Farham	Low hill	690	73	5
373	Match, 6 miles northeast	J. A. Crow	Gentle hillside	670	26	5
• 374	Match, 5 miles east	H. T. Chunn	Low hill	660	75	6
375	Match, 1 mile east	W. A. Harbison	Low ridge	740	308	5
376	Match	E. D. Minor	Hillside	825	66	6
377	Match, 3 miles south	Mrs. M. L. Barber	Low spur	725	40	6
378	Culleoka, 4 miles north	S. A. Sims	Terrace	580	83	5¼
379	do.	F. M. Landres	Low hill	610	116	5¼
380	Silver Creek, 3 miles north	G. W. Tindell	Level	650	25	30
381	Silver Creek, 1 mile west	Dr. W. R. Orr	Base of hill	690	24	5
382	do.	do.	Hillside	720	1¼	5
• 383	Silver Creek, 2 miles west	W. E. Cheek	do.	730	115	5
384	Culleoka	Hobbs Bros.	do.	705	100	6

MAURY COUNTY

• Analysis given in table of analyses.

GROUND WATER IN SOUTH-CENTRAL TENNESSEE

Records of wells in Maury County—Continued

No. on pl. 1	Water-bearing beds			Water level		Use of water	Total hardness as CaCO ₃ (parts per million)	Remarks
	Depth (feet)	Lithologic character	Stratigraphic position	Above or below surface (feet)	Date of measure- ment (1930)			
348	80±	Chert.....	Fort Payne chert.....	-71	July 17	Domestic.....		Wells in Williamsport generally dug through about 20 feet of alluvial gravel and silt into bedrock below.
349	30±	Shaly limestone.....	Leipers limestone.....	-19	do.	do.		
350	28±	(?)	St. Louis limestone.....	-23	do.	do.		
351	20±	Limestone.....	Bigby limestone.....	-16	July 16	do.		
352	62±	Chert.....	Fort Payne chert.....	-84	July 17	do.		
353		Limestone.....	Bigby limestone.....			do.		
354	29±	do.	do.	-29	July 16	do.		Water reported hard. This and another well close by and of same depth furnish 30,000 to 40,000 gallons a day.
355		Residual chert (?)	Fort Payne chert.....			do.		
356	150±	Limestone.....	Lowville limestone.....	-10		Domestic; boiler.....		
357	58±	Residual chert (?)	Fort Payne chert (?)	-58	July 18	Domestic; stock.....		
358	46±	Shaly limestone.....	Cathays limestone.....	-41.5	July 10	do.		
359	37±	do.	do.	-20	July 10	Well abandoned.....		Reported to have produced at rate of 300 gallons a minute continuously. Abandoned because supply inadequate for needs. Sulphur water.
360	700±	Limestone.....						
361	110±	do.	Lowville limestone.....	-54		Cooling.....		
362	60±	(?)	Hermilage formation.....	-30		Domestic.....		
363	70	Limestone.....	Lebanon limestone (?)	-50		Stock.....		
364	70±	do.	Hermilage formation.....	-36		Domestic; stock.....		Only water found was a seep, estimated at 1 gallon an hour, from 800-foot depth. Six other wells 300 to 500 feet deep obtained no water. Abandoned well at former location of ice plant on northwest edge of town. Reported to have yielded 75 gallons a minute.
365	61±	do.	Bigby limestone.....	-38	July 18	Domestic.....		
366	97	do.	Lowville limestone.....	-50±		Domestic; stock.....		
367				-40		None.....		
368	300±	Limestone.....	Stones River group.....			Cooling.....		
369	26±		Hermilage formation.....	-16.5	July 17	Domestic.....		Water low and unfit for use on July 19.
370	32±		do.	-14	July 19	do.		
371	28±	Limestone.....	do.	-23	do.	do.		
372	73±	do.	Lebanon limestone.....	-1.8	Oct. 14	Domestic; stock.....	500	
373	26±	do.	do.	-14		do.	270	

374	75±	do.	do. (?)	-67	Oct. 14	Medicinal		Water contains H ₂ S and is salty.
375								Deepest of 7 holes drilled within radius of 500 feet without obtaining water. Formations passed through were Lebanon, Ridley, and Pierce.
376	66±		Catheys limestone	-53	Oct. 15	Domestic; stock	315	
377	40±	Limestone	Lowville limestone (?)	-81.8	do.	do.	440	
378	83±	do.	Lebanon limestone (?)	-29.0	Oct. 15	Domestic	445	
379	116±	do.	do.	-42	do.	Domestic; stock	345	
380	24±	do.	Lebanon limestone	-24.2	Oct. 15	do.	310	
381	24±	do.	do.	-18.9	do.	do.	155	
382		do.	do.	0	do.	Stock	500±	Drill hole in abandoned quarry.
383	115±	do.	do.	-104	Oct. 15	Domestic		
384	100±	do.	Lebanon limestone	-20	do.	do.		

* Determined in field with standard soap solution.

Records of springs in Maury County

No. on pl. 1	Location with respect to nearest map point	Owner or lessee	Topographic situation	Approximate altitude (feet)	Kind of rock	Stratigraphic position
• 385	Thota	Oscar Peach	Small valley	925	Limestone	St. Louis limestone.
386	Santa Fe, 2 miles northeast	Charles Harris	Base of hill	680	do.	Leipers limestone.
387	Santa Fe, 3 miles west	Village of Water Valley	Hillside	720	Shaly limestone	Do.
388	Mount Pleasant	Mount Pleasant Ice Co.	Base of hill	630	Limestone	Hermitage formation.
389	Mount Pleasant, 5 miles southeast	Bob Benderman	do.	780	do.	Bigby limestone.
390	Culleoka, 6 miles west	Stella Horn	do.	750	do.	Hermitage formation.
391	Culleoka, 6 miles southwest	Mrs. V. A. Richardson	do.	845	do.	Bigby limestone.
• 392	Culleoka, 6 miles northwest	Moore & McLean	Creek	675	do.	Lowville limestone.
• 393	Columbia, 2 miles northeast	Dr. O. J. Porter	do.	625	do.	Do.
394	Columbia, 3½ miles west	Dr. W. K. Shedd	Head of drain	750	do.	Hermitage formation.
395	Columbia, 4 miles southwest	John M. Gray	Branch	650	do.	Do.
396	Columbia	Columbia Ice & Cold Storage Co.	Bluff at edge of flood plain.	550	do.	Lowville limestone.
397	Columbia, 2½ miles north	Public	Base of hill	690	do.	Do.
• 398	Spring Hill	Branham & Hughes	do.	680	do.	Bigby limestone.
399	Match, 2 miles east	W. A. Hardison	Valley	690	do.	Lebanon limestone.
400	Culleoka, 2 miles south	T. M. Hobbs	Base of hill	705	do.	Lowville limestone.

* Analysis given in table of analyses.

MAURY COUNTY

15

GROUND WATER IN SOUTH-CENTRAL TENNESSEE

Records of springs in Maury County—Continued

No. on pl. 1	Openings		Approximate yield		Use of water	Total hardness as CaCO ₃ (parts per million)*	Remarks
	Num-ber	Character	Gallons a minute	Date of measurement (1930)			
385	1	Enlarged bedding plane	3±	July 17	Domestic; stock		
386	1	Bedding plane	1	do	Domestic		
387	1	Joint crack (?)	10±	July 13	Domestic; stock		
388	1	Enlarged bedding plane	3±	July 11	Cooling		
389	1	Solution channel	12	Oct. 17	Domestic; stock	180	Furnishes water to about 12 houses in village 1/4 mile west.
390	1	do	40±	July 13	do		Galloway Spring.
391	1	Enlarged bedding plane	8	do	do		
392	1	Enlarged joint plane	5±	do	do		Bigby Spring. Reported to have stopped flowing after each of several rains. Discussed on p. 40.
393	1	do		July 9	Medicinal		
394	1	Enlarged bedding plane	1	do	do		
395	1	do	1	July 14	Stock		
396	1	Solution channel	75±	July 9	Domestic		White Spring. Evidence of contamination at several points.
397	1	Enlarged joint crack	5±	July 17	Abandoned		
398	2	Enlarged bedding plane			Public supply		Except in summer supplies town. Supplemented by well in summer.
399	1	Concealed	24±	Oct. 14	Domestic; stock	245	
400	2	Solution channel	75	Oct. 10	do	140	

* Determined in field with standard soap solution.

MOORE COUNTY

Analyses of ground waters from Maury County

[Nos. 372 and 374 analyzed by D. F. Farrar, Tennessee Geological Survey; the rest by Margaret D. Foster, U. S. Geological Survey. Parts per million. Numbers at heads of columns correspond to numbers in tables of well and spring data]

	348	355	363	364	371	372	374
Silica (SiO ₂).....	10	7.9	8.8	6.3	12	14	14
Iron (Fe).....	.07	.17	.09	.06	.08	1.2	1.8
Calcium (Ca).....	25	33	46	98	64	235	848
Magnesium (Mg).....	4.7	4.9	30	5.2	3.8	27	52
Sodium (Na).....	1.8	9.9	13	2.3	1.7	10	35
Potassium (K).....	1.0	5.6	6.4	1.7	.7	8.0	4.1
Carbonate (CO ₃).....	0	0	0	0	0	0	0
Bicarbonate (HCO ₃).....	91	48	258	286	200	329	414
Sulphate (SO ₄).....	3.3	59	54	12	4.0	400	1,881
Chloride (Cl).....	1.8	10	1.8	2.7	1.8	18	60
Nitrate (NO ₃).....	2.3	16	2.6	30	8.5	.60	.80
Total dissolved solids.....	95	177	290	311	200	955	3,283
Total hardness as CaCO ₃ (calculated).....	80	103	238	266	176	697	2,324
Date of collection (1930).....	July 17	July 16	July 15	July 15	July 16	Oct. 14	Nov. 8

	385	392	393	398	Duck River *	Duck River *
Silica (SiO ₂).....	9.5	16	12	12	4.1	11
Iron (Fe).....	.04	.06	.05	.04	.04	.04
Calcium (Ca).....	12	86	38	69	38	40
Magnesium (Mg).....	5.4	9.5	23	5.8	4.6	4.1
Sodium (Na).....	1.8	2.3	58	5.0	2.3	1.7
Potassium (K).....	1.0	1.3	4.3	1.3	.9	1.0
Carbonate (CO ₃).....	0	0	0	0	0	0
Bicarbonate (HCO ₃).....	46	283	254	164	129	124
Sulphate (SO ₄).....	2.8	13	75	28	6.6	16
Chloride (Cl).....	2.3	2.4	21	8.0	1.7	1.6
Nitrate (NO ₃).....	13	10	.75	38	1.3	.46
Total dissolved solids.....	74	284	349	249	124	138
Total hardness as CaCO ₃ (calculated).....	52	254	189	196	114	117
Date of collection (1930).....	July 17	July 15	July 9	July 19	July 9	July 9

* Duck River at Columbia; sample taken just above dam of Tennessee Electric Power Co.; river at low stage.

* Duck River at Columbia; municipal water supply; sampled at clear well after sedimentation, alum treatment, and filtration.

MOORE COUNTY

[Area, 141 square miles; population, 4,037]

Moore County, the smallest county in the area of this report, is on the eastern border of the area, wedged in between Bedford, Coffee, Franklin, and Lincoln Counties. The county seat is Lynchburg (population 380).

Practically the entire area of the county is drained by a few small tributaries of the Elk River. The Duck River divide lies just about on its northern boundary.

No railroad enters the county. One hard-surfaced highway connects Lynchburg with the Shelbyville-Winchester highway, which passes through the northeastern part of the county. Others to Winchester and Fayetteville are under construction (1930).

Agriculture is the only industry. Large distilleries formerly operated in the county.

REFERENCE NO. 15

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
 RECORDS OF WATER WELLS IN SELECTED AREAS OF TENNESSEE

Treatment plant / O, I
 Ser Vices

EXPLANATION OF COLUMN HEADINGS

QUAD/NTN = Designation by number, quadrant and ninth of the 2.5 - minute quadrangle area in which the well is located. The leading numbers identify the 15-minute quadrangle, the next two letters identify the 7.5-minute quadrant and the last digit identifies the one-ninth subdivision of the latter.

COUNTY = County in which the well is located.

WELL NUM = Identification number assigned to the well by the State.

TAG NUM = An inspection number assigned to the well at the time of inspection by the State.

OWNER'S NAME = Name of person or organization for whom the well was drilled.

LOCATION ROAD = Name of street or road from which to access the well. Blank if unknown.

COMP DATE = Month, day and year the well was completed.

INSPCT DATE = Month, day and year the well was inspected by TDHE. Blank if well has not been inspected.

TOT DEPTH = Total depth of the well in feet.

AQ DEPTH = Depth, in feet, below land surface to the top of the shallowest aquifer or water-bearing zone tapped by the well.

TOT YIELD = Total yield of the well in gallons per minute (gpm). Yields less than one-half gpm reported as zero.

STAT LEVEL = Static water-level: depth, in feet, from the land surface to the surface of the water standing in an idle well.

CSE DEPTH = Casing depth: depth, in feet, to the bottom of the water tight casing installed in the well.

CSE TYPE = Casing type: PLAST = Plastic; STEEL = Steel; OTHER = any other material such as concrete, fiberglass or tile.

WELL FINISH = Construction of the well in the interval supplying water to the well: OPEN = Uncased or open hole; SLOT = Hand perforated or slotted pipe; SCREEN = Manufactured device designed to maintain the wall of the borehole and allow ground water to enter the well.

INTERVAL = The depth, in feet, from the top to the bottom of the interval that is open to the well.

WAT QUAL = Water Quality: a word to describe the relative quality of the well water such as GOOD, FAIR, BAD, LIME, IRON, SULFUR, SALT, OIL, GAS, OTHER.

GEO FORM = Name of the geologic formation tapped by the well (not generally reported).

LATITUDE = Latitude of well site in degrees, minutes, and seconds.

LONGITUDE = Longitude of well site in degrees, minutes, and seconds.

A/C = Accuracy Code for latitude and longitude: S = Nearest second; F = nearest 15 seconds; T = nearest 30 seconds; M = nearest minute; Blank = nearest 2.5 minutes.

LOG = Refers to availability of drillers log: Y = yes; N = no.

DRILLER = License number of driller who supervised construction of the well. Names provided upon request.

USE = Purpose for which the well was constructed: HOME = residential; COMM = commercial; etc.

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE
QUADRANGLE 10057NE TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C DRILLER LOG USE
0057NE MAURY	11900686	MILES W	06/14/1973 / /	802 775	2 --	21 STEEL	-- --	GOOD	- - - -	00120 HOME
0057NE MAURY	11900723	KNOLTON L.	08/22/1973 / /	1175 1125	3 21	23 STEEL	-- --		- - - -	00120 HOME
0057NE MAURY	11900822	DALE F.	07/16/1975 / /	1275 1240	3 196	28 STEEL	-- --	GOOD	- - - -	00120 HOME
0057NE MAURY	11909190	KERNIE COTHRAN	01/03/1967 / /	1022 1010	3 146	--	-- --		- - - -	00120
0057NE MAURY	11909193	OSCAR DAMRON	04/28/1965 / /	1096 1017	2 235	--	-- --	GOOD	- - - -	00120
0057NE MAURY	11909195	JAY DEMASTUS	05/02/1975 / /	1117 1050	4 64	--	-- --	GOOD	- - - -	00120
0057NE MAURY	11909219	EARL ERWIN NO-1	09/18/1959 / /	1047 1047	5 68	--	-- --	GOOD	- - - -	00416
0057NE MAURY	11909220	EARL ERWIN NO-2	06/28/1963 / /	1054 1030	3 148	--	-- --	GOOD	- - - -	00416
0057NE MAURY	11909241	CARLICE LOVELL	06/23/1972 / /	1085 1025	-- 130	--	-- --		- - - -	00120
0057NE MAURY	11909256	CORLICE LOVELL	06/23/1972 / /	1085 1025	-- 130	--	-- --		- - - -	00120
0057NE MAURY	11909266	JAMES H. REESE NO-2	09/29/1966 / /	883 865	3 63	--	-- --	GOOD	- - - -	00252
0057NE MAURY	11909291	B.H. WALTERS	04/06/1961 / /	905 900	6 40	--	-- --	GOOD	- - - -	00120
0057NE MAURY	11909293	STANLEY WILLIAMS	11/02/1962 / /	917 917	10 62	--	-- --	BAD	- - - -	00120
0057NE 1 MAURY	11900059	GOOD F	06/06/1964 / /	80 55	5 35	11 STEEL	-- --	BAD	35-44-34 87-06-14	S 00058 HOME
0057NE 1 MAURY	11900090	WOODY J	07/07/1964 / /	96 70	20 30	38 STEEL	-- --	GOOD	35-43-50 87-07-20	S 00120 HOME
0057NE 1 MAURY	11900160	LOCKHART J	05/13/1965 / /	100 65	10 40	6 STEEL	-- --	GOOD	35-43-04 87-07-17	S 00252 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GODWIN QUADRANGLE (0057NE) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0057NE 1 MAURY	11900431	POTTS R	01/10/1968 / /	120 50	1 --	25 STEEL	-- - --	GOOD	35-43-13 87-07-27	S	00120 HOME
0057NE 1 MAURY	11901276	BEATTY_____ CHAR ARTHUR HUTCHISO	03/14/1989 / /	100 84	12 50	20 OTHER	OPEN 20 - 100	GOOD	- - - -		00640 HOME
0057NE 1 MAURY	11901282	CONNLEY_____ JACK TAYLOR	04/24/1989 / /	175 --	0 --	51 OTHER	-- - --	OTHR	- - - -		00640 HOME
0057NE 1 MAURY	11901283	CONALLEY_____ JACK TAYLOR	05/08/1989 / /	125 85	5 72	84 OTHER	OPEN 96 - 125	GOOD	- - - -		00640 HOME
0057NE 1 MAURY	94000158	GASKELL_____ BOBB 2250 SANTA FE P	01/03/1994 / /	340 --	-- --	-- OTHER	-- - --	OTHR	- - - -		00227 HOME
0057NE 1 MAURY	94001171 D0001467	BELL_____ VIRG PARSONS BEND RD	04/01/1994 / /	350 115	18 60	63 OTHER	OPEN 63 - 350	GOOD	- - - -		00120 HOME
0057NE 2 MAURY	11900181	THURMAN E	/ /19 / /	235 44	12 94	--	-- - --	GOOD	35-44-12 87-04-20	S	00120 HOME
0057NE 2 MAURY	11900231	HAYWOOD	05/26/1966 / /	70 30	3 30	15 STEEL	-- - --	GOOD	35-43-46 87-02-41	S	00252 HOME
0057NE 2 MAURY	11900562	WALKERS J	07/24/1971 / /	65 30	-- 30	21 STEEL	-- - --	BAD	35-44-14 87-04-02	S	00120 FARM
0057NE 2 MAURY	11900864	GOAD G.	09/10/1976 / /	300 40	1 32	21 STEEL	-- - --	GOOD	35-43-12 87-03-41	S	00120 FARM
0057NE 2 MAURY	11900866	STEWART E.	09/29/1976 / /	325 290	31 190	21 STEEL	-- - --	GOOD	35-43-35 87-03-53	S	00120 HOME
0057NE 2 MAURY	11900872	MCMINN L.	11/11/1976 / /	75 45	12 30	22 STEEL	-- - --	BAD	35-43-35 87-03-53	S	00120 HOME
0057NE 2 MAURY	11900970	KAPUGA R.	10/19/1979 / /	175 155	5 --	25 STEEL	-- - --	GOOD	35-43-24 87-03-06	S	00015 HOME
0057NE 2 MAURY	11901181	D&M BUILDERS____ FITZGERALD	01/15/1987 04/13/1987	85 75	12 --	20 OTHER	OPEN 20 - 85	GOOD	35-43-14 87-03-48	S Y	00120 HOME
0057NE 2 MAURY	11901290	PORTER_____ WALT GRAVEL HILL	05/24/1989 / /	360 30	1 --	20 OTHER	OPEN 20 - 360	OTHR	- - - -		00227 HOME
0057NE 2 MAURY	92001309	MCNELLY_____ RAY PETTY LN	03/23/1992 / /	1026 --	5 --	41 STEEL	OPEN 41 - 1026	GOOD	- - - -		00015 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GODWIN QUADRANGLE (0057NE) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0057NE 2 MAURY	92001310	MCNEILY _____ RAY_ PETTY LN	03/23/1991 / /	310 80	1 --	20 STEEL	OPEN 20 - 310	GOOD	- - - -		00015 HOME
0057NE 2 MAURY	93004040	MCKAY _____ CAME MAHAN	09/27/1993 / /	100 50	6 --	20 OTHER	OPEN 20 - 100	OTHR	- - - -	Y	00227 HOME
0057NE 3 MAURY	11900380	DAMRON O	06/24/1968 / /	325 190	1 100	20 STEEL	-- -	GOOD	35-42-58 87-00-57	S	00292 HOME
0057NE 3 MAURY	11900533	SCHOATS M	08/04/1970 / /	200 45	1 --	20 STEEL	-- -		35-44-28 87-01-37	S	00120 FARM
0057NE 3 MAURY	11900552	CLARK E.	05/25/1971 / /	260 170	-- 20	21 STEEL	-- -	GOOD	35-44-47 87-00-37	S	00120 FARM
0057NE 3 MAURY	11900600	CLARK	10/29/1971 / /	102 45	8 25	21 STEEL	-- -	GOOD	35-44-39 87-00-36	S	00252 HOME
0057NE 3 MAURY	11900621	SOUTH B	05/22/1972 / /	147 125	-- 50	22 STEEL	-- -	GOOD	35-44-10 87-00-37	S	00058 HOME
0057NE 3 MAURY	11901122	MCKAY _____ CAME MAHON	07/29/1985 / /	225 170	12 --	20 OTHER	OPEN 20 - 225	FAIR	- - - -	Y	00120 HOME
0057NE 3 MAURY	94000627 D0002005	HOWARD _____ RAND PETTY LANE	03/16/1994 / /	300 --	-- --	20 OTHER	OPEN 20 - 300	OTHR	- - - -	Y	00227 HOME
0057NE 4 MAURY	11900163	HUGHES H	05/08/1965 / /	339 117	1 100	67 STEEL	-- -	GOOD	35-41-34 87-05-19	S	00252 HOME
0057NE 4 MAURY	11900229	HUGHES H	/ /19 / /	220 140	3 75	15 STEEL	-- -	GOOD	35-41-34 87-05-19	S	00252 HOME
0057NE 4 MAURY	11900393	HOOD B	09/18/1968 / /	100 75	100 --	20 STEEL	-- -		35-41-58 87-05-34	S	00120 HOME
0057NE 4 MAURY	11900468	JOHNSON M.P.	10/15/1969 / /	1016 1006	2 118	22 STEEL	-- -		35-41-37 87-05-23	S	00120 HOME
0057NE 4 MAURY	11900635	WOODY B	11/24/1972 / /	200 100	1 --	21 STEEL	-- -		35-42-14 87-06-13	S	00120 FARM
0057NE 4 MAURY	11900661	ASBRIGE J	03/15/1972 / /	100 65	-- --	21 STEEL	-- -		35-41-27 87-05-03	S	00178 FARM
0057NE 4 MAURY	11901267	MCMEEN _____ FREE ROBERTS BEND	10/21/1988 / /	250 85	2 60	20 OTHER	OPEN 20 - 250	GOOD	- - - -	Y	00640 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GODWIN QUADRANGLE (0057NE) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER
0057NE 4 MAURY	91000047	LAWLER _____ MIKE SANTAFE PK	10/26/1990 / /	300 --	0 --	-- OTHER	OPEN 0 - 300	OTHR	- - - -	- Y	00640 HOME
0057NE 4 MAURY	91000048	LAWLER _____ MIKE SANTA FE PK	10/29/1990 / /	250 225	3 40	20 OTHER	OPEN 20 - 250	GOOD	- - - -	- Y	00640 HOME
0057NE 5 MAURY	11900006	RICHARDSON J	09/12/1963 / /	200 180	6 100	5 STEEL	-- - --	GOOD	35-41-12 87-03-20	S	00120 HOME
0057NE 5 MAURY	11900135	PARKS J	12/18/1964 / /	304 294	15 150	9 STEEL	-- - --	GOOD	35-41-35 87-02-38	S	00058 HOME
0057NE 5 MAURY	11900354	WILEY C	07/18/1967 / /	100 40	10 40	21 STEEL	-- - --	GOOD	35-41-16 87-04-01	S	00120 HOME
0057NE 5 MAURY	11900395	THURMAN F	09/29/1968 / /	125 98	150 --	21 STEEL	-- - --		35-41-26 87-04-50	S	00120 HOME
0057NE 5 MAURY	11900397	PREICES E	10/07/1968 / /	140 115	100 --	21 STEEL	-- - --		35-41-25 87-04-49	S	00120 HOME
0057NE 5 MAURY	11901095	DAVIS _____ JOHN DOWELL BRANCH	09/24/1984 / /	225 --	0 --	49 OTHER	OPEN 49 - 225	OTHR	- - - -	- Y	00120 HOME
0057NE 5 MAURY	11901096	DAVIS _____ JOHN DOWELL BRANCH	09/14/1984 / /	295 --	-- --	-- OTHER	-- - --	OTHR	- - - -	- Y	00120 HOME
0057NE 5 MAURY	11901097	DAVIS _____ JOHN DOWELL BRANCH	09/19/1984 / /	205 58	1 48	46 OTHER	OPEN 46 - 205	GOOD	- - - -	- Y	00120 HOME
0057NE 5 MAURY	94000626 D0002006	HOWARD _____ RAND PETTY LN	03/17/1994 / /	150 130	15 --	20 OTHER	OPEN 20 - 150	OTHR	- - - -	- Y	00227 HOME
0057NE 6 MAURY	11900173	WALLS D	07/09/1965 / /	225 --	-- --	20 STEEL	-- - --		35-41-28 87-00-28	S	00252
0057NE 6 MAURY	11900176	PARKS N	/ /19 / /	306 165	50 125	31 STEEL	-- - --	GOOD	35-41-18 87-01-52	S	00120 HOME
0057NE 6 MAURY	11900194	WEST _____ GLEN DARKS MILL	08/18/1965 / /	153 68	4 40	7 STEEL	OPEN 7 - 153	BAD	35-41-15 87-01-26	S Y	00058 HOME
0057NE 6 MAURY	11901059	STAR DAIRY THETA RD	8/28/1983 / /	260 49	2 0	21 STEEL	21 - 260	H2S	35-40-24 87-02-17	S Y	00103
0057NE 6 MAURY	11901131	TVA _____ CARTER CREEK	11/04/1985 / /	300 --	0 --	20 OTHER	OPEN 20 - 300	OTHR	- - - -	- Y	00120 IND

12/01/94

PAGE 5

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GOLWIN QUADRANGLE (100' X 7' IN.)

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER LOG USE
0057NE 6 MAURY	11901132	TVA CARTERS CREEK	11/05/1985 07/28/1986	300 175	3 --	20 OTHER	OPEN 20 - 300	BAD	35-39-35 87-02-38	M Y	00120 IND
0057NE 7 MAURY	11900026	GREY T	09/28/1963 / /	210 170	1 20	4 STEEL	-- - --	BAD	35-37-52 86-06-30	S	00120 HOME
0057NE 7 MAURY	11900065	VENSON W	04/07/1964 / /	127 50	20 40	7 STEEL	-- - --	GOOD	35-38-33 87-06-15	S	00120 HOME
0057NE 7 MAURY	11900069	JOICE K	03/13/1964 / /	262 245	4 160	21 STEEL	-- - --	GOOD	35-38-23 87-06-09	S	00120 HOME
0057NE 7 MAURY	11900464	SMITH C	11/02/1969 / /	540 510	4 --	23 STEEL	-- - --	GOOD	35-38-18 87-06-11	S	00015 HOME
0057NE 7 MAURY	11900873	BOOKER J.	11/08/1976 / /	1050 --	6 150	-- STEEL	-- - --	GOOD	35-38-12 87-05-58	S	00120 HOME
0057NE 7 MAURY	11901113	COTHRAN OLD WILLIAMSPOR	KERN 03/21/1985 / /	1250 1025	12 --	285 OTHER	OPEN 285 - 1250	OTHR	- - - -	- Y	00120 FARM
0057NE 7 MAURY	11901127	MABRY OLD WILLIAMS PO	KENN 11/12/1985 / /	360 80	1 --	20 OTHER	OPEN 20 - 360	OTHR	- - - -	- Y	00120 HEAT
0057NE 7 MAURY	11901128	MABRY OLD WILLIAMSPOR	KENN 11/13/1985 / /	360 --	-- --	20 OTHER	OPEN 20 - 360	OTHR	- - - -	- Y	00120 HEAT
0057NE 7 MAURY	91000724	RICHARDSON ESTES	CHAR 02/06/1991 / /	345 --	0 --	20 OTHER	OPEN 20 - 245	GOOD	- - - -	- Y	00120 HOME
0057NE 8 MAURY	11900029	GRAY M	11/16/1963 / /	120 120	1 1	661 STEEL	-- - --		35-39-22 87-04-00	S	00000 HOME
0057NE 8 MAURY	11900120	EMBER P	07/23/1964 / /	175 160	6 65	24 STEEL	-- - --	GOOD	35-37-38 87-04-32	S	00120 HOME
0057NE 8 MAURY	11900151	SISK D	03/19/1965 / /	300 240	20 40	39 STEEL	-- - --		35-39-40 87-03-43	S	00120 HOME
0057NE 8 MAURY	11900183	SLUG C	/ /19 / /	190 158	24 120	31 STEEL	-- - --	GOOD	35-39-00 87-02-52	S	00120 IND
0057NE 8 MAURY	11900215	BROUSONPP	12/13/1965 / /	205 165	1 40	60 STEEL	-- - --	GOOD	35-39-22 87-04-10	S	00252 IND
0057NE 8 MAURY	11900230	KELLEY E	/ /19 / /	187 130	7 50	20 STEEL	-- - --	GOOD	35-39-49 87-04-47	S	00252 HOME

12/01/94

PAGE 6

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GODWIN QUADRANGLE (0057NE) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0057NE 8 MAURY	11900240	GIBSON L	08/18/1966 / /	1000 640	2 50	10 STEEL	-- - --	GOOD	35-39-20 87-03-29	S	00252 IND
0057NE 8 MAURY	11900330	LUNA J	10/31/1967 / /	950 890	2 40	21 STEEL	-- - --	GOOD	35-39-58 87-04-30	S	00120 MDOM
0057NE 8 MAURY	11900875	HERMAN G.	/ /19 / /	1000 905	18 120	23 STEEL	-- - --	GOOD	35-38-17 87-11-31	S	00120 HOME
0057NE 9 MAURY	11900227	REESE J	06/17/1966 / /	840 800	3 100	5 STEEL	-- - --	GOOD	35-39-18 87-00-59	S	00252 HOME
0057NE 9 MAURY	11901171	TUCKER _____ ARCH WEATHERSPOON RD	03/23/1987 / /	125 80	1 --	20 OTHER	OPEN -- - --	OTHR	- - - -	- Y	00001 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE
QUADRANGLE (0057SE) TN.

QUAD / COUNTY	NTH REG NUM	WELL NUM OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0057SE MAURY	11900389	LANGA A CAYCE LANE	10/21/1968 / /	988 960	10 122	22 STEEL	-- --		35-36-30 87-05-30	T	00120
0057SE MAURY	11909172	DR. ANDY BERRY	08/00/1975 / /	1179 1150	8 131	--	-- --	GOOD	-- --		00120
0057SE MAURY	11909184	CLIFFORD CARTER	11/00/1962 / /	740 --	10 --	--	-- --	GOOD	-- --		00416
0057SE MAURY	11909188	MARLIN CHURCH	08/11/1971 / /	1072 1040	-- 178	--	-- --		-- --		00120
0057SE MAURY	11909194	DOUGLAS DEMASTUS	11/24/1969 / /	951 80	31 85	--	-- --	GOOD	-- --		00120
0057SE 1 MAURY	11900175	ESKEW F	/ /19 / /	190 174	24 100	13 STEEL	-- --	GOOD	35-36-03 87-05-43	S	00120 HOME
0057SE 1 MAURY	11900191	JOHNS M	04/21/1965 / /	202 180	18 100	18 STEEL	-- --	GOOD	35-37-10 87-06-09	S	00120 HOME
0057SE 1 MAURY	11901203	BRADLEY____BERN JEWELL DR	07/02/1987 / /	105 80	50 22	64 OTHER	OPEN 64 - 105	GOOD	-- --	Y	00120 IRR
0057SE 1 MAURY	90002513	UNDERWOOD____DONA SUGAR HILL	07/05/1990 / /	105 22	20 2	20 OTHER	OPEN 0 - 105	BAD	-- --	Y	00640 HOME
0057SE 2 MAURY	90000757	L_D_S_CHURCH____ HY WAY 50	09/28/1989 / /	320 70	1 --	-- OTHER	-- --	OTHR	-- --	Y	00227 IRR
0057SE 3 MAURY	11900062	PRINCE D	/ /19 / /	825 --	-- --	12 STEEL	-- --	BAD	35-35-41 87-00-02	S	00100 HOME
0057SE 3 MAURY	11900178	GRAY F	05/25/1965 / /	186 130	1 80	--	-- --	GOOD	35-35-32 87-01-39	S	00120 HOME
0057SE 3 MAURY	11900198	WHITE H	08/30/1965 / /	202 80	2 30	11 STEEL	-- --	BAD	35-35-53 87-00-35	S	00058 HOME
0057SE 3 MAURY	11900528	HARDY J	09/02/1970 / /	185 140	15 58	23 STEEL	-- --		35-36-38 87-00-02	S	00120 HOME
0057SE 3 MAURY	11909044	GLADYS CHEEK	/ /19 / /	-- --	-- --	--	-- --		35-35-27 87-00-20	S	OTHR
0057SE 3 MAURY	11909047	W E CHEEK	/ /19 / /	-- --	-- 57	--	-- --		35-35-26 87-00-15	S	OTHR

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE COLUMBIA QUADRANGLE (0057SE) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER
0057SE 3 MAURY	11909048	MAE CRAIN HOWELL	/ /19 / /	-- --	-- --	-- --	-- --	-- --	35-35-29 87-00-00	S OTHR	
0057SE 3 MAURY	11909049	WADE CHAPPELL	/ /19 / /	-- --	-- 37	-- --	-- --	-- --	35-35-58 87-00-29	S OTHR	
0057SE 3 MAURY	11909050	WADE CHAPPELL	/ /19 / /	-- --	-- --	-- --	-- --	-- --	35-35-51 87-00-31	S OTHR	
0057SE 3 MAURY	11909051	DAVID T WARREN	/ /19 / /	-- --	-- --	-- --	-- --	-- --	35-35-26 87-00-15	S OTHR	
0057SE 3 MAURY	11909055	W F HARMON	/ /19 / /	-- --	-- --	-- --	-- --	-- --	35-36-01 87-00-31	S OTHR	
0057SE 3 MAURY	11909056	W F HARMON	/ /19 / /	-- --	-- --	-- --	-- --	-- --	35-36-03 87-00-29	S FARM	
0057SE 4 MAURY	11900021	PATRICK J	11/22/1963 / /	375 360	3 --	25 STEEL	-- --	GOOD --	35-33-09 87-06-28	S HOME	00057
0057SE 4 MAURY	11900096	JONES F	05/15/1964 / /	200 170	15 60	16 STEEL	-- --	-- --	35-33-36 87-05-56	S HOME	00120
0057SE 4 MAURY	11900774	YOUNGBLOOD E TROUSDALE	09/30/1974 / /	1170 1170	10 300	69 STEEL	-- --	GOOD --	35-34-30 87-06-00	T HOME	00015
0057SE 4 MAURY	11900831	JEWELL C.	04/04/1975 / /	1100 1095	18 --	21 STEEL	-- --	GOOD --	35-34-10 87-06-51	S HOME	00120
0057SE 4 MAURY	11901184	NICKOLSON_____ TROUSDALE LANE	02/11/1987 / /	145 25	12 4	20 OTHER	OPEN 20 -	FAIR 145	- - - -	- Y	00120 OTHR
0057SE 4 MAURY	11901248	MOBLEY_____ SOWELL HOLLOW	07/30/1988 / /	105 --	0 --	-- OTHER	-- --	OTHR --	- - - -	- Y	00640 HOME
0057SE 4 MAURY	11901249	MOBLEY_____ SOWELL HOLLOW	07/31/1988 / /	105 18	1 --	20 OTHER	OPEN 20 -	GOOD 105	- - - -	- Y	00640 HOME
0057SE 4 MAURY	11901252	JENKINS_____ TROUSDALE LANE	07/31/1988 / /	65 --	0 --	20 OTHER	OPEN 20 -	OTHR 65	- - - -	- Y	00640 HOME
0057SE 4 MAURY	11909230	JEWELL HIDHWAY 43	04/07/1975 / /	1100 1050	18 42	-- --	-- --	GOOD --	35-34-30 87-07-30	T	00120
0057SE 5 MAURY	11900027	KENNEDY F	10/16/1963 / /	239 215	10 98	12 STEEL	-- --	GOOD --	35-33-29 87-02-45	S HOME	00120

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE COLUMBIA QUADRANGLE (0057SE) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0057SE 5 MAURY	11900028	LITTON L	11/01/1963 / /	97 44	10 35	14 STEEL	-- - --	BAD	35-34-25 87-03-43	S	00120 HOME
0057SE 5 MAURY	11900100	WEBSTER G	05/15/1964 / /	137 123	10 65	12 STEEL	-- - --	GOOD	35-34-43 87-03-26	S	00120 HOME
0057SE 5 MAURY	11900192	MCFARLAND L	05/03/1965 / /	165 150	5 5	22 STEEL	-- - --		35-33-12 87-02-40	S	00120 HOME
0057SE 5 MAURY	11900859	CHAPMAN F. ALBERT MATHEWS	07/21/1976 / /	100 45	5 30	22 STEEL	-- - --	GOOD	35-33-15 87-04-25	S	00120 HOME
0057SE 5 MAURY	11901052	OWENS COTT INDIAN SPRINGS	5/27/1983 / /	514 337	20 90	21 STEEL	21 - 514	GOOD	- - - -		00103 Y
0057SE 6 MAURY	11900038	VOSS J	01/02/1964 / /	226 160	1 109	17 STEEL	-- - --	GOOD	35-33-12 87-01-08	S	00058 HOME
0057SE 6 MAURY	11900124	HOMMONS P	07/02/1964 / /	98 65	30 43	38 STEEL	-- - --	GOOD	35-34-56 87-01-30	S	00120 HOME
0057SE 6 MAURY	11900152	RUMMAGE A	11/14/1964 / /	200 50	-- 40	14 STEEL	-- - --	GOOD	35-33-58 87-00-25	S	00120 HOME
0057SE 6 MAURY	11900189	WITHERSPOON R	04/05/1965 / /	735 720	2 94	15 STEEL	-- - --	GOOD	35-34-38 87-00-10	S	00120 OTHR
0057SE 6 MAURY	11900295	HICKMAN U	06/14/1966 / /	935 935	2 100	30 STEEL	-- - --		35-33-43 87-01-15	S	00120 HOME
0057SE 6 MAURY	11901153	SANDERS _____ FRED HAYES DENTON	02/26/1986 / /	248 35	1 25	20 STEEL	OPEN 20 - 248	GOOD	- - - -		00640 Y HOME
0057SE 6 MAURY	11901272	BREWER _____ LARR COVEY HOLLOW	02/02/1988 05/04/1989	85 40	50 6	20 OTHER	OPEN -- - --	GOOD 001783	35-29-06 87-00-37	S Y	00640 HOME
0057SE 6 MAURY	11901280	FREDERICK _____ DR_D KIPPSFORD POND	05/08/1989 / /	105 --	0 --	-- OTHER	-- - --	OTHR	- - - -		00640 Y IRR
0057SE 6 MAURY	11909033	WILLIAM H TROOP	/ /19 / /	-- --	-- --	--	-- - --		35-33-32 86-00-06	S	HOME
0057SE 6 MAURY	11909036	WILSON F WITHERSPOO	/ /19 / /	-- --	-- --	--	-- - --		35-34-25 86-00-03	S	HOME
0057SE 6 MAURY	11909037	DAISY DEAN	/ /19 / /	-- --	-- 60	--	-- - --		35-34-47 87-00-10	S	OTHR

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE COLUMBIA QUADRANGLE (0057SE) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0057SE 7 MAURY	11900211	GADCOURT R	11/11/1965 / /	320 280	-- 250	5 STEEL	-- - --	GOOD	35-30-04 87-06-28	S	00252 HOME
0057SE 7 MAURY	11901163	NORMAN _____ DALE REESE CHURCH	08/14/1986 / /	225 60	0 --	20 OTHER	OPEN 20 - 225	OTHR	- - - -		00120 HOME
0057SE 7 MAURY	11901235	VICK _____ DOUG SOWELL HOLLOW	06/14/1988 / /	85 55	5 --	20 OTHER	OPEN 20 - 85	GOOD	- - - -		00640 HOME
0057SE 7 MAURY	91000715	GRZYBOWSKI _____ ROBE SOWELL HOLLOW R	08/10/1987 5/ 5/1990	300 80	4 16	20 OTHER	OPEN 20 - 300	OTHR 001704	35-32-24 87-07-26	S Y	00640 HOME
0057SE 7 MAURY	91000716	GRZYBOWSKI _____ ROBE SOWELL HOLLOW	10/18/1987 / /	125 --	0 6	-- OTHER	-- - --	OTHR	- - - -		00640 HOME
0057SE 7 MAURY	91000717	GRZYBOWSKI _____ ROBE SOWELL HOLLOW	10/16/1987 / /	125 90	0 --	-- OTHER	-- - --	OTHR	- - - -		00640 HOME
0057SE 7 MAURY	91000718	GRZYBOWSKI _____ ROBE SOWELL HOLLOW	10/12/1987 / /	225 --	-- --	-- OTHER	-- - --	OTHR	- - - -		00640 OTHR
0057SE 7 MAURY	91000719	GRZYBOWSKI _____ ROBE SOWELL HOLLOW	10/10/1987 / /	100 70	1 --	-- OTHER	OPEN 20 - 70	OTHR	- - - -		00640 HOME
0057SE 8 MAURY	11900017	SCRIFINCE P	10/22/1963 / /	309 145	1 70	20 STEEL	-- - --	GOOD	35-32-02 87-02-54	S	00058 HOME
0057SE 8 MAURY	11900113	SCRIFNER E	10/12/1964 / /	46 46	30 20	46 STEEL	-- - --	GOOD	35-31-02 87-03-18	S	00058 HOME
0057SE 8 MAURY	11900182	HARRIS J	06/17/1965 / /	250 90	-- 200	18 STEEL	-- - --	GOOD	35-31-09 87-04-06	S	00120 HOME
0057SE 8 MAURY	11900187	MORROW E	07/16/1965 / /	346 335	-- 246	9 STEEL	-- - --		35-31-14 87-04-44	S	00120 HOME
0057SE 8 MAURY	11900188	HARRIS _____ MARY BIGBYVILLE	06/30/1965 / /	168 90	0 80	6 STEEL	OPEN 6 - 168		35-31-17 87-03-55	S Y	00120 HOME
0057SE 8 MAURY	11900193	BENDERMAN L	05/21/1965 / /	260 210	11 75	38 STEEL	-- - --		35-30-01 87-03-15	S	00120 HOME
0057SE 8 MAURY	11900576	GILLIAM _____ J BIGBYVILLE	06/27/1971 / /	945 930	2 100	21 STEEL	-- - --	GOOD	35-31-30 87-00-00	T	00120 FARM
0057SE 8 MAURY	11900871	FARRIS W.	11/12/1976 / /	75 40	200 6	51 STEEL	-- - --	GOOD	36-30-46 87-02-50	S	00120 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE COLUMBIA QUADRANGLE (0057SE) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER HOME
0057SE 8 MAURY	11901105	MATTHEWS _____ DUNC HOPEWELL	02/28/1985 / /	290 120	2 --	22 OTHER	OPEN 22 - 290	OTHR -	- - - -	Y	00120 HOME
0057SE 8 MAURY	11909249	MCCAINS C.P.CHURCH MCCAINS LANE	03/28/1966 / /	934 824	3 113	--	-- - --	GOOD	35-31-00 87-03-00	T	00058 MDOM
0057SE 9 MAURY	11900018	JACKSON B	11/16/1963 / /	300 70	-- 22	18 STEEL	-- - --	GOOD	35-30-57 87-00-10	S	00058 HOME
0057SE 9 MAURY	11900123	PERRY H	06/06/1964 / /	225 220	1 5	13 STEEL	-- - --	GOOD	35-31-48 87-00-53	S	00120 OTHR
0057SE 9 MAURY	11900142	HINDMAN H	01/22/1965 / /	75 65	25 25	10 STEEL	-- - --	BAD	35-30-35 87-01-53	S	00100 HOME
0057SE 9 MAURY	11900172	ERWIN C COVEY HOLLOW	/ /19 / /	300 290	3 135	35 STEEL	OPEN 35 - 300	BAD	35-30-22 87-01-53	S Y	00252 HOME
0057SE 9 MAURY	11900221	CHURCH	03/28/1966 / /	934 824	1 113	16 STEEL	-- - --	BAD	35-30-41 87-01-45	S	00058 HOME
0057SE 9 MAURY	11900451	BIBLE B	03/30/1970 / /	817 806	4 22	--	-- - --	GOOD	35-31-28 87-00-11	S	00058 HOME
0057SE 9 MAURY	11901093	CHEATHAM _____ GRAN COVEY HOLLOW	09/27/1984 / /	150 67	5 --	21 STEEL	OPEN 21 - 150	GOOD	- - - -	Y	00120 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE QUADRANGLE (0064NW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C DRILLER LOG USE
0064NW MAURY	11900293	FOSTER B	09/14/1966 / /	890 885	2 110	33 STEEL	-- --	GOOD	- - - -	00120 HOME
0064NW MAURY	11900536	HUMBLE OIL CO	07/09/1970 / /	892 870	12 89	21 STEEL	-- --		- - - -	00120 COMM
0064NW MAURY	11900549	BUTLER G	11/30/1971 / /	895 885	4 130	20 STEEL	-- --	BAD	- - - -	00058 HOME
0064NW MAURY	11900606	SMITH W	08/01/1971 / /	926 920	3 140	20 STEEL	-- --	BAD	- - - -	00058
0064NW MAURY	11900638	BEARD C	07/05/1972 / /	755 730	6 --	23 STEEL	-- --	BAD	- - - -	00120 FARM
0064NW MAURY	11900712	JONES G	03/13/1973 / /	1028 1000	4 --	28 STEEL	-- --	GOOD	- - - -	00120 FARM
0064NW MAURY	11900790	ROBERT.HALL	08/29/1974 / /	774 770	15 84	--	-- --	GOOD	- - - -	00120
0064NW MAURY	11909170	JAMES BAILEY	04/05/1973 / /	863 --	3 47	--	-- --		- - - -	00120
0064NW MAURY	11909175		00/00/1955 / /	-- --	-- --	--	-- --		- - - -	00416
0064NW MAURY	11909181	TOM CAMUSE	02/00/1962 / /	770 765	5 --	--	-- --	GOOD	- - - -	
0064NW MAURY	11909183	ROBERT L. CARPENTER	00/00/1962 / /	750 745	5 --	--	-- --	GOOD	- - - -	00057
0064NW MAURY	11909186	HOWARD HARTLEY	12/27/1971 / /	726 700	3 81	--	-- --		- - - -	00227
0064NW MAURY	11909187	AUSTIN CHAPPELL	00/00/1960 / /	801 --	-- 50	--	-- --	BAD	- - - -	00416
0064NW MAURY	11909196	ROY CARUTHERS	04/23/1968 / /	989 985	5 166	--	-- --	BAD	- - - -	00058
0064NW MAURY	11909197	RAYMOND CATES	08/04/1973 / /	802 750	4 93	--	-- --		- - - -	00120
0064NW MAURY	11909199	MARLON HENDRICKS	00/00/1960 / /	754 750	5 --	--	-- --	BAD	- - - -	00057

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE QUADRANGLE (0064NW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C DRILLER LOG USE
0064NW MAURY	11909202	EARL HAYES	03/02/1966 / /	794 790	10 --	--	-- - --	BAD	- - - -	00120
0064NW MAURY	11909204	HOWARD HARTLEY	12/27/1971 / /	726 700	3 81	--	-- - --		- - - -	00227
0064NW MAURY	11909207	WALLACE HALL	11/13/1971 / /	905 890	5 121	--	-- - --		- - - -	00120
0064NW MAURY	11909212	RICHARD FORD	11/25/1969 / /	1004 1000	7 --	--	-- - --		- - - -	00058
0064NW MAURY	11909214	ALMOND FITZGERALD	00/00/1962 / /	814 810	5 --	--	-- - --		- - - -	00058
0064NW MAURY	11909218	NOEL EVANS	12/07/1966 / /	918 880	1 17	--	-- - --	GOOD	- - - -	00120
0064NW MAURY	11909221	JOE DUVAL	05/28/1968 / /	798 784	15 119	--	-- - --	GOOD	- - - -	00120
0064NW MAURY	11909231	TOMMY JOHNSON	00/00/1960 / /	784 --	-- 36	--	-- - --		- - - -	00416
0064NW MAURY	11909240	LARRY LOGUE	11/00/1970 / /	921 --	1 130	--	-- - --	BAD	- - - -	00058
0064NW MAURY	11909242	GENE LOVETT	00/00/1959 / /	778 775	5 --	--	-- - --	GOOD	- - - -	00057
0064NW MAURY	11909243	DR.DOUGLAS OVERTON	10/01/1964 / /	835 --	-- --	--	-- - --		- - - -	00252
0064NW MAURY	11909245	T.B.MALONE	10/12/1971 / /	741 --	3 47	--	-- - --	GOOD	- - - -	00252
0064NW MAURY	11909250	JESSE MCNEELY	07/00/1962 / /	750 --	-- --	--	-- - --		- - - -	
0064NW MAURY	11909254	KENNETH MULLINEX	11/00/1961 / /	893 860	3 100	--	-- - --	BAD	- - - -	00058
0064NW MAURY	11909259	DR.DOUGLAS OVERTON	10/01/1964 / /	835 758	-- --	--	-- - --		- - - -	00252
0064NW MAURY	11909260	FOSTER PARKS	00/00/1962 / /	901 --	-- --	--	-- - --		- - - -	

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE QUADRANGLE (0064NW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER
0064NW MAURY	11909263	EVELYN PRINCE	02/22/1972 / /	820 800	3 36	--	-- - --		- - - -		00120
0064NW MAURY	11909265	ABENY (NOEL EVANS)	12/07/1966 / /	918 880	1 17	--	-- - --	GOOD	- - - -		00120
0064NW MAURY	11909267	JOHN REESE	04/30/1971 / /	817 800	4 107	32	-- - --	GOOD	- - - -		00120
0064NW MAURY	11909268	GARRETT RIGGS	10/09/1972 / /	928 900	2 66	--	-- - --		- - - -		00120
0064NW MAURY	11909269	GARRETT R. RIGGS NO-	02/26/1973 / /	1214 --	-- --	--	-- - --		- - - -		00120
0064NW MAURY	11909274	VIRGIL SEALEY	00/00/1962 / /	790 780	5 --	--	-- - --		- - - -		00057
0064NW MAURY	11909276	J.B. SIMMONS, JR.	00/00/1960 / /	775 775	10 20	--	-- - --	BAD	- - - -		00416
0064NW MAURY	11909278	WILBURN SMITH	/ /19 / /	-- --	-- --	--	-- - --		- - - -		00416
0064NW MAURY	11909288	JAMES C. VAUGHN NO-1	07/17/1969 / /	939 930	12 165	--	-- - --	GOOD	- - - -		00120
0064NW 1 MAURY	11900166	QUICK J	08/06/1965 / /	202 180	48 90	33 STEEL	-- - --	GOOD	35-42-41 86-58-48	S	00058 HOME
0064NW 1 MAURY	11900216	SULLIVAN S	12/15/1965 / /	973 965	3 110	23 STEEL	-- - --	BAD	35-42-38 86-58-80	S	00058 HOME
0064NW 1 MAURY	11900294	U T EXPERIMENTAL	08/26/1966 / /	860 850	2 95	31 STEEL	-- - --		35-43-13 86-57-58	S	00120 MUN
0064NW 1 MAURY	91000723	CRIGGER _____ WALD	01/31/1991 / /	85 85	40 --	62 OTHER	OPEN 62 -	GOOD 85	- - - -	Y	00120 HOME
0064NW 2 MAURY	11900081	CRUMP T	07/08/1964 / /	120 40	2 12	10 STEEL	-- - --	GOOD	35-44-37 86-55-29	S	00094 HOME
0064NW 2 MAURY	11900225	WEAVER J	02/24/1966 / /	58 45	10 20	37 STEEL	-- - --	GOOD	35-43-15 86-55-24	S	00058 HOME
0064NW 2 MAURY	11900318	MUMS H	02/28/1967 / /	155 138	200 12	10	-- - --		35-44-25 86-55-26	S	00120 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE CARTERS-CREEK QUADRANGLE (0064NW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER LOG USE
0064NW 2 MAURY	11900614	REED J	08/24/1972 / /	144 --	0 --	--	-- - --		35-42-41 86-55-25	S	00058 FARM
0064NW 2 MAURY	11900677	REID J	10/10/1972 / /	1025 775	-- --	21 STEEL	-- - --	GOOD	35-42-41 86-55-25	S	00492 HOME
0064NW 2 MAURY	93003691	NEAL _____ MIKE CRAFTON RD	08/26/1993 / /	804 780	7 --	20 STEEL	OPEN 20 - 804	GOOD	- - - -	Y	00015 HOME
0064NW 3 MAURY	11900056	RENOLD J	04/30/1964 / /	75 55	10 15	38 STEEL	-- - --	GOOD	35-43-20 86-53-50	S	00007 HOME
0064NW 3 MAURY	11900590	LUNN S	01/26/1971 / /	848 815	3 74	52 STEEL	-- - --	BAD	35-44-17 86-53-30	S	00120 FARM
0064NW 3 MAURY	11901193	SPRING_HILL _____ CITY LUNN	07/17/1987 / /	150 73	50 10	20 OTHER	OPEN 20 - 150	GOOD	- - - -	Y	00120 MUN
0064NW 3 MAURY	11901194	SPRINGHILL _____ CITY LUNN	07/20/1987 / /	175 85	6 9	20 OTHER	OPEN 20 - 175	OTHR	- - - -	Y	00120 MUN
0064NW 4 MAURY	11900156	KINCAID O	04/06/1965 / /	203 133	-- --	6 STEEL	-- - --	BAD	35-40-37 86-57-41	S	00058 HOME
0064NW 4 MAURY	11900167	TALLEY H	07/24/1965 / /	802 795	1 80	34 STEEL	-- - --	BAD	86-58-55 35-41-48	S	00058 HOME
0064NW 4 MAURY	11900209	HOLANDSS	09/20/1965 / /	303 140	-- 75	7 STEEL	-- - --	BAD	35-40-26 86-59-35	S	00058 HOME
0064NW 4 MAURY	11900608	SHAYTON E	05/05/1971 / /	200 98	3 45	20 STEEL	-- - --	GOOD	35-40-45 86-57-45	S	00058 FARM
0064NW 4 MAURY	11900976	NICHOLSON L	09/26/1979 / /	950 915	3 --	42 STEEL	-- - --	GOOD	35-40-08 86-58-53	S	00120 HOME
0064NW 4 MAURY	94000089 D0000385	DUVALL _____ KERI OLLIE CHUNN	11/30/1993 / /	165 80	3 --	20 STEEL	OPEN 20 - 165	GOOD	- - - -	Y	00015 HOME
0064NW 5 MAURY	11900054	AKIN S	03/11/1964 / /	242 140	4 45	20 STEEL	-- - --	BAD	35-41-42 86-57-03	S	00058 HOME
0064NW 5 MAURY	11900117	LOGUE C	10/30/1964 / /	80 26	-- 11	17 STEEL	-- - --	GOOD	35-41-08 86-57-06	S	00057 HOME
0064NW 5 MAURY	11900118	BAUGUS O	11/07/1964 / /	225 170	-- --	18 STEEL	-- - --	BAD	35-40-56 86-57-35	S	00057 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE CARTERS-CREEK QUADRANGLE (0064NW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064NW 5 MAURY	11900137	LOVETT E	12/02/1964 / /	190 182	1 96	36 STEEL	-- - --	BAD	35-41-21 86-55-01	S	00057 HOME
0064NW 5 MAURY	11900146	SMITH E	01/24/1965 / /	130 40	1 30	6 STEEL	-- - --	GOOD	35-41-45 86-56-31	S	00058 HOME
0064NW 5 MAURY	11900207	DALE J	10/15/1965 / /	204 180	5 75	34 STEEL	-- - --	GOOD	35-40-49 86-56-26	S	00058 HOME
0064NW 5 MAURY	11900453	JONES S	04/28/1970 / /	152 145	6 20	29 STEEL	-- - --	GOOD	35-41-30 86-55-15	S	00058
0064NW 5 MAURY	11900619	WEST E C	07/14/1972 / /	300 270	7 120	45 STEEL	-- - --	GOOD	35-40-37 86-57-17	S	00058 HOME
0064NW 5 MAURY	11900673	LOVE T	06/06/1973 / /	281 --	5 45	36 STEEL	-- - --	GOOD	35-40-54 86-56-30	S	00492 HOME
0064NW 5 MAURY	11901224	AGENT _____ HARO GREEN MILL	09/09/1987 / /	1055 1050	10 55	24 OTHER	OPEN 24 - 1055	GOOD	- - - -		00120 HOME
0064NW 6 MAURY	11900012	ABERNATHY S	09/28/1963 / /	270 140	1 140	10 STEEL	-- - --	BAD	35-41-49 86-53-56	S	00057 HOME
0064NW 6 MAURY	11900061	WEAVER W	05/24/1964 / /	903 850	1 140	25 STEEL	-- - --	BAD	35-42-25 86-54-45	S	00058 HOME
0064NW 6 MAURY	11900071	MCNEELY J	06/19/1964 / /	75 58	12 5	10 STEEL	-- - --	BAD	35-42-10 86-53-59	S	00057 HOME
0064NW 6 MAURY	11900072	MCNEELY J	06/22/1964 / /	92 80	44 41	23 STEEL	-- - --	GOOD	35-41-58 86-53-50	S	00057 HOME
0064NW 6 MAURY	11900073	RUMMAGE J	06/26/1964 / /	57 89	110 12	68 STEEL	-- - --		35-42-07 86-53-56	S	00000 HOME
0064NW 6 MAURY	11900077	STEWART B	07/14/1964 / /	200 --	0 --	100 STEEL	-- - --		35-40-55 86-52-56	S	00057 HOME
0064NW 6 MAURY	11900105	LEE B	10/06/1964 / /	100 68	-- 35	27 STEEL	-- - --	GOOD	35-40-08 86-53-53	S	00057 HOME
0064NW 6 MAURY	11900502	HARRIS C	03/16/1970 / /	300 --	0 --	--	-- - --		35-41-17 86-54-37	S	00252 OTHR
0064NW 6 MAURY	11900558	BROWN H	08/23/1971 / /	800 785	12 124	25 STEEL	-- - --	GOOD	35-41-33 86-53-19	S	00120 FARM

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE CARTERS-CREEK QUADRANGLE (0064NW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064NW 6 MAURY	11900569	REESE J	04/28/1971 / /	815 795	4 --	33 STEEL	-- - --	GOOD	35-41-27 86-53-10	S	00120 FARM
0064NW 6 MAURY	11900617	LEE J	08/08/1972 / /	300 --	0 --	21 STEEL	-- - --		35-41-52 86-53-56	S	00492 OTHR
0064NW 6 MAURY	11900675	MURPHY F	02/15/1973 / /	868 885	-- 45	21 STEEL	-- - --	GOOD	35-41-43 86-53-28	S	00492 HOME
0064NW 6 MAURY	11900778	VAUGHN J.C.NO-2	09/13/1974 / /	1100 1075	4 184	26 STEEL	-- - --	GOOD	35-41-17 86-54-43	S	00120 FARM
0064NW 6 MAURY	11900781	PARRISH R.	/ /19 / /	-- --	-- --	21 STEEL	-- - --		35-40-16 86-54-26	S	
0064NW 6 MAURY	11900918	GREEN J	04/00/1978 / /	230 50	1 --	30 STEEL	-- - --	GOOD	35-40-27 86-54-27	S	00120 HOME
0064NW 6 MAURY	11900928	REED J	05/12/1978 / /	430 40	1 40	21 STEEL	-- - --	GOOD	35-42-15 86-54-53	S	00252 OTHR
0064NW 6 MAURY	11901050	JOHNSON THOM NEW LASER	6/10/1983 / /	145 45	0 18	21 STEEL	21 - 145	H2S	- - - -	Y	00103
0064NW 6 MAURY	11901051	JOHNSON BILL GREEN MILL RD	5/26/1983 / /	305 0	0 215	21 STEEL	21 - 305	OTHR	- - - -	Y	00103
0064NW 6 MAURY	11901142	ANDRE _____ JON JOE PEAY	12/06/1985 / /	700 688	3 150	20 OTHER	OPEN 20 - 700	OTHR	- - - -	Y	00227 HOME
0064NW 6 WILLIAMSON	18702617	WEBB _____ JOHN HOLT ROAD	04/21/1984 / /	207 180	25 --	-- OTHER	OPEN 150 - 207	GOOD	36-00-00 86-50-00	- Y	00015 HOME
0064NW 7 MARSHALL	11709015	RL YOUNG	/ /19 / /	-- --	-- 24	--	-- - --		35-38-17 86-59-23	S	OTHR
0064NW 7 MAURY	11900057	LOVETT F	04/20/1964 / /	995 808	-- 40	9 STEEL	-- - --	BAD	35-38-04 86-58-58	S	00057 HOME
0064NW 7 MAURY	11900066	PATTERSON W	04/16/1964 / /	125 90	2 50	20 STEEL	-- - --	BAD	35-38-12 86-59-35	S	00120 HOME
0064NW 7 MAURY	11900074	HILL W	07/06/1964 / /	225 90	1 60	16 STEEL	-- - --	GOOD	35-38-06 86-58-20	S	00057 HOME
0064NW 7 MAURY	11900140	PILKINTES D	01/29/1965 / /	145 53	-- 7	-- STEEL	-- - --	BAD	35-38-04 86-58-13	S	00057 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE CARTERS-CREEK QUADRANGLE (0064NW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064NW 7 MAURY	11900322	PARRETT H	03/10/1967 / /	135 115	25 29	22 STEEL	-- - --	GOOD	35-37-56 86-59-19	S	00120 HOME
0064NW 7 MAURY	11900605	BUTLER G	12/28/1971 / /	900 900	3 160	20 STEEL	-- - --	GOOD	35-37-47 86-58-38	S	00058 HOME
0064NW 7 MAURY	11900820	DELK J.	07/03/1975 / /	200 90	2 --	23 STEEL	-- - --	GOOD	35-38-48 86-59-18	S	00120 HOME
0064NW 7 MAURY	94001690 D0000438	THORNESBURY____JOHN CRANFORD HOLLOW	05/10/1994 / /	1090 1080	8 --	41 STEEL	OPEN 42 - 1090	GOOD	- - - -	- Y	00015 HOME
0064NW 8 MAURY	11900075	DERRYBERRY F	06/17/1964 / /	100 --	0 --	8 STEEL	-- - --		35-37-49 86-56-43	S	00057 HOME
0064NW 8 MAURY	11900079	BRADLEY E	06/29/1964 / /	76 65	20 40	19 STEEL	-- - --	BAD	35-38-10 86-57-00	S	00058 HOME
0064NW 8 MAURY	11900139	KINCAID B	02/05/1965 / /	50 12	1 11	11 STEEL	-- - --	GOOD	35-38-40 86-56-20	S	HOME
0064NW 8 MAURY	11900335	SURYBERRY W	09/12/1967 / /	980 950	1 --	21 STEEL	-- - --	GOOD	35-38-33 86-57-23	S	00120 HOME
0064NW 8 MAURY	11900412	AMERICAN OIL CO	07/09/1968 / /	740 735	20 100	21 STEEL	-- - --		35-38-39 86-55-45	S	00120 COMM
0064NW 8 MAURY	11900515	BRADLEY	06/18/1970 / /	30 24	6 15	30 STEEL	-- - --	GOOD	35-38-09 86-56-59	S	00252 FARM
0064NW 8 MAURY	11900516	BRADLEY	06/04/1970 / /	180 170	1 100	0	-- - --	BAD	35-38-09 86-56-59	S	00252 FARM
0064NW 8 MAURY	11900685	DERRYBERRY J	06/12/1973 / /	300 100	1 --	23 STEEL	-- - --	GOOD	- - - -		00120 HOME
0064NW 9 MAURY	11900049	FOX R	02/10/1964 / /	812 795	2 85	22 STEEL	-- - --	BAD	35-39-18 86-53-27	S	00057 HOME
0064NW 9 MAURY	11900106	CONNELLY J	09/26/1964 / /	800 748	2 77	16 STEEL	-- - --	BAD	35-38-02 86-54-23	S	00057 HOME
0064NW 9 MAURY	11900110	CROFTON M	10/14/1964 / /	300 35	-- 25	--	-- - --		35-37-38 86-54-49	S	00057 HOME
0064NW 9 MAURY	11900219	VAUGHN & HALL	01/09/1966 / /	370 340	1 90	6 STEEL	-- - --	GOOD	35-39-27 86-53-52	S	00252 HOME

12/01/94

PAGE 12

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE CARTERS-OF-LEK QUADRANGLE (0064NW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064NW 9 MAURY	11900220	VAUGHN & HALL	01/08/1966 / /	850 800	-- 250	16 STEEL	-- - --		35-39-29 86-53-50	S	00252 HOME
0064NW 9 MAURY	11900323	HUCHEBY J	03/11/1967 / /	95 65	10 35	21 STEEL	-- - --	GOOD	35-38-39 86-53-26	S	00120 HOME
0064NW 9 MAURY	11900427	BROWN L	06/28/1968 / /	200 35	-- --	23 STEEL	-- - --	GOOD	35-38-41 86-52-17	S	00120 HOME
0064NW 9 MAURY	11900456	ANDERSON C	09/26/1969 / /	125 85	30 30	22 STEEL	-- - --		35-38-36 86-53-14	S	00015 COMM
0064NW 9 MAURY	11900465	CADWELD W	02/19/1970 / /	695 690	4 40	22 STEEL	-- - --		35-37-39 86-54-27	S	00015 HOME
0064NW 9 MAURY	11900523	GULF OIL CO	11/03/1970 / /	789 750	6 --	22 STEEL	-- - --	GOOD	35-38-35 86-53-40	S	00120 COMM
0064NW 9 MAURY	11900565	MOORE H	07/07/1971 / /	800 785	6 127	22 STEEL	-- - --	GOOD	35-38-39 86-53-33	S	00120 COMM
0064NW 9 MAURY	11900587	BRADLEY H	11/12/1971 / /	35 25	8 --	23 STEEL	-- - --	GOOD	35-38-38 86-54-36	S	00120 FARM
0064NW 9 MAURY	11900647	ALLEN H	07/17/1972 / /	935 920	3 179	22 STEEL	-- - --	GOOD	35-39-12 86-54-46	S	00120 HOME
0064NW 9 MAURY	11900657	ANDERSON R	05/12/1972 / /	80 30	5 --	22 STEEL	-- - --	GOOD	35-38-41 86-52-42	S	00120 HOME
0064NW 9 MAURY	11900658	ANDERSON R	05/10/1972 / /	155 --	0 --	26 STEEL	-- - --		35-38-41 86-52-42	S	00120 HOME
0064NW 9 MAURY	11900695	ANDERSON R	07/03/1973 / /	725 700	12 30	21 STEEL	-- - --	BAD	35-38-42 86-52-44	S	00120 HOME
0064NW 9 MAURY	11901269	HOOD _____ SUE SHARP	04/11/1989 / /	90 80	15 --	20 STEEL	OPEN 20 - 90	FAIR	- - - -	Y	00015 HOME
0064NW 9 MAURY	92001985	HARDIN _____ BUDD SHARP RD	06/08/1992 / /	175 140	6 40	20 OTHER	OPEN 20 - 175	GOOD	- - - -	Y	00120 HOME
0064NW 9 MARSHALL	92002873	WHITE _____ TONY OLD HWY 99	05/16/1992 / /	804 790	10 --	-- OTHER	OPEN 350 - 804	GOOD	- - - -	Y	00015 FARM

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE QUADRANGLE (0064SW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER
0064SW MAURY	11900263	CALLIAR L	03/27/1966 / /	63 30	30 21	13 STEEL	-- -- --	GOOD	35-31-47 86-57-25	S	00120 HOME
0064SW MAURY	11900315	WILLIS D.	02/10/1967 / /	895 890	6 110	35 STEEL	-- -- --	BAD	- - - -		00120 HOME
0064SW MAURY	11900674	JAMESLSTOFEL	04/24/1973 / /	888 872	1 47	21 STEEL	-- -- --	GOOD	- - - -		00492
0064SW MAURY	11900792	BROWN A.	07/20/1974 / /	900 850	2 62	22 STEEL	-- -- --	GOOD	- - - -		00120 HOME
0064SW MAURY	11900802	PENROD E.	02/18/1974 / /	825 810	12 60	38 STEEL	-- -- --	BAD	- - - -		00120 HOME
0064SW MAURY	11900805	DERRYBERRY P.	03/26/1974 / /	775 745	2 82	22 STEEL	-- -- --	GOOD	- - - -		00120 HOME
0064SW MAURY	11900806	BROWN D.	04/10/1974 / /	720 716	30 80	55 STEEL	-- -- --	BAD	- - - -		00120 FARM
0064SW MAURY	11909205	H.L.HARRIS	08/28/1970 / /	922 900	5 129	--	-- -- --	GOOD	- - - -		00120
0064SW MAURY	11909222	EDW.M."NED"DENTON	04/16/1963 / /	770 765	12 66	--	-- -- --	GOOD	- - - -		00058
0064SW MAURY	11909225	LAUON HOOI	02/09/1962 / /	802 802	10 76	22	-- -- --	GOOD	- - - -		00120
0064SW MAURY	11909227	HUMBLE ESSO NO-2	08/13/1970 / /	908 880	10 128	--	-- -- --		- - - -		00120
0064SW MAURY	11909228	ALFRED INGRAM	10/21/1968 / /	934 930	8 62	--	-- -- --	BAD	- - - -		00058
0064SW MAURY	11909236	HAROLD LANDERS	11/03/1967 / /	734 730	4 19	--	-- -- --	GOOD	- - - -		00058
0064SW MAURY	11909238	GENE LEGG	06/28/1963 / /	868 --	-- --	--	-- -- --		- - - -		
0064SW MAURY	11909247	MRS LEX K.MARTIN	09/04/1962 / /	677 670	10 32	--	-- -- --	GOOD	- - - -		
0064SW MAURY	11909261	JERRY PRIMM	07/21/1971 / /	1042 980	1 22	20	-- -- --	GOOD	- - - -		00120

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE QUADRANGLE (0064SW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER
0064SW MAURY	11909271	ED SEAGRAVES	04/25/1969 / /	726 714	8 --	--	-- - --		- - - -		00120
0064SW MAURY	11909272	JOHN TINSLEY, JR.	10/01/1964 / /	854 850	2 129	--	-- - --	GOOD	- - - -		00120
0064SW MAURY	11909273	PAUL SCRIBNER	10/26/1972 / /	924 --	2 72	--	-- - --		- - - -		00120
0064SW MAURY	11909275	BEN SHELTON	12/07/1966 / /	847 825	2 22	--	-- - --		- - - -		00120
0064SW MAURY	11909280	D.E. STACEY	10/02/1963 / /	1033 --	-- 259	--	-- - --		- - - -		00120
0064SW MAURY	11909285	CECIL UPSHAWSON	09/18/1963 / /	820 800	3 65	--	-- - --	GOOD	- - - -		00058
0064SW 1 MARSHALL	11701157	KITTS_SERVICE_C MOONS BEND	09/15/1988 / /	290 280	7 --	124 OTHER	OPEN 124 - 290	GOOD	- - - -	Y	00015 HOME
0064SW 1 MAURY	11900078	CHILDRES R	07/07/1964 / /	98 60	2 40	8	-- - --	GOOD	35-36-07 86-58-45	S	00058 HOME
0064SW 1 MAURY	11900112	WEST J	11/05/1964 / /	280 70	1 --	18 STEEL	-- - --	GOOD	35-36-37 86-59-40	S	00058 HOME
0064SW 1 MAURY	11900114	SHAPESON J	10/05/1964 / /	345 210	-- --	28 STEEL	-- - --		35-37-20 86-57-42	S	00058 HOME
0064SW 1 MAURY	11900264	JONES H	06/16/1966 / /	266 235	5 25	32 STEEL	-- - --	GOOD	35-36-20 86-58-18	S	00120 OTHR
0064SW 1 MAURY	11900454	HUCKABY L	04/10/1970 / /	80 48	3 4	21 STEEL	-- - --	GOOD	35-36-45 86-59-51	S	00058 TEST
0064SW 1 MAURY	11900472	FAUTT M	07/24/1969 / /	300 215	1 140	21 STEEL	-- - --	GOOD	35-36-33 86-58-04	S	00015 HOME
0064SW 1 MAURY	11909045	J C LOFTIN	/ /19 / /	-- --	-- --	--	-- - --		35-35-23 86-59-44	S	FARM
0064SW 1 MAURY	11909046	CHARLES W STOFEL	/ /19 / /	-- --	-- --	--	-- - --		35-35-21 86-59-33	S	OTHR
0064SW 1 MAURY	11909054	DAISY DEAN	/ /19 / /	-- --	-- 8	--	-- - --		35-35-20 86-59-33	S	OTHR

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE (0064SW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064SW 1 MAURY	11909057	ALTON LYNN	/ /19 / /	-- 98	--	--	-- - --		35-35-23 86-58-48	S	HOME
0064SW 1 MAURY	11909058	H M TANKERSLEY	/ /19 / /	-- --	--	--	-- - --		35-35-18 86-58-22	S	OTHR
0064SW 1 MAURY	11909059	JIMMIE MCCORMACK	/ /19 / /	-- --	--	--	-- - --		35-36-32 86-58-35	S	HOME
0064SW 1 MAURY	11909060		/ /19 / /	-- 219	--	--	-- - --		35-36-17 86-59-05	S	FARM
0064SW 1 MAURY	11909061	ROY ALEXANDER JR	/ /19 / /	-- 37	--	--	-- - --		35-36-19 86-59-22	S	HOME
0064SW 1 MAURY	11909070	EARL P CHEEK	/ /19 / /	-- --	--	--	-- - --		35-35-28 86-59-23	S	OTHR
0064SW 1 MAURY	11909072	WILLIAM H CONNER	/ /19 / /	-- --	--	--	-- - --		35-35-42 86-57-28	S	HOME
0064SW 2 MAURY	11900024	CONNELLY J	12/16/1963 / /	260 244	30 112	140 STEEL	-- - --	GOOD	35-35-49 86-56-53	S	00057 HOME
0064SW 2 MAURY	11900064	COTHRAS C	04/27/1964 / /	170 135	3 65	19 STEEL	-- - --	GOOD	35-35-51 86-57-16	S	00120 HOME
0064SW 2 MAURY	11900102	PRIMM N	10/10/1964 / /	185 120	22 80	10 STEEL	-- - --	GOOD	35-35-48 86-56-48	S	00100 HOME
0064SW 2 MAURY	11900121	FINSLEY J	10/04/1964 / /	850 850	2 211	12 STEEL	-- - --	GOOD	35-35-34 86-57-20	S	00120 HOME
0064SW 2 MAURY	11900208	KINGER J	10/30/1965 / /	163 155	30 --	54 STEEL	-- - --	GOOD	35-37-24 86-55-21	S	OTHR
0064SW 2 MAURY	11900265	THORN K	06/18/1966 / /	110 70	1 22	15 STEEL	-- - --	GOOD	35-37-25 86-56-45	S	00120 HOME
0064SW 2 MAURY	11900442	MILLER W	03/31/1969 / /	1050 900	2 158	22 STEEL	-- - --		35-35-17 86-57-42	S	00120 HOME
0064SW 2 MAURY	11900547	HUCKABY H D	05/18/1971 / /	105 50	2 22	21 STEEL	-- - --	GOOD	35-35-42 86-55-37	S	00453 HOME
0064SW 2 MAURY	11900563	PRIMM J	07/21/1971 / /	1040 995	1 55	25	-- - --	GOOD	35-35-06 86-56-02	S	00120 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE
QUADRANGLE (0064SW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064SW 2 MAURY	11900568	DUGGER B	06/01/1971 / /	320 75	-- 13	21 STEEL	-- - --	GOOD	35-36-42 86-56-30	S	00120 FARM
0064SW 2 MAURY	11909062	HERBERT LUNN	/ /19 / /	-- --	-- 108	--	-- - --		35-35-51 86-57-14	S	HOME
0064SW 2 MAURY	11909063	J A LOFTIN	/ /19 / /	-- --	--	--	-- - --		35-36-05 86-57-10	S	HOME
0064SW 2 MAURY	11909064	IRVIN L CORDER	/ /19 / /	-- --	--	--	-- - --		35-36-08 86-56-54	S	HOME
0064SW 2 MAURY	11909065	LAVON HOOIE	/ /19 / /	-- --	--	--	-- - --		35-36-24 86-57-22	S	FARM
0064SW 2 MAURY	11909069	ALFRED J THOMAS	/ /19 / /	-- --	-- 126	--	-- - --		35-36-20 86-57-08	S	HOME
0064SW 2 MAURY	11909105	JACK W JONES	/ /19 / /	-- --	-- 3	--	-- - --		35-35-12 86-56-20	S	OTHR
0064SW 2 MAURY	11909106	JASPER LEE	/ /19 / /	-- --	-- 81	--	-- - --		35-35-11 86-56-22	S	HOME
0064SW 2 MAURY	11909107	MONROE PRIMM	/ /19 / /	-- --	-- 37	--	-- - --		35-35-12 86-56-10	S	OTHR
0064SW 2 MAURY	11909108	FRANK HARRIS	/ /19 / /	-- --	--	--	-- - --		35-35-49 86-56-28	S	HOME
0064SW 2 MAURY	11909109	DOROTHY LUNN	/ /19 / /	-- --	--	--	-- - --		35-36-05 86-56-46	S	HOME
0064SW 2 MAURY	91002960	ANDERSON _____ UNION BEND	GARY 07/24/1991 / /	150 138	0 25	21 OTHER	OPEN 21 - 150	H2S	- - - -	- Y	00330 HOME
0064SW 2 MAURY	92001986	THOMPSON _____ CRANFORD HOLLOW	BOB 06/02/1992 / /	300 --	0 0	20 OTHER	OPEN 20 - 300	OTHR	- - - -	- Y	00120 HOME
0064SW 2 MAURY	92002956	THOMPSON _____ CRANFORD	ROBE 06/07/1992 / /	1075 1025	8 225	22 OTHER	OPEN 22 - 1075	H2S	- - - -	- Y	00330 HOME
0064SW 3 MAURY	11900011	RUMMAGE J	09/07/1963 / /	108 85	32 80	11 STEEL	-- - --	GOOD	35-37-25 86-54-00	S	00057 HOME
0064SW 3 MAURY	11900087	HARDISON	07/01/19 / /	168 160	20 74	12 STEEL	-- - --	GOOD	35-35-00 86-53-23	S	00100 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE CLIMATE QUADRANGLE 111-4SW IN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER USE
0064SW 3 MAURY	11900186	SHANNON E	07/27/1965 / /	105 100	4 58	13 STEEL	-- - --		35-36-58 86-54-34	S	00120 HOME
0064SW 3 MAURY	11901139	WATTERS _____ SHAYS	GARY 01/14/1986 / /	200 --	0 --	20 OTHER	OPEN 20 - 200	OTHR	- - - -	Y	00330 HOME
0064SW 3 MAURY	11901140	WATTERS _____ SHAYS	GARY 01/14/1986 / /	160 --	0 --	20 OTHER	OPEN 20 - 160	OTHR	- - - -	Y	00330 HOME
0064SW 3 MAURY	11901146	CLIFTON _____ CARPENTER BRDG	IRMA 03/31/1986 / /	300 220	1 50	20 OTHER	OPEN 20 - 300	FAIR	- - - -	Y	00330 HOME
0064SW 3 MAURY	11909115	THOMAS H PEEBLES	/ /19 / /	-- --	-- 5	--	-- - --		35-35-29 86-53-30	S	OTHR
0064SW 3 MAURY	11909116	J C WILLIAMS	/ /19 / /	-- --	-- --	--	-- - --		35-35-25 86-54-26	S	HOME
0064SW 3 MAURY	11909117	ARTHUR WENTZEL	/ /19 / /	-- --	-- --	--	-- - --		35-35-27 86-54-27	S	HOME
0064SW 3 MAURY	11909118	R B WILLIAMS	/ /19 / /	-- --	-- --	--	-- - --		35-35-27 86-54-35	S	HOME
0064SW 3 MAURY	11909119	CARL PILKINTON	/ /19 / /	-- --	-- 23	--	-- - --		35-35-32 86-54-46	S	OTHR
0064SW 3 MAURY	11909120	CARL PILKINTON	/ /19 / /	-- --	-- 24	--	-- - --		35-35-46 86-54-27	S	OTHR
0064SW 3 MAURY	11909133	MARSHALL HARDISON	/ /19 / /	-- --	-- 18	--	-- - --		35-36-52 86-53-13	S	HOME
0064SW 3 MAURY	11909141	CLYDE YORK	/ /19 / /	-- --	-- 92	--	-- - --		35-36-03 86-53-18	S	OTHR
0064SW 3 MAURY	91000031	GULHAN _____ SOWELL MILL PK	J_W_ 09/26/1990 / /	650 640	15 --	20 OTHER	OPEN -- - --	GOOD	- - - -	Y	00120 HOME
0064SW 4 MAURY	11900008	GIBSON E	09/19/1963 / /	100 70	15 25	10 STEEL	-- - --	GOOD	35-33-54 86-58-37	S	00120 HOME
0064SW 4 MAURY	11900045	SCOTT M	01/27/1964 / /	800 795	2 22	65 STEEL	-- - --	GOOD	35-33-06 86-59-29	S	00120 HOME
0064SW 4 MAURY	11900052	SWAFFORD J	03/09/1964 / /	105 50	30 22	22 STEEL	-- - --	GOOD	35-32-37 86-57-42	S	00120 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE (0064SW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064SW 4 MAURY	11900070	LYNN C	03/19/1964 / /	73 35	25 18	6 STEEL	-- - --	GOOD	35-34-13 86-59-52	S	00120 FARM
0064SW 4 MAURY	11900161	MOORE C	06/02/1965 / /	798 790	1 60	27 STEEL	-- - --	GOOD	35-33-10 86-59-30	S	00058 HOME
0064SW 4 MAURY	11900185	PURYEAR H	/ /19 / /	150 50	1 10	14 STEEL	-- - --	GOOD	35-32-40 86-57-14	S	00120 HOME
0064SW 4 MAURY	11900197	MOORE H	09/06/1965 / /	164 160	20 40	13 STEEL	-- - --	BAD	35-32-34 86-59-03	S	00058 HOME
0064SW 4 MAURY	11900217	KILPATRICK MARGRET	01/10/1966 / /	755 750	5 40	16 STEEL	-- - --	BAD	35-33-30 86-59-00	S	00058 HOME
0064SW 4 MAURY	11900262	MCKEE G	03/31/1966 / /	70 35	30 30	23 STEEL	-- - --	GOOD	35-42-31 86-57-39	S	00120 HOME
0064SW 4 MAURY	11900861	CRAIG J.	08/26/1976 / /	425 350	1 50	84 STEEL	-- - --	BAD	- - - -		00120 HOME
0064SW 4 MAURY	11901251	BUNKER _____ FLOY DIXON	07/16/1988 / /	375 --	0 --	35 OTHER	OPEN 35 - 375	OTHR	- - - -	Y	00640 HOME
0064SW 4 MAURY	11909001	CECIL UPSHAW	/ /19 / /	-- --	-- --	--	-- - --		35-33-16 86-58-58	S	HOME
0064SW 4 MAURY	11909002	WILLIAM L THOMAS	/ /19 / /	-- --	-- --	--	-- - --		35-33-04 86-58-00	S	HOME
0064SW 4 MAURY	11909011	LEE D ESTES	/ /19 / /	-- --	-- --	--	-- - --		35-32-33 86-59-22	S	HOME
0064SW 4 MAURY	11909014	THOMAS R TATE	/ /19 / /	-- 35	-- --	--	-- - --		35-32-31 86-59-13	S	HOME
0064SW 4 MAURY	11909017	HARDIN VOSS	/ /19 / /	-- --	-- --	--	-- - --		35-32-02 86-59-50	S	HOME
0064SW 4 MAURY	11909020	C W DILLEHAY	/ /19 / /	-- --	-- 5	--	-- - --		35-32-16 86-59-14	S	OTHR
0064SW 4 MAURY	11909021	CHARLES E HARGROVE	/ /19 / /	-- --	-- --	--	-- - --		35-33-14 86-59-43	S	HOME
0064SW 4 MAURY	11909029	C H WEAVER	/ /19 / /	-- --	-- 38	--	-- - --		35-33-51 86-59-42	S	OTHR

12/01/94

PAGE 41

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE 10064SW, 1N.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOI DEPTH AQ	DEPTH STAT	YIELD LEVEL	CSE CSE TYPE	DEPTH INTERVAL	WELL FINISH	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064SW 4 MAURY	11909030	R H BROADWAY	/ /19 / /	-- --	-- --	-- --	-- --	-- --	-- --	-- --	35-34-02 86-59-40	S OTHR	
0064SW 4 MAURY	11909034	CARL THOMAS CRAIN	/ /19 / /	-- --	-- 43	-- --	-- --	-- --	-- --	-- --	35-34-14 87-00-00	S HOME	
0064SW 4 MAURY	11909035	DAVID LOVETT	/ /19 / /	-- --	-- 21	-- --	-- --	-- --	-- --	-- --	35-34-17 86-59-55	S HOME	
0064SW 4 MAURY	11909038	HAROLD G LANDERS	/ /19 / /	-- --	-- --	-- --	-- --	-- --	-- --	-- --	35-33-40 86-58-36	S HOME	
0064SW 4 MAURY	11909039	HELEN MOORE LANDERS	/ /19 / /	-- --	-- --	-- --	-- --	-- --	-- --	-- --	35-33-29 86-58-28	S HOME	
0064SW 4 MAURY	11909040	PEARL J HARRIS	/ /19 / /	-- --	-- --	-- --	-- --	-- --	-- --	-- --	35-33-32 86-59-20	S OTHR	
0064SW 4 MAURY	11909041	PEARL J HARRIS	/ /19 / /	-- --	-- 3	-- --	-- --	-- --	-- --	-- --	35-33-28 86-59-24	S OTHR	
0064SW 4 MAURY	11909042		/ /19 / /	-- --	-- --	-- --	-- --	-- --	-- --	-- --	35-33-23 86-58-40	S HOME	
0064SW 4 MAURY	11909043	MARTIN D PARRISH	/ /19 / /	-- --	-- 25	-- --	-- --	-- --	-- --	-- --	35-34-21 86-59-30	S OTHR	
0064SW 4 MAURY	11909052	ROBERT A PARRISH	/ /19 / /	-- --	-- 60	-- --	-- --	-- --	-- --	-- --	35-34-32 86-59-35	S HOME	
0064SW 4 MAURY	11909053	R L VAUGHANS HEIRS	/ /19 / /	-- --	-- 14	-- --	-- --	-- --	-- --	-- --	35-34-56 86-59-16	S OTHR	
0064SW 4 MAURY	11909067	NETTIE RIEVES NIX	/ /19 / /	-- --	-- 8	-- --	-- --	-- --	-- --	-- --	35-34-33 86-57-47	S OTHR	
0064SW 4 MAURY	11909073	H B SLOAN	/ /19 / /	-- --	-- 42	-- --	-- --	-- --	-- --	-- --	35-33-41 86-58-19	S HOME	
0064SW 4 MAURY	11909074	EUGENE WILSON	/ /19 / /	-- --	-- 24	-- --	-- --	-- --	-- --	-- --	35-34-23 86-59-36	S HOME	
0064SW 4 MAURY	11909075	ROBERT MCKINZIE	/ /19 / /	-- --	-- 24	-- --	-- --	-- --	-- --	-- --	35-34-18 86-59-16	S HOME	
0064SW 4 MAURY	11909078	DAVID M CRAIG	/ /19 / /	-- --	-- --	-- --	-- --	-- --	-- --	-- --	35-32-52 86-57-32	S HOME	

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE (0064SW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOI DEPTH AQ DEPTH	TOI YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER
0064SW 4 MAURY	11909088	DAVID M CHEEK	/ /19	--	--	--	-- - --		35-32-39 86-57-51	S	HOME
0064SW 4 MAURY	91003926	DUCK RIVER AGENCY MOORE	08/30/1991 / /	1009 910	5 --	32 STEEL	OPEN 32 - 1009	GOOD	- - - -		00015 HOME
0064SW 4 MAURY	92003258	HASKINS _____ RICK VOSS RD	07/08/1992 / /	145 143	8 23	20 OTHER	OPEN 20 - 145	GOOD	- - - -		00120 HOME
0064SW 4 MAURY	93001307	KEELE _____ LARR HWY 50	03/17/1993 / /	700 695	10 60	20 OTHER	OPEN 20 - 700	GOOD	- - - -		00120 HOME
0064SW 5 MAURY	11900246	WORLEY C	09/29/1966 / /	802 800	3 86	21 STEEL	-- - --	BAD	35-32-42 86-56-08	S	00058 HOME
0064SW 5 MAURY	11900257	BRYANT E	01/25/1967 / /	158 65	-- 29	27 STEEL	-- - --	GOOD	35-32-32 86-57-10	S	00058 HOME
0064SW 5 MAURY	11900367	PERKS M	07/11/1967 / /	800 795	1 --	21 STEEL	-- - --	GOOD	35-32-46 86-55-41	S	00120 HOME
0064SW 5 MAURY	11900368	BASHEARS S	07/13/1967 / /	250 95	-- 63	23 STEEL	-- - --	GOOD	35-32-40 86-55-41	S	00120 HOME
0064SW 5 MAURY	11900413	JOHNSON C	07/09/1965 / /	885 860	3 38	36 STEEL	-- - --		35-34-58 86-56-28	S	00120 HOME
0064SW 5 MAURY	11900867	INGRAM T.	09/25/1976 / /	300 70	1 60	42 STEEL	-- - --	BAD	35-33-14 86-57-08	S	00120 HOME
0064SW 5 MAURY	11900985	CUSHING J	03/18/1980 / /	125 80	100 --	95 STEEL	-- - --	GOOD	35-33-26 86-55-12	S	00120 HOME
0064SW 5 MAURY	11900986	HARGROVE B	03/24/1980 / /	125 90	4 --	21 STEEL	-- - --	GOOD	35-33-32 86-55-14	S	00120 HOME
0064SW 5 MAURY	11901088	CORLEY _____ JIM BRYANT RD	08/22/1984 / /	920 800	3 --	20 OTHER	OPEN 20 - 920	FAIR	- - - -		00120 HOME
0064SW 5 MAURY	11901148	COOPER _____ WILL NEGRO CREEK	04/24/1986 / /	200 --	-- --	20 OTHER	OPEN 20 - 200	OTHR	- - - -		00640 HOME
0064SW 5 MAURY	11901168	BAKER _____ KEIT NEW CUT RD	12/18/1986 / /	1155 1120	7 350	20 OTHER	OPEN 20 - 1155	IRON	- - - -		00120 HOME
0064SW 5 MAURY	11901201	COOPER _____ BILL NEGRO CREEK	05/13/1987 / /	125 23	11 50	20 OTHER	OPEN 24 - 125	FAIR	- - - -		00120 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE (0004SW) TN

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064SW 5 MAURY	11901303	HARGROVE BILL HOWARD BRIDGE R	09/28/1989 / /	250 0	1 80	20 STEEL	OPEN 20 - 250	GOOD	- - - -		00330 HOME
0064SW 5 MAURY	11909066	C E HARLAN	/ /19 / /	-- --	-- --	--	-- - --		35-34-36 86-57-20	S	HOME
0064SW 5 MAURY	11909068	EMMITT YOUNG	/ /19 / /	-- --	-- 65	--	-- - --		35-33-06 86-56-19	S	OTHR
0064SW 5 MAURY	11909071	ANDREW D BENEFIELD	/ /19 / /	-- --	-- 48	--	-- - --		35-33-18 86-56-48	S	HOME
0064SW 5 MAURY	11909076	J W MATTHEWS	/ /19 / /	-- --	-- 106	--	-- - --		35-32-49 86-57-20	S	HOME
0064SW 5 MAURY	11909077	CARTHAL VAUGHN	/ /19 / /	-- --	-- 20	--	-- - --		35-32-43 86-56-16	S	HOME
0064SW 5 MAURY	11909079	HAZEL E CAREY	/ /19 / /	-- --	-- 45	--	-- - --		35-32-32 86-57-04	S	OTHR
0064SW 5 MAURY	11909084	NG DAVIDSON	/ /19 / /	-- --	-- 12	--	-- - --		35-32-46 86-56-39	S	OTHR
0064SW 5 MAURY	11909086	MRS HUEY T HOLLOWAY	/ /19 / /	-- --	-- 8	--	-- - --		35-32-36 86-56-36	S	HOME
0064SW 5 MAURY	11909087	CYNTHIA L DAVIDSON	/ /19 / /	-- --	-- 52	--	-- - --		35-33-03 86-56-22	S	HOME
0064SW 5 MAURY	11909089	AUBREY SMITHSON	/ /19 / /	-- --	-- 79	--	-- - --		35-33-23 86-55-02	S	HOME
0064SW 5 MAURY	11909091	MICHAEL PERKO	/ /19 / /	-- --	-- 40	--	-- - --		35-33-13 86-55-41	S	OTHR
0064SW 5 MAURY	11909096	T E DERRYBERRY	/ /19 / /	-- --	-- --	--	-- - --		35-34-05 86-55-18	S	HOME
0064SW 5 MAURY	11909097	CAMERON H MCKAY	/ /19 / /	-- --	-- 11	--	-- - --		35-33-41 86-55-36	S	OTHR
0064SW 5 MAURY	11909099	N MONROE PRIMM	/ /19 / /	-- --	-- 46	--	-- - --		35-34-33 86-55-03	S	OTHR
0064SW 5 MAURY	11909102	EARL P CHEEK	/ /19 / /	-- --	-- --	--	-- - --		35-34-52 86-55-28	S	HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE (0064SW) TN.

QUAD / COUNTY	NTH REG NUM	WELL NUM OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL 125 NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064SW 5 MAURY	11909103	CECIL JOHNSON	/ /19 / /	-- 19	--	--	-- - --		35-34-53 86-56-30	S	OTHR
0064SW 5 MAURY	11909104	J C CHEEK	/ /19 / /	-- 67	--	--	-- - --		35-34-57 86-55-55	S	OTHR
0064SW 5 MAURY	91000936	DAVIS _____ KING PRESSNELL	03/06/1991 / /	850 775	8 60	34 OTHER	OPEN 34 - 950	H2S	- - - -	Y	00330 HOME
0064SW 5 MAURY	92002831	ANDREWS _____ BILL SOWELL RD	06/15/1992 / /	804 780	6 --	63 STEEL	OPEN 63 - 804	GOOD	- - - -	Y	00015 HOME
0064SW 6 MAURY	11900023	HARTY D	12/05/1963 / /	120 66	4 48	38 STEEL	-- - --	GOOD	35-33-31 86-54-48	S	00057 HOME
0064SW 6 MAURY	11900324	PRIMM J	07/14/1967 / /	150 125	6 43	21 STEEL	-- - --	GOOD	35-34-46 86-54-41	S	00120 HOME
0064SW 6 MAURY	11900534	ENGLAND G	04/18/1970 / /	185 50	1 --	37	-- - --		35-34-04 86-52-46	S	00120 HOME
0064SW 6 MAURY	11901196	LEATHERWOOD _____ EDDI TVA	08/21/1987 04/22/1988	145 23	6 --	20 OTHER	OPEN 20 - 145	GOOD	35-34-30 86-54-30	M Y	00120 HOME
0064SW 6 MAURY	11909090	CARLES G YOUNG	/ /19 / /	-- 89	--	--	-- - --		35-33-19 86-54-43	S	HOME
0064SW 6 MAURY	11909092	CP CHEEK	/ /19 / /	-- 65	--	--	-- - --		35-33-44 86-53-50	S	HOME
0064SW 6 MAURY	11909093	C P CHEEK	/ /19 / /	-- 20	--	--	-- - --		35-33-35 86-54-16	S	OTHR
0064SW 6 MAURY	11909094	CLYDE MALPHUS	/ /19 / /	-- 50	--	--	-- - --		35-33-05 86-54-35	S	OTHR
0064SW 6 MAURY	11909095	H N CHEEK	/ /19 / /	-- 53	--	--	-- - --		35-34-06 86-54-57	S	OTHR
0064SW 6 MAURY	11909098	J T PRIMM	/ /19 / /	-- 13	--	--	-- - --		35-34-35 86-54-48	S	OTHR
0064SW 6 MAURY	11909100	ERNEST WRIGHT	/ /19 / /	-- 30	--	--	-- - --		35-34-29 86-54-55	S	OTHR
0064SW 6 MAURY	11909101	M REGEN CHUMBLEY	/ /19 / /	-- --	--	--	-- - --		35-34-55 86-54-53	S	HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDARE QUADRANGLE (0064SW, TN.)

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER
0064SW 6 MAURY	11909110	DAISY DEAN	/ /19 / /	-- 64	--	--	-- - --	--	35-32-35 86-54-11	S	HOME
0064SW 6 MAURY	11909111	LUKE MOSER	/ /19 / /	-- --	--	--	-- - --	--	35-32-49 86-52-59	S	HOME
0064SW 6 MAURY	11909112	LUKE MOSER	/ /19 / /	-- 35	--	--	-- - --	--	35-32-47 86-53-02	S	OTHR
0064SW 6 MAURY	11909114	A E SANDERS	/ /19 / /	-- 25	--	--	-- - --	--	35-33-06 86-52-35	S	OTHR
0064SW 6 MAURY	11909129	DIXIE FERGURSON	/ /19 / /	-- 130	--	--	-- - --	--	35-34-07 86-53-06	S	HOME
0064SW 6 MAURY	11909130	W H THOMLINSON	/ /19 / /	-- 60	--	--	-- - --	--	35-34-10 86-52-57	S	HOME
0064SW 6 MAURY	11909131	PRESTON CARROLL	/ /19 / /	-- 25	--	--	-- - --	--	35-34-33 86-53-02	S	HOME
0064SW 6 MAURY	11909165	A D LIGGETT	/ /19 / /	-- 110	--	--	-- - --	--	35-33-45 86-53-18	S	HOME
0064SW 6 MAURY	90001642	GILLIAM_____RICH SOWELL MILL PIK	05/30/1990 / /	205 200	50 12	28 OTHER	OPEN 28 - 205	GOOD	- - - -	Y	00640 HOME
0064SW 6 MAURY	90002052	BOSTWICK_____DANI SOWELL MILL PK	05/07/1990 / /	250 148	8 5	66 OTHER	OPEN 66 - 250	GOOD	- - - -	Y	00640 HOME
0064SW 6 MAURY	91000053	BROWN_____STEV NEW CUT RD	11/26/1990 / /	275 125	2 93	20 OTHER	OPEN 20 - 275	GOOD	- - - -	Y	00120 HOME
0064SW 6 MAURY	92003851	PARKS DEVELOPMENT C HOUSTON CHEEK	05/04/1992 / /	225 --	0 54	20 OTHER	OPEN 20 - 225	GOOD	- - - -	Y	00120 HOME
0064SW 7 MAURY	11900153	WILSON B	01/28/1965 / /	779 775	3 90	15 STEEL	-- - --	--	35-30-58 86-59-32	S	00120 HOME
0064SW 7 MAURY	11901056	TROOP WILL DENTON	6/14/1983 / /	740 715	3 10	21 STEEL	21 - 740	GOOD	- - - -	Y	00103
0064SW 7 MAURY	11901058	ADAMS BOBB BRUSH CREEK	7/11/1983 / /	160 145	4 20	21 STEEL	21 - 160	GOOD	- - - -	Y	00613
0064SW 7 MAURY	11901176	ESTES_____SIDN	08/18/1986 / /	825 815	3 100	20 OTHER	OPEN 20 - 825	GOOD	- - - -	N	00018 HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE (0064SW, TN.)

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG	DRILLER USE
0064SW 7 MAURY	11901191	GREGORY _____ LONN TOBE ROBERSON	08/14/1987 / /	350 --	-- --	29 STEEL	OPEN 29 - 350	FAIR	- - - -		00015 HOME
0064SW 7 MAURY	11909003	LUTHER N LAMAR	/ /19 / /	-- --	-- 47	--	-- - --		35-32-13 86-58-00	S	HOME
0064SW 7 MAURY	11909004	HARRY W MITCHELL	/ /19 / /	-- --	-- --	--	-- - --		35-32-28 86-58-17	S	OTHR
0064SW 7 MAURY	11909005	HARRY W MITCHELL	/ /19 / /	-- --	-- --	--	-- - --		35-32-28 86-58-18	S	OTHR
0064SW 7 MAURY	11909006	ANNIE RUTH CLARK	/ /19 / /	-- --	-- --	--	-- - --		35-32-24 86-58-29	S	OTHR
0064SW 7 MAURY	11909008	HARRY W MITCHELL	/ /19 / /	-- --	-- 54	--	-- - --		35-32-20 86-58-17	S	OTHR
0064SW 7 MAURY	11909009	RAY MOORES HEIRS	/ /19 / /	-- --	-- 4	--	-- - --		35-32-13 86-58-51	S	OTHR
0064SW 7 MAURY	11909010	ANNIE RUTH CLARK	/ /19 / /	-- --	-- 3	--	-- - --		35-32-22 86-58-43	S	OTHR
0064SW 7 MAURY	11909012	MARY DENTON CATHEY	/ /19 / /	-- --	-- --	--	-- - --		35-32-24 86-59-16	S	HOME
0064SW 7 MAURY	11909013	MARY DENTON CATHEY	/ /19 / /	-- --	-- 13	--	-- - --		35-32-27 86-59-21	S	OTHR
0064SW 7 MAURY	11909015	MARY DENTON CATHEY	/ /19 / /	-- --	-- 34	--	-- - --		35-32-25 86-59-26	S	HOME
0064SW 7 MAURY	11909016	DAVID THOMASON	/ /19 / /	-- --	-- 24	--	-- - --		35-32-27 86-59-30	S	HOME
0064SW 7 MAURY	11909018	MARY CHALES MITCHEL	/ /19 / /	-- --	-- --	--	-- - --		35-32-02 86-59-05	S	OTHR
0064SW 7 MAURY	11909019	MARY DENTON CATHEY	/ /19 / /	-- --	-- --	--	-- - --		35-32-25 86-59-35	S	OTHR
0064SW 7 MAURY	11909022	HENRY PAYNE	/ /19 / /	-- --	-- 76	--	-- - --		35-31-51 86-58-06	S	HOME
0064SW 7 MAURY	11909023	LESLIE EDDLEMAN	/ /19 / /	-- --	-- --	--	-- - --		35-31-37 86-58-27	S	HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE (0064SW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSP DATE	TOT DEPTH DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER
0064SW 7 MAURY	11909024	H H HIGHT HEIRS	/ /19 / /	-- 39	-- 39	--	--	--	35-31-36 86-58-23	S OTHR	
0064SW 7 MAURY	11909025	THOMAS SHARP	/ /19 / /	-- --	-- --	--	--	--	35-31-40 86-58-01	S HOME	
0064SW 7 MAURY	11909026	ELLIS DUGGER	/ /19 / /	-- --	-- --	--	--	--	35-30-48 86-57-54	S HOME	
0064SW 7 MAURY	11909027	ELLIS DUGGER	/ /19 / /	-- 25	-- 25	--	--	--	-- --	-- HOME	
0064SW 7 MAURY	11909028	JOHN W FINNEYS HEIR	/ /19 / /	-- --	-- --	--	--	--	35-32-07 86-58-48	S HOME	
0064SW 7 MAURY	11909031	ROBERT S HARDISON	/ /19 / /	-- 34	-- 34	--	--	--	35-31-31 86-57-31	S OTHR	
0064SW 7 MAURY	11909032	ROBERT S HARDISON	/ /19 / /	-- --	-- --	--	--	--	35-31-31 86-57-29	S HOME	
0064SW 7 MAURY	90000194	KALMANEK _____ RICH GLENCOE	10/02/1989 / /	165 165	8 --	53 STEEL	OPEN 53 - 165	GOOD	- - - -	00015 Y HOME	
0064SW 7 MAURY	90000195	KALMANEK _____ RICH GLENCOE	10/03/1989 / /	150 85	75 --	20 STEEL	OPEN 20 - 150	UNK	- - - -	00015 Y HEAT	
0064SW 7 MAURY	92003704	LOOPER _____ MIKE GREASY BRANCH	08/18/1992 / /	250 150	4 80	63 OTHER	OPEN 63 - 250	GOOD	- - - -	00330 Y HOME	
0064SW 7 MAURY	93000097	LOOPER _____ MIKE GREASY BRANCH	12/08/1992 / /	300 120	2 25	20 OTHER	OPEN 20 - 300	GOOD	- - - -	00330 Y HOME	
0064SW 7 MAURY	93003946	LOVELL _____ RONA	09/14/1993 / /	130 --	0 --	-- OTHER	-- -- - --	OTHR	- - - -	00120 Y HOME	
0064SW 8 MAURY	11900088	CHEEK C	07/10/1964 / /	75 40	5 17	6 STEEL	-- -- - --	GOOD	35-31-42 86-55-24	S HOME	00100
0064SW 8 MAURY	11900141	DILLEHAY O	01/20/1965 / /	100 68	8 76	35 STEEL	-- -- - --	GOOD	35-31-00 86-55-24	S HOME	00057
0064SW 8 MAURY	11900195	WHITAKER H	09/12/1965 / /	89 75	10 39	8 STEEL	-- -- - --	BAD	35-32-20 86-55-17	S HOME	00058
0064SW 8 MAURY	11900218	STONE J	01/19/1966 / /	190 180	10 70	70 STEEL	-- -- - --	GOOD	35-31-40 86-56-35	S HOME	00058

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE (0064SW) TN

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER
0064SW 8 MAURY	11900226	VAUGHN P	05/01/1966 / /	70 45	6 30	16 STEEL	-- - --	GOOD	35-30-07 86-56-37	S	00252 HOME
0064SW 8 MAURY	11900336	BILLINGLEY V	08/18/1967 / /	110 85	50 46	23 STEEL	-- - --	GOOD	35-31-20 86-55-05	S	00120 HOME
0064SW 8 MAURY	11900349	CRUMLEY A	08/11/1967 / /	230 80	1 85	40 STEEL	-- - --		35-31-35 86-54-57	S	00120 HOME
0064SW 8 MAURY	11900452	MITCHELL A.	10/04/1973 / /	200 25	1 58	21 STEEL	-- - --	GOOD	35-32-05 86-55-20	S	00120 HOME
0064SW 8 MAURY	11900499	FINNENGAN DIXIE	09/19/1970 / /	275 252	2 84	20 STEEL	-- - --	GOOD	35-32-03 86-56-42	S	00453 HOME
0064SW 8 MAURY	11900575	LANDERS W	02/25/1971 / /	200 185	8 102	128 STEEL	-- - --	GOOD	35-32-17 86-57-22	S	00120 FARM
0064SW 8 MAURY	11900625	CRAIG F	02/07/1972 / /	160 140	-- 23	20 STEEL	-- - --	GOOD	35-31-07 86-56-23	S	00058 HOME
0064SW 8 MAURY	11900627	MCCULLIN J B	02/11/1972 / /	842 835	2 55	25 STEEL	-- - --	BAD	35-30-30 86-56-35	S	00058 HOME
0064SW 8 MAURY	11901045	LAMAR HWY 50	LUTH 2/22/1983 / /	40 22	10 0	20 STEEL	20 - 40	GOOD	- - - -	Y	00103
0064SW 8 MAURY	11901046	LAMAR HWY 50	LUTH 2/25/1983 / /	205 0	0 0	21 STEEL	21 - 205		- - - -	Y	00103
0064SW 8 MAURY	11901047	LAMAR HWY 50	LUTH 2/28/1983 / /	245 0	0	21 STEEL	21 - 245	OTHR	- - - -	Y	00103
0064SW 8 MAURY	11901159	HENSON _____ SMITH	LILL 09/15/1986 / /	160 138	15 40	42 OTHER	OPEN 42 - 160	GOOD	- - - -	Y	00269 HOME
0064SW 8 MAURY	11901207	PILKTON _____ SMITH ACRES	DAVI 07/30/1987 / /	100 85	20 18	20 OTHER	OPEN 20 - 100	GOOD	- - - -	Y	00330 HOME
0064SW 8 MAURY	11901242	FALCONBURY _____ CULLOOKA	JEFF 09/10/1988 / /	300 125	0 30	20 OTHER	OPEN 20 - 300	GOOD	- - - -	Y	00330 HOME
0064SW 8 MAURY	11909080	MRS ED WALKER	/ /19 / /	-- --	-- 23	--	-- - --		35-32-18 86-57-12	S	HOME
0064SW 8 MAURY	11909081	ALTON WALKER	/ /19 / /	-- --	-- 78	--	-- - --		35-32-24 86-57-17	S	HOME

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE (0064SW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE LONGITUDE	A/C LOG USE	DRILLER
0064SW 8 MAURY	11909082	HARDIN LIGGETT	/ /19 / /	-- --	-- 26	--	-- - --		35-32-00 86-55-54	S	HOME
0064SW 8 MAURY	11909083	DELLA ROBERT	/ /19 / /	-- --	-- 18	--	-- - --		35-31-55 86-55-41	S	HOME
0064SW 8 MAURY	11909125	MRS R L MURPHY	/ /19 / /	-- --	-- --	--	-- - --		35-30-18 86-57-15	S	FARM
0064SW 8 MAURY	11909126	PERSIA OSBORNE	/ /19 / /	-- --	-- 12	--	-- - --		35-30-20 86-56-55	S	HOME
0064SW 8 MAURY	11909127	CAROLYN C STARLING	/ /19 / /	-- --	-- 13	--	-- - --		35-30-18 86-57-09	S	HOME
0064SW 8 MAURY	91001566	FALCONBURY____JEFF PARK STATION	04/16/1991 / /	825 780	4 60	30 OTHER	OPEN 30 -	H2S 825	- - - -	Y	00330 HOME
0064SW 8 MAURY	92001125	WILDERNESS SCHOOL N B KERR RD	11/18/1991 / /	175 75	10 6	20 OTHER	OPEN 20 -	GOOD 175	- - - -	Y	00120 COMM
0064SW 8 MAURY	92001126	NAT TR GROUP HOME 2513B KERR RD	10/28/1991 / /	85 35	45 8	20 OTHER	OPEN 20 -	GOOD 85	- - - -	Y	00120 COMM
0064SW 8 MAURY	92001127	NAT TR GROUP HOME 2513B KERR RD	10/23/1991 / /	125 --	0 --	-- OTHER	-- - --	OTHR --	- - - -	Y	00120 COMM
0064SW 8 MAURY	92003260	NAT TR GROUP HOME 2513 B KERR RD	08/07/1992 / /	1630 1630	14 65	20 OTHER	OPEN 20 -	GOOD 1630	- - - -	Y	00120 HOME
0064SW 9 MAURY	11900015	MOORE C	10/11/1963 / /	56 41	4 26	15 STEEL	-- - --	GOOD	35-31-35 86-54-55	S	00057 HOME
0064SW 9 MAURY	11900046	LEDDBETTER M	02/06/1964 / /	836 815	3 85	13 STEEL	-- - --	GOOD	35-31-09 86-53-39	S	00120 HOME
0064SW 9 MAURY	11900971	UZELL F	12/19/1979 / /	800 750	6 200	21 STEEL	-- - --	BAD	35-31-00 86-52-53	S	00330 HOME
0064SW 9 MAURY	11901041	STONE NEW CUT RD	EMME 3/15/1983 / /	307 128	1	27 STEEL	27 -	GOOD 307	- - - -	Y	00103
0064SW 9 MAURY	11901053	PREAS SMYRNA CHURCH	RONA 12/22/1982 / /	160 135	10 60	50 STEEL	50 -	GOOD 160	- - - -	Y	00613
0064SW 9 MAURY	11901054	WALSH SMYRNA CHURCH	BERN 3/24/1983 / /	125 0	20 50	0	-	BAD	- - - -	N	00613

TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION - DIVISION OF WATER SUPPLY
RECORDS OF WATER WELLS ON THE GLENDALE QUADRANGLE (0064SW) TN.

QUAD / NTH COUNTY	WELL NUM REG NUM	OWNER'S NAME LOCATION ROAD	COMP DATE INSPT DATE	TOT DEPTH AQ DEPTH	TOT YIELD STAT LEVEL	CSE DEPTH CSE TYPE	WELL FINISH INTERVAL	WAT QUAL TAG NUM	LATITUDE	A/C DRILLER LOG USE
0064SW 9 MAURY	11901055	WALSH SMYRNA CHURCH	BERN 3/24/1983 / /	160 140	10 20	21 STEEL	21 - 160	H2S	- - - -	00613 Y
0064SW 9 MAURY	11901080	WORTHY_____ RICK	04/16/1984 / /	700 645	30 50	20 OTHER	OPEN 20 - 700	GOOD	- - - -	00613 HOME Y
0064SW 9 MAURY	11901121	JAMES_____ HWY 50	RUEB 07/26/1985 / /	80 22	7 10	22 OTHER	SLOT 22 - 27	GOOD	- - - -	00330 HOME Y
0064SW 9 MAURY	11901145	CLAYTON_____ OLD COLUMBIA	TIMO 02/04/1986 / /	160 148	20 25	30 OTHER	OPEN 30 - 160	GOOD	- - - -	00330 HOME Y
0064SW 9 MAURY	11901298	TAYLOR_____ FRED	07/28/1989 / /	-- 660	15 --	34 OTHER	OPEN -- - --	OTHR	- - - -	00227 HOME Y
0064SW 9 MAURY	90001462	MORGAN_____ LUKE MOSER	GREG 04/12/1990 / /	700 660	5 10	21 OTHER	OPEN 21 - 700	H2S	- - - -	00330 HOME Y
0064SW 9 MAURY	92003208	GWYN_____ GREEN FIELD EST	PEND 07/16/1992 / /	125 95	5 45	20 OTHER	OPEN 20 - 125	GOOD	- - - -	00330 HOME Y
0064SW 9 MAURY	93004900	SHARPE_____ LUKE MOSER	JAME 10/28/1993 / /	150 73	2 45	20 OTHER	OPEN 20 - 150	H2S	- - - -	00330 HOME Y
0064SW 9 MAURY	93005117 D0002555	DUNCAN_____ BRISTOW	GENE 11/10/1993 / /	300 --	0 --	20 OTHER	OPEN 20 - 300	OTHR	- - - -	00330 HOME Y
0064SW 9 MAURY	94001935 D0002613	RUBERT_____ SMYRNA CHURCH	TODD 05/25/1994 / /	150 130	11 --	20 OTHER	OPEN 20 - 150	GOOD	- - - -	00330 HOME Y
0064SW 9 MAURY	94002829 D0002640	GRIFFIS_____ BRIS TOW 2815	RUTH 07/12/1994 / /	300 --	0 --	-- OTHER	0 - 300	GOOD	- - - -	00330 HOME Y

REFERENCE NO. 16

1990 CPH-1-44

1990 Census of
Population and Housing
Summary Population and
Housing Characteristics
Tennessee

Issued August 1991



U.S. Department of Commerce
Robert A. Mosbacher, Secretary
Rockwell A. Schnabel, Deputy Secretary

Economics and Statistics Administration
Michael R. Darby, Under Secretary
for Economic Affairs and Administrator

BUREAU OF THE CENSUS
Barbara Everitt Bryant, Director

Table 6. Household, Family, and Group Quarters Characteristics: 1990

[for definitions of terms and meanings of symbols, see text]

State County Place and [In Selected States] County Subdivision	Family households					Nonfamily households				Persons per—		Persons in group quarters			
	Persons in households	All house- holds	Total	Married- couple family	Female house- holder, no husband present	Total	Householder living alone			Household	family	Total	Insti- tutional- ized persons	Other per- sons in group quarters	
							Total	65 years and over	Female						
The State	4 748 056	1 853 725	1 348 019	1 059 569	232 699	505 706	442 129	178 077	143 105	2.56	3.05	129 129	65 389	63 740	
COUNTY															
Anderson County	67 595	27 384	19 846	16 181	2 958	7 538	6 911	3 117	2 547	2.47	2.96	655	578	77	
Bedford County	30 031	11 608	8 768	7 087	1 289	2 840	2 536	1 290	1 017	2.59	3.01	380	343	37	
Benton County	14 255	5 784	4 333	3 732	465	1 451	1 349	751	603	2.46	2.90	269	228	41	
Bledsoe County	8 608	3 261	2 522	2 104	300	739	670	320	240	2.64	3.06	1 061	1 051	10	
Blount County	84 463	33 624	25 344	21 284	3 237	8 280	7 400	3 267	2 661	2.51	2.94	1 506	1 044	462	
Bradley County	72 043	27 604	21 157	17 518	2 841	6 447	5 714	2 277	1 825	2.61	3.02	1 669	539	1 130	
Campbell County	34 783	13 150	10 158	8 036	1 702	2 992	2 789	1 496	1 192	2.65	3.07	296	285	11	
Cannon County	10 356	3 980	3 035	2 574	351	945	872	470	375	2.60	3.03	111	111	—	
Carroll County	26 860	10 727	8 013	6 612	1 092	2 714	2 531	1 435	1 148	2.50	2.95	654	388	266	
Carter County	50 225	20 189	14 979	12 283	2 114	5 210	4 779	2 314	1 839	2.49	2.94	1 280	749	531	
Cheatham County	26 840	9 515	7 748	6 679	776	1 767	1 524	587	436	2.82	3.15	300	180	120	
Chester County	11 791	4 558	3 505	2 933	446	1 053	963	514	422	2.59	3.01	1 028	187	841	
Clatsop County	25 533	9 629	7 579	6 266	1 007	2 050	1 910	935	772	2.65	3.05	604	210	394	
Clay County	7 158	2 855	2 144	1 748	301	711	649	318	214	2.51	2.93	80	71	9	
Cocke County	28 840	11 191	8 483	6 551	1 500	2 708	2 470	1 138	882	2.58	3.00	301	270	31	
Colfax County	39 855	15 500	11 727	9 693	1 556	3 773	3 431	1 588	1 264	2.57	3.01	484	452	32	
Crockett County	13 103	5 183	3 856	3 141	567	1 327	1 257	766	623	2.53	3.00	275	275	—	
Cumberland County	34 207	13 426	10 451	8 842	1 265	2 975	2 688	1 299	1 026	2.55	2.92	529	529	—	
Davidson County	489 689	207 530	131 395	95 592	29 555	76 135	62 830	18 268	14 969	2.36	2.97	21 095	10 317	10 778	
Decatur County	10 330	4 216	3 109	2 603	391	1 107	1 032	607	461	2.45	2.91	142	142	—	
DeKalb County	14 237	5 696	4 316	3 574	584	1 380	1 293	692	563	2.50	2.93	123	106	17	
Dickson County	34 532	13 019	10 099	8 188	1 510	2 920	2 648	1 285	1 007	2.65	3.06	529	389	140	
Dyer County	34 343	13 617	9 923	7 869	1 643	3 694	3 360	1 773	1 435	2.52	3.01	511	474	37	
Fayette County	25 110	8 453	6 717	5 038	1 334	1 736	1 576	765	556	2.97	3.40	449	436	13	
Fentress County	14 559	5 511	4 258	3 415	665	1 253	1 165	585	439	2.64	3.07	110	110	—	
Franklin County	33 429	12 660	9 883	8 412	1 135	2 777	2 530	1 312	1 061	2.64	3.04	1 296	314	982	
Gibson County	45 568	18 361	13 472	10 708	2 248	4 889	4 573	2 560	2 114	2.48	2.96	747	644	103	
Giles County	25 336	9 832	7 454	6 038	1 116	2 378	2 218	1 166	891	2.58	3.02	405	205	200	
Granger County	16 912	6 394	5 076	4 281	591	1 318	1 217	590	459	2.64	3.02	183	146	37	
Greene County	54 175	21 482	16 280	13 290	2 295	5 202	4 747	2 120	1 687	2.52	2.94	1 678	727	951	
Grundy County	13 157	4 784	3 743	3 048	534	1 041	976	522	412	2.75	3.18	205	193	12	
Hamblen County	49 750	19 429	14 795	11 895	2 314	4 634	4 138	1 629	1 313	2.56	2.97	730	525	205	
Hamilton County	279 044	111 799	78 964	60 790	15 042	32 835	29 025	11 581	9 488	2.50	3.02	6 492	3 622	2 870	
Hancock County	6 571	2 484	1 924	1 505	321	560	532	269	212	2.65	3.07	168	168	—	
Harden County	22 589	8 276	6 190	4 534	1 356	2 086	1 887	968	751	2.73	3.22	788	770	18	
Hart County	22 350	8 726	6 633	5 490	882	2 093	1 940	978	764	2.56	3.00	281	263	20	
Hawkins County	44 232	17 167	13 223	11 100	1 624	3 944	3 639	1 671	1 334	2.58	2.99	333	299	34	
Haywood County	19 240	7 014	5 150	3 566	1 320	1 864	1 708	905	703	2.74	3.29	197	59	138	
Henderson County	21 630	8 527	6 466	5 393	820	2 061	1 922	975	765	2.54	2.97	214	212	2	
Henry County	27 456	11 362	8 216	6 743	1 126	3 146	2 902	1 619	1 282	2.42	2.89	432	388	44	
Hickman County	15 715	5 976	4 608	3 883	526	1 368	1 229	619	505	2.63	3.04	1 039	1 039	—	
Houston County	6 842	2 683	2 039	1 705	261	644	604	335	248	2.55	2.98	176	163	13	
Humphreys County	15 551	6 063	4 593	3 844	561	1 470	1 373	665	514	2.56	3.01	244	110	134	
Jackson County	9 176	3 642	2 782	2 303	334	860	806	475	358	2.52	2.94	121	119	2	
Jefferson County	31 415	12 329	9 510	8 018	1 144	2 819	2 530	1 192	940	2.55	2.94	1 601	445	1 156	
Johnson County	13 609	5 406	4 081	3 260	599	1 325	1 230	618	464	2.52	2.95	157	145	12	
Knox County	323 400	133 639	90 561	71 679	15 478	43 078	36 661	12 962	10 642	2.42	2.97	12 349	3 288	9 061	
Lake County	6 057	2 418	1 735	1 328	323	683	625	343	262	2.50	3.00	1 072	1 051	21	
Lauderdale County	22 598	8 423	6 351	4 846	1 259	2 072	1 898	1 059	842	2.68	3.15	893	884	9	
Lawrence County	34 992	13 338	10 265	8 665	1 291	3 073	2 884	1 596	1 317	2.62	3.06	311	302	9	
Lewis County	9 098	3 533	2 606	2 179	328	927	859	451	353	2.58	3.06	149	136	13	
Lincoln County	27 910	10 881	8 230	6 812	1 097	2 451	2 455	1 376	1 090	2.57	3.01	247	239	8	
Loudon County	30 926	12 155	9 289	7 687	1 301	2 866	2 635	1 237	1 005	2.54	2.96	329	329	—	
McMinn County	41 710	16 351	12 458	10 275	1 751	3 893	3 600	1 755	1 425	2.55	2.98	673	446	227	
McMurray County	22 180	8 834	6 678	5 592	824	2 156	2 014	1 073	863	2.51	2.95	242	242	—	
Macon County	15 817	6 159	4 711	4 027	522	1 448	1 356	707	577	2.57	3.00	89	89	33	
Madison County	75 515	29 609	21 301	15 950	4 304	8 308	7 397	3 026	2 554	2.55	3.06	2 467	841	1 626	
Marion County	24 645	9 215	7 171	5 838	1 032	2 044	1 873	963	761	2.67	3.08	215	205	10	
Marshall County	21 248	8 268	6 120	4 950	881	2 148	1 954	989	779	2.57	3.04	291	279	62	
Maury County	54 073	20 608	15 552	12 280	2 672	5 056	4 554	2 052	1 680	2.67	3.07	739	688	51	
Meigs County	7 921	2 996	2 333	1 958	261	663	592	255	194	2.64	3.03	112	112	—	
Monroe County	29 940	11 363	8 781	7 231	1 163	2 582	2 385	1 167	917	2.63	3.06	601	317	284	
Montgomery County	93 516	34 345	26 914	22 284	3 712	7 431	6 208	2 071	1 628	2.72	3.09	6 982	472	6 510	
Moore County	4 714	1 734	1 391	1 222	112	343	327	169	136	2.72	3.11	7	7	—	
Morgan County	16 011	5 841	4 621	3 745	680	1 220	1 119	558	432	2.74	3.13	1 289	1 289	—	
Obion County	31 399	12 412	9 219	7 624	1 279	3 193	2 950	1 598	1 290	2.53	3.00.				

REFERENCE NO. 17


BLACK & VEATCH Waste Science, Inc.
Philadelphia Office

MEMORANDUM

USEPA Region IV
Treatment Plant/Oil Services Company
Population served by groundwater

BVWS Project 52012.545
BVWS File N
February 13, 1995

To: Treatment Plant/Oil Services Co. File

From: Michael Ferrari 


The following table depicts the distribution of the population within 4 miles of the site that obtain their water supply from groundwater or springs. This is the portion of the surrounding population which is *not* served by CPW water.

Population within 4 miles of Treatment Plant site
using groundwater or springs for drinking water

Distance Ring (miles)	Houses served by Private Supply	County Population per Household ¹	Total Population using groundwater or springs
0 - ¼	0	2.62	0
¼ - ½	0	2.62	0
½ - 1	0	2.62	0
1 - 2	8	2.62	21
2 - 3	13	2.62	34
3 - 4	28	2.62	73
Total			128

¹ Value of 2.62 is the Maury County persons per household figure obtained from U.S. Bureau of Census data.

REFERENCE NO. 18



15 mile Surface Water Migration
Pathway Map for

TREATMENT PLANT/OIL SERVICES CO.

Columbia, Maury County, TN

TND 980515779


BVWS Project # 52012.545


SPECIAL NOTE


This document was prepared primarily by stereoscopic analysis of high altitude aerial photographs. Wetlands were identified on the photographs based on vegetation, visible hydrology, and geography in accordance with **Classification of Wetlands and Deepwater Habitats of the United States (FWS/OBS - 79/31 December 1979)**. The aerial photographs typically reflect conditions during the specific year and season when they were taken. In addition, there is a margin of error inherent in the use of the aerial photographs. Thus, a detailed on the ground and historical analysis of a single site may result in a revision of the wetland boundaries established through photographic interpretation. In addition, some small wetlands and those obscured by dense forest cover may not be included on this document.

Federal, State and local regulatory agencies with jurisdiction over wetlands may define and describe wetlands in a different manner than that used in this inventory. There is

SYMBOLGY EXAMPLE







Approximate 15-mile Surface
Water Migration Pathway Limit

(GODWIN 57-NE)
3555 II NE


3

REFERENCE NO. 19



Water Resources Data Tennessee Water Year 1992

by D.F. Flohr, F.D. Edwards, J.G. Lewis, and R.A. Orr



U.S. GEOLOGICAL SURVEY WATER-DATA REPORT TN-92-1
Prepared in cooperation with the State of Tennessee
and with other agencies

TENNESSEE RIVER BASIN

03599500 DUCK RIVER AT COLUMBIA, TN

LOCATION.--Lat 35°37'05", Long 87°01'56", Maury County, Hydrologic Unit 06040003, on right bank 4 ft downstream from bridge on former U.S. Highway 31, 2 blocks north of public square in Columbia, 2.4 mi upstream from Rutherford Creek, and at mile 132.8.

DRAINAGE AREA.--1,208 mi².

PERIOD OF RECORD.--October 1904 to December 1908, April 1920 to current year. Monthly discharge only for some periods, published in WSP 1305. Gage-height records collected at same site, 1887-95, 1911 (fragmentary), 1947-71, published in reports of U.S. Weather Bureau, 1983-1991, discharge records furnished by Tennessee Valley Authority.

REVISED RECORD.--WSP 783: 1929(M). WSP 853: Drainage area. WSP 1306: 1905-9, 1920-22, 1923(M).

GAGE.--Water-stage encoder and satellite telemeter at station. Datum of gage is 535.33 ft above National Geodetic Vertical Datum of 1929, supplementary adjustment of 1955. Prior to Jan. 9, 1925, nonrecording gages near this site; all gages at datum 2.37 ft higher prior to Oct. 1, 1933.

REMARKS.--No estimated daily discharges. Records good. Maximum discharge prior to regulation, 61,500 ft³/s, Mar. 17, 1973; maximum gage height, 51.75 ft Feb. 14, 1948; minimum no flow Oct. 22, 1922, caused by regulation by power plant .75 mi upstream. Flow regulated by Normandy Lake (station 03596460) since January 1976.

EXTREMES OUTSIDE PERIOD OF RECORD.--Flood of March 30, 1902, reached a stage of 48.0 ft, present datum, discharge, 50,700 ft³/s.

EXTREMES FOR CURRENT YEAR.--Maximum discharge, 40,800 ft³/s, Dec. 3, gage height, 41.70 ft; minimum, 169 ft³/s, Oct. 5.

DISCHARGE, CUBIC FEET PER SECOND, WATER YEAR OCTOBER 1991 TO SEPTEMBER 1992
DAILY MEAN VALUES

DAY	OCT	NOV	DEC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP
1	224	252	14000	3700	999	3270	1640	481	216	819	247	823
2	202	234	25900	3220	944	2620	1430	442	237	998	307	627
3	182	229	39600	5970	895	2240	1260	399	269	1750	335	700
4	177	225	38100	11000	856	1810	1110	345	1820	2110	257	788
5	171	217	29000	8110	786	1390	1000	316	1220	1820	248	1120
6	171	213	10400	4960	631	1220	887	293	1010	2200	268	1000
7	180	321	5220	4340	581	1110	836	282	776	2700	297	775
8	231	498	4320	3970	552	1090	834	281	628	1710	261	619
9	226	493	6390	3900	523	1080	890	276	584	1210	239	604
10	210	490	13400	5110	492	11500	811	286	468	918	270	468
11	205	489	11900	3880	467	15600	732	285	992	732	458	372
12	205	486	6730	2620	448	8160	672	284	752	608	587	312
13	191	480	6420	2560	441	4470	613	317	637	516	518	283
14	194	476	12100	6230	448	3270	564	321	1360	452	1160	284
15	191	476	12500	5610	498	2610	578	360	1020	414	1060	268
16	187	471	7240	4320	641	2200	691	316	692	387	572	253
17	186	472	5110	3470	707	1940	586	259	509	374	378	247
18	189	469	4170	2970	785	1830	578	228	417	362	297	575
19	181	462	3540	2150	800	2680	525	209	421	341	253	601
20	181	573	3140	1690	778	3210	577	194	1990	333	232	640
21	178	911	2870	1510	710	2910	1270	191	1050	318	228	512
22	176	939	2700	1380	645	2220	2320	209	635	294	233	3970
23	266	1610	2710	1410	2900	2300	2170	233	447	290	435	17100
24	610	1780	4710	1650	7650	2680	1430	231	383	844	410	19000
25	994	1170	5170	1670	5680	2220	1070	204	357	1090	537	6550
26	697	882	3500	1480	8390	2020	862	191	1270	569	671	4700
27	482	759	2730	1340	10100	1980	742	182	1980	393	700	6010
28	376	724	2740	1250	6440	1750	649	178	1660	326	2410	4420
29	316	693	6420	1170	4420	1530	577	207	981	286	4400	3000
30	282	1770	6470	1110	---	1540	528	207	693	264	2390	2150
31	262	---	4290	1050	---	1720	---	198	---	255	1210	---
TOTAL	8523	19264	303490	104800	60207	96170	28432	8405	25474	25683	21868	78771
MEAN	275	642	9790	3381	2076	3102	948	271	849	828	705	2626
MAX	994	1780	39600	11000	10100	15600	2320	481	1990	2700	4400	19000
MIN	171	213	2700	1050	441	1080	525	178	216	255	228	247
(+)	-2300	-8000	-9000	-2100	+2200	+6500	+5800	+100	+1500	-1400	-700	+1500
MEAN±	201	375	9500	3313	2152	3312	1141	274	899	783	683	2676
CFSM±	.17	.31	7.86	2.74	1.78	2.74	.94	.23	.74	.65	.57	2.22
IN.±	.19	.35	9.07	3.16	1.92	3.16	1.05	.26	.83	.75	.65	2.47

CAL YR 1991 MEAN± 3112 CFSM± 2.58 IN.± 34.97
WTR YR 1992 MEAN± 2140 CFSM± 1.77 IN.± 24.11

† Change in contents, in cfs-days, in Normandy Lake.

± Adjusted for change in contents.

NOTE.--Contents (cfs-days) for adjustments furnished by Tennessee Valley Authority.

TENNESSEE RIVER BASIN

215


03599500 DUCK RIVER AT COLUMBIA, TN--Continued

STATISTICS OF MONTHLY MEAN DATA FOR WATER YEARS 1977 - 1992, BY WATER YEAR (WY)

MEAN	842	2299	3804	3375	3606	3745	2533	2255	882	726	401	728
MAX	3642	5925	10360	8513	9901	10090	6984	9105	4117	4740	938	3832
(WY)	1990	1987	1991	1979	1991	1980	1983	1983	1989	1989	1982	1979
MIN	180	236	418	273	953	1104	325	244	167	220	185	163
(WY)	1988	1981	1981	1986	1978	1985	1986	1988	1988	1988	1991	1984

SUMMARY STATISTICS	FOR 1991 CALENDAR YEAR		FOR 1992 WATER YEAR		*WATER YEARS 1977 - 1992	
ANNUAL TOTAL	1144351		781087		2094	
ANNUAL MEAN	3135		2134		3282	
HIGHEST ANNUAL MEAN					553	
LOWEST ANNUAL MEAN					52300	
HIGHEST DAILY MEAN	52300	Feb 20	39600	Dec 3	52300	Feb 20 1991
LOWEST DAILY MEAN	117	Sep 13	171	aOct 5	86	Oct 4 1982
ANNUAL SEVEN-DAY MINIMUM	123	Sep 8	183	Oct 16	100	Sep 28 1982
INSTANTANEOUS PEAK FLOW			40800	Dec 3	52300	Feb 20 1991
INSTANTANEOUS PEAK STAGE			41.70	Dec 3	45.82	Feb 20 1991
INSTANTANEOUS LOW FLOW			169	Oct 5		
ANNUAL RUNOFF (CFSM)	2.60		1.77		1.73	
ANNUAL RUNOFF (INCHES)	35.24		24.05		23.55	
10 PERCENT EXCEEDS	7060		5110		4870	
50 PERCENT EXCEEDS	1110		717		732	
90 PERCENT EXCEEDS	170		227		187	


* Regulated period only.
a Also occurred Oct. 6



REFERENCE NO. 20

NOV 14 1994 02:42PM BLACK & WHITE WASTE SCIENCE P. 27

ENDANGERED & THREATENED SPECIES



of the **SOUTHEAST**
UNITED STATES



"The Red Book"
REGION 4
ATLANTA
GEORGIA

9300991

**ENDANGERED AND THREATENED SPECIES
OF THE
SOUTHEASTERN UNITED STATES
(THE RED BOOK)**

Prepared by:

U.S. Fish and Wildlife Service
Southeast Region
Atlanta, Georgia

January 1992

Availability Unlimited
For Sale by Superintendent of Documents
Post Office Box 371954
Pittsburgh, PA 15250-7954

Stock Order Number: 924-003-00000-6

4/22/92

Federally Listed Species by StateTENNESSEE

(E=Endangered; T=Threatened; CH=Critical Habitat determined)

<u>Mammals</u>	<u>General Distribution</u>	
Bat, gray (<u>Myotis grisescens</u>) - E	Entire State	✓
Bat, Indiana (<u>Myotis sodalis</u>) - E, CH	Central, East	✓
Cougar, eastern (<u>Felis concolor couguar</u>) - E	North, East	✓
Panther, Florida (<u>Felis concolor coryi</u>) - E	Southwest	
Squirrel, Carolina northern flying (<u>Glaucomys sabrinus coloratus</u>) - E	Eastern mountains (Carter and Sevier Counties)	
<u>Birds</u>		
Eagle, bald (<u>Haliaeetus leucocephalus</u>) - E	Entire State	✓
Falcon, American peregrine (<u>Falco peregrinus anatum</u>) - E	East, Central, Extreme Northwest	✓
Falcon, Arctic peregrine (<u>Falco peregrinus tundrius</u>) - T	Entire State (mostly West)	✓
Tern, least (<u>Sterna antillarum</u>) interior population - E	Mississippi River West	
Warbler, Bachman's (<u>Vermivora bachmanii</u>) - E	Extreme Northeast	
Warbler, Kirtland's (<u>Dendroica kirtlandii</u>) - E		
Woodpecker, ivory-billed (<u>Campephilus principalis</u>) - E	Extreme West	
Woodpecker, red-cockaded (<u>Picoides [=Dendrocopos] borealis</u>) - E	East	✓
<u>Fishes</u>		
Chub, slender (<u>Hybopsis cahni</u>) - T,CH	Hancock, Claiborne, Grainger Counties	
Chub, spotfin (<u>Hybopsis monacha</u>) - T,CH	Hawkins, Sullivan, Morgan, Fentress, and Cumberland Counties	
Dace, blackside (<u>Phoxinus Cumberlandensis</u>) - T	Upper Cumberland River System (Scott, Campbell, and Claiborne Counties)	
Darter, amber (<u>Percina antesella</u>) - E,CH	Conasauga R., Polk County	

TENNESSEE (Cont'd)

Darter, boulder (Etheostoma [Nothonotus sp.) - E

Darter, slackwater (Etheostoma boschungii) - T, CH

Darter, snail (Percina tanasi) - T

Logperch, Conasauga (Percina jenkinsi) - E, CH

Madtom, smoky (Noturus bailey) - E, CH

Madtom, yellowfin (Noturus flavipinnis) - T, CH

Shiner, blue (Cyprinella caerulea) - T

Mollusks

Mussel, Alabama lamp pearly (Lampsilis virescens) - E

Mussel, Appalachian monkeyface pearly (Quadrula sparsa) - E

Mussel, birdwing pearly (Conradilla caelata) - E

Mussel, Cumberland bean pearly (Villosa trabilis) - E

Mussel, Cumberland monkeyface pearly (Quadrula intermedia) - E

Mussel, Cumberland pigtoe (Pleurobema gibberum) - E

Mussel, dromedary pearly (Dromus dromas) - E

Mussel, fine-rayed pigtoe pearly (Fusconaia cuneolus) - E

State Lists 4/22/92

General Distribution

Lower Elk River System,
Giles County

Wayne and Lawrence
Counties
Knox, Loudon, Meigs, Polk,
Bradley/McMinn, Hamilton,
Marion, and Giles Counties

Conasauga R., Polk
County

Citico Creek, Monroe
County

Claiborne and Hancock
Counties; Monroe County
(Citico Creek)

Conasauga River and
Minnewauga Creek

Estill Fork, Franklin
County

Powell River

Powell, Clinch, Elk and
Duck Rivers

Big S. Fork of
Cumberland River

Elk, Powell and Duck
Rivers

Caney Fork River System

Powell, Clinch,
Cumberland and Tennessee
Rivers

Powell, Clinch, Elk,
Sequalchie, N. Fork Holston
and Little Rivers

TENNESSEE (Cont'd)

State Lists 4/22/92

Mussel, green-blossom pearly
 (Epioblasma [=Dysnomia]
torulosa gubernaculum) - E

Clinch River

General Distribution

Mussel, little-wing pearly
 (Pegias fabula) - E

Cave Creek

Mussel, orange-footed pearly
 (Plethobasus cooperianus) - E

Tennessee and
Cumberland Rivers

Mussel, pale lilliput pearly
Toxolasma [= Carunculina] cylindrella) - E

Historic; no recent TN
records

Mussel, pink mucket pearly
 (Lampsilis orbiculata) - E

Tennessee, Clinch and
Cumberland Rivers

Mussel, rough pigtoe pearly
 (Pleurobema plenum) - E

Clinch, Cumberland and
Tennessee Rivers

Mussel, shiny pigtoe pearly
 (Fusconaia edgariana) - E

Powell, Clinch and Elk
Rivers

Mussel, tan riffle shell
 (Epioblasma [=Dysnomia] walkeri) - E

Historic; no recent TN
records

Mussel, tubercled-blossom pearly
 (Epioblasma [=Dysnomia] torulosa
torulosa) - E

Possibly extinct

Mussel, turgid-blossom pearly
 (Epioblasma [=Dysnomia] turgidula) - E

Possibly extinct

Mussel, white warty-back pearly
 (Plethobasus cicatricocis) - E

Tennessee River

Mussel, yellow-blossom pearly
 (Epioblasma [=Dysnomia] florentina
florentina) - E

Possibly extinct

Snail, Chittenango ovate amber
 (Succinea chittenangoensis) - T

Monroe County

Snail, painted snake coiled forest
 (Anquospira picta) - T

Franklin County

Arthropods:

Crayfish, Nashville (Orconectes shoupi) - E

Mill Creek, Davidson and
Williamson CountiesPlants

Arenaria cumberlandensis (Cumberland
 sandwort) - E

Cumberland plateau
north central (Fentress,
Morgan, Pickett, and Scott
Counties)

TENNESSEE (Cont'd)

State Lists 4/22/92

Conradina verticillata (Cumberland
rosemary) - TGeneral Distribution

Big South Fork Cumberland
River, Morgan, Scott, and
Fentress Counties; Caney
Fork River, Cumberland and
White Counties; Obed River
System, Morgan and
Cumberland Counties

Astragalus bibullatus (Guthrie's
ground-plum) - E

Rutherford County

Dalea foliosa (=Petalostanum
foliosum) - (Leafy prairie clover) - E

Rutherford, Wilson,
Marshall, Bedford,
Davidson, Williamson,
and Maury Counties

Echinacea tennesseensis (Tennessee
coneflower) - E

Davidson, Rutherford,
Wilson Counties

Isotria medeoloides (small whorled
pogonia) - E

Hamilton County

Phyllitis scolopendrium var. Americana
(American Hart's Tongue Fern) - T

Marion County

Pityopsis ruthii (Ruth's golden aster) - E

Polk County

Scutellaria montana (large-flowered
skullcap) - E

Hamilton and Marion
Counties

Solidago spithamea (Blue Ridge
goldenrod) - T

Carter County ✓

Xyris tennesseensis (Tennessee yellow-eyed
grass) - E

Lewis County

REFERENCE NO. 21

CENSUS DATA

=====

Treatment Plt

LATITUDE 35:37:38 LONGITUDE 87: 2:15 1990 HOUSING

	0- $\frac{1}{4}$ mile	$\frac{1}{4}$ - $\frac{1}{2}$ mile	$\frac{1}{2}$ -1 mile	1-2 miles	2-3 miles	3-4 miles	SECTOR
KM	0.00-.400	.400-.800	.800-1.60	1.60-3.20	3.20-4.80	4.80-6.40	TOTALS
S 1	0	0	0	0	104	0	104
S 2	0	0	687	779	0	0	1466
S 3	0	0	0	489	0	0	489
S 4	0	0	0	1595	247	0	1842
S 5	0	0	508	649	869	0	2026
S 6	0	0	430	698	2129	658	3915
S 7	0	0	774	517	0	306	1597
S 8	0	0	517	0	0	0	517
RING	0	0	2916	4727	3349	964	11956
TOTALS							

Press RETURN key to continue ...

ANSILG ONBIN80:09600 7E1 [Home]=Menu FDX 8 LF X

GEMS database printout for the Treatment Plant/Oil
Services Company site.

Downloaded by Corry T. Platt, BYWS, February 13, 1995.

REFERENCE NO. 22

BLACK & VEATCH Waste Science, Inc.
Philadelphia Office

MEMORANDUM

USEPA Region IV
Treatment Plant/Oil Services Company
Population Within 4 mile radius

BVWS Project 52012.545
BVWS File N
February 13, 1995

To: Treatment Plant/Oil Services Co. File

From: Michael Ferrari

MFE

The following table depicts the distribution of the population within 4 miles of the site.

Distance Ring (miles)	Houses	County Population per Household	Total Population
0 - ¼	29 ¹	2.62 ²	76
¼ - ½	193 ¹	2.62 ²	506
½ - 1	-	-	2,916 ³
1 - 2	-	-	4,727 ³
2 - 3	-	-	3,349 ³
3 - 4	-	-	964 ³
Total			12,538

¹ Number of houses obtained from house count from USGS topographic maps.

² Value of 2.62 is the Maury County persons per household figure obtained from U.S. Bureau of Census data.

³ Population values obtained from GEMS database.

REFERENCE NO. 23


BLACK & VEATCH Waste Science, Inc.
Philadelphia Office

MEMORANDUM

USEPA Region IV
Treatment Plant/Oil Services Company
Wetlands within 4 miles of site

BVWS Project 52012.545
BVWS File N
February 10, 1995

To: Treatment Plant/Oil Services Co. File

From: Michael Ferrari 

The following table depicts the distribution of wetlands within 4 miles of the site.

Distance Ring (miles)	Wetland acreage
0 - ¼	0
¼ - ½	0
½ - 1	0
1 - 2	11
2 - 3	24
3 - 4	39
Total	74 acres

REGION: 04
STATE: TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

1 : 933
RUN DATE: 02/03/87
RUN TIME: 13:53:24

M.2 - SITE MAINTENANCE FORM

EPA ID : TND980515779

SITE NAME: TREATMENT PLANT/OIL SERVICES CO

SOURCE: H

STREET : 408 SANTA FE PIKE

CONG DIST: 06

CITY : COLUMBIA

ZIP: 38401

CNTY NAME: MAURY

CNTY CODE : 119

LATITUDE : 35/36/54.0

LONGITUDE : 087/02/12.0

LL-SOURCE: R

LL-ACCURACY:

SMSA :

HYDRO UNIT: 06040003

INVENTORY IND: Y REMEDIAL IND: Y REMOVAL IND: N FED FAC IND: N

NPL IND: N NPL LISTING DATE:

NPL DELISTING DATE:

SITE/SPILL IDS:

RPM NAME:

RPM PHONE: - -

SITE CLASSIFICATION:

SITE APPROACH:

DIOXIN TIER:

REG FLD1:

REG FLD2: 4

RESP TERM: PENDING ()

NO FURTHER ACTION ()

ENF DISP: NO VIABLE RESP PARTY ()
ENFORCED RESPONSE ()

VOLUNTARY RESPONSE ()
COST RECOVERY ()

SITE DESCRIPTION:

* ACTION: _

* _____ *

* _____ *

* _____ *

* _____ *

* ____/____/____.____ *

* _____ *

* _____ *

* _____ *

* _____/____/____ *

* _____ *

* _____ *

* _____ *

* _____ *

* PENDING (____) NO FURTHER ACTION (____) *

* _____ *

* _____ *

* _____ *

* _____ *

* _____ *

* _____ *

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

934
RUN DATE: 02/03/87
RUN TIME: 13:53:24

M.2 - PROGRAM MAINTENANCE FORM

SITE: TREATMENT PLANT/OIL SERVICES CO

EPA ID: TND980515779 PROGRAM CODE: H01 PROGRAM TYPE:

PROGRAM QUALIFIER: ALIAS LINK :

PROGRAM NAME: SITE EVALUATION

DESCRIPTION:

* ACTION: _

* _ *

* _ *

* _ *

* _ *

* _ *

* _ *

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

935
RUN DATE: 02/03/87
RUN TIME: 13:53:24

M.2 - EVENT MAINTENANCE FORM

SITE: TREATMENT PLANT/OIL SERVICES CO
PROGRAM: SITE EVALUATION

EPA ID: TND980515779 PROGRAM CODE: H01

EVENT TYPE: DS1

FMS CODE: EVENT QUALIFIER :

EVENT LEAD: E

EVENT NAME: DISCOVERY

STATUS:

DESCRIPTION:

* ACTION: _

* _ _ _ _ *

* _ _ _ _ *

* _ _ _ _ *

* _ _ _ _ *

* _ _ _ _ *

* _ _ _ _ *

ORIGINAL

CURRENT

ACTUAL

START:

START:

START:

* _/_/_

//_

//_ *

COMP :

COMP :

COMP : 03/01/81

* _/_/_

//_

//_ *

HQ COMMENT:

* _ _ _ _ *

RG COMMENT:

* _ _ _ _ *

COOP AGR #

AMENDMENT #

STATUS

STATE %

0

* _ _ _ _ *

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

936
RUN DATE: 02/03/87
RUN TIME: 13:53:24

M.2 - EVENT MAINTENANCE FORM

SITE: TREATMENT PLANT/OIL SERVICES CO
PROGRAM: SITE EVALUATION

EPA ID: TND980515779 PROGRAM CODE: H01

EVENT TYPE: PA1

FMS CODE: EVENT QUALIFIER :

EVENT LEAD: S

EVENT NAME: PRELIMINARY ASSESSMENT

STATUS:

DESCRIPTION:

* ACTION: _

* _ _ _ *

* _ _ _ *

* _ _ _ *

* _ _ _ *

* _ _ _ *

* _ _ _ *

ORIGINAL

CURRENT

ACTUAL

START:

START:

START: 01/01/84

* _/_/_ _/_/_ _/_/_ *

COMP :

COMP :

COMP : 08/01/84

* _/_/_ _/_/_ _/_/_ *

HQ COMMENT:

* _ _ _ *

RG COMMENT:

* _ _ _ *

COOP AGR #

AMENDMENT #

STATUS

STATE %

0

* _ _ _ _ *

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

```

          :          937
RUN DATE: 02/03/87
RUN TIME: 13:53:24

```

* ACTION: _____

STATUS:

* _____
 * _____
 * _____
 * _____
 * _____
 * _____

RG COMMENT:

①

* _/_/_/____

* _/_/_/____

* _/_/_/____

* _____

* _____

* _____

REGION: 04
STATE : TN

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF EMERGENCY AND REMEDIAL RESPONSE
C E R C L I S V 1.2

: 938
RUN DATE: 02/03/87
RUN TIME: 13:53:24

M.2 - COMMENT MAINTENANCE FORM

SITE: TREATMENT PLANT/OIL SERVICES CO

EPA ID: TND980515779

COM
NO COMMENT

001 PART A- ON FILE

ACTION

*	-	_____	*
*		_____	*



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION

01 STATE TN 02 SITE NUMBER TND980515779

II. SITE NAME AND LOCATION

01 SITE NAME Oil Service Co. / Treatment Plant 02 STREET ROUTE NO. OR SPECIFIC LOCATION IDENTIFIER 408 Santa Fe Pike
03 CITY Columbia 04 STATE TN 05 ZIP CODE 38401 06 COUNTY Maury 07 COUNTY CODE 08 CONG. DIST.
09 COORDINATES
LATITUDE LONGITUDE
10 TYPE OF OWNERSHIP (Check one)
☒ A. PRIVATE ☐ B. FEDERAL ☐ C. STATE ☐ D. COUNTY ☐ E. MUNICIPAL ☐ F. OTHER ☐ G. UNKNOWN

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 4-5-84 02 SITE STATUS ☒ ACTIVE ☐ INACTIVE 03 YEARS OF OPERATION 1980 present UNKNOWN
MONTH DAY YEAR BEGINNING YEAR ENDING YEAR
04 AGENCY PERFORMING INSPECTION (Check all that apply)
☐ A. EPA ☐ B. EPA CONTRACTOR ☐ C. MUNICIPAL ☐ D. MUNICIPAL CONTRACTOR
☒ E. STATE ☐ F. STATE CONTRACTOR ☐ G. OTHER

05 CHIEF INSPECTOR Karen Bonner 06 TITLE Chemist 07 ORGANIZATION SWM 08 TELEPHONE NO. (615) 741-6287
09 OTHER INSPECTORS Charles Allen 10 TITLE Engineer 11 ORGANIZATION SWM 12 TELEPHONE NO. (615) 741-6287
() ()
() ()
() ()
() ()

13 SITE REPRESENTATIVES INTERVIEWED
Kenneth Harris 14 TITLE President 15 ADDRESS 302 Hill St. Columbia, TN 38401 16 TELEPHONE NO. (615) 381-4999
Steve Maloney 17 TITLE Operator 18 ADDRESS Tri-Tech Waldron Rd. Dover, TN 19 TELEPHONE NO. (615) 388-3448
() ()
() ()
() ()
() ()

17 ACCESS GAINED BY (Check one)
☒ PERMISSION ☐ WARRANT 18 TIME OF INSPECTION 12:30 PM 19 WEATHER CONDITIONS Cloudy, 45°F

IV. INFORMATION AVAILABLE FROM

01 CONTACT Steve Maloney 02 OF Agency Organization Tri-Tech Laboratories 03 TELEPHONE NO. (615) 793-7547
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Karen Bonner 05 AGENCY SWM 06 ORGANIZATION 07 TELEPHONE NO. (615) 741-6287 08 DATE 4-9-84
MONTH DAY YEAR



1. HIGHLY VOLATILE
2. EXPLOSIVE
3. REACTIVE
4. INCOMPATIBLE
5. NOT APPLICABLE



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TN10

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ M. UNSTABLE CONTAINMENT OF WASTES

Spills, Leaks, Releases, Leaking Drums

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____

04 NARRATIVE DESCRIPTION

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ P. ILLEGAL UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE _____)

☐ POTENTIAL

☐ ALLEGED

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e.g., State Reg. Agency, Reports, Reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TN0980515779

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

01 ☐ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

01 ☐ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

01 ☐ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: _____ Acres 04 NARRATIVE DESCRIPTION

01 ☐ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED _____ 04 NARRATIVE DESCRIPTION



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE TN 02 SITE NUMBER 7ND98051579

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED <small>Check all that apply.</small>	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCC PLAN				
<input type="checkbox"/> G. STATE <small>Specify:</small>				
<input type="checkbox"/> H. LOCAL <small>Specify:</small>				
<input type="checkbox"/> I. OTHER <small>Specify:</small>				
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/ DISPOSAL <small>Check all that apply.</small>	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT <small>Check all that apply.</small>	05 OTHER
<input type="checkbox"/> A. SURFACE IMPOUNDMENT			<input type="checkbox"/> A. INCINERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/ PHYSICAL	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input checked="" type="checkbox"/> E. WASTE OIL PROCESSING	06 AREA OF SITE
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/ RECOVERY	
<input type="checkbox"/> H. OPEN DUMP			<input type="checkbox"/> H. OTHER <small>Specify:</small>	
<input checked="" type="checkbox"/> I. OTHER <u>Basins</u> <small>Specify:</small>	<u>unknown</u>			

07 COMMENTS

This is an old sewer treatment plant that Oil Services leased 3 years ago. A company by the name of Ore-Tech operates this plant for them. They treat waste oil. Waste water is discharged to the municipal system and is tested every so often. Oil Services hauls sludge and waste oil out to a licensed treatment facility.

IV. CONTAINMENT

01 CONTAINMENT OF WASTES Check one:

☒ A. ADEQUATE, SECURE ☐ B. MODERATE ☐ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

Waste oil is contained in concrete basins.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE ☒ YES ☐ NO

02 COMMENTS

VI. SOURCES OF INFORMATION (Cite specific references, e.g. SIBS files, SIBS analysis reports.)

4-5-84 - Site Investigation



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

1. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TN0980515-719

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE Check one.

☐ A 10^{-6} - 10^{-7} cm/sec ☐ B 10^{-7} - 10^{-8} cm/sec ☐ C 10^{-8} - 10^{-9} cm/sec ☐ D GREATER THAN 10^{-5} cm/sec

02 PERMEABILITY OF BEDROCK Check one.

☐ A IMPERMEABLE ☐ B RELATIVELY IMPERMEABLE ☐ C RELATIVELY PERMEABLE ☐ D VERY PERMEABLE
Less than 10^{-9} cm/sec 10^{-9} - 10^{-7} cm/sec 10^{-7} - 10^{-5} cm/sec Greater than 10^{-5} cm/sec

03 DEPTH TO BEDROCK

04 DEPTH OF CONTAMINATED SOIL ZONE

05 SOIL ON

06 NET PRECIPITATION

07 ONE YEAR 24 HOUR RAINFALL

08 SLOPE

SITE SLOPE

DIRECTION OF SITE SLOPE

TERRAIN AVERAGE SLOPE

09 FLOOD POTENTIAL

10

SITE IS IN _____ YEAR FLOODPLAIN

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

OTHER

A. _____ (ft)

B. _____ (ft)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

_____ (ft)

ENDANGERED SPECIES: _____

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS, NATIONAL STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A. _____ (ft)

B. _____ (ft)

C. _____ (ft)

D. _____ (ft)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state maps, sample analysis reports)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5- WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
TX	TXID980515

774

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY <small>(Check as appropriate)</small>		02 STATUS			03 DISTANCE TO SITE	
<input type="checkbox"/> SURFACE	<input type="checkbox"/> WELL	<input type="checkbox"/> ENDANGERED	<input type="checkbox"/> AFFECTED	<input type="checkbox"/> MONITORED		
COMMUNITY	A <input type="checkbox"/> B <input type="checkbox"/>	A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/>	A. _____ (mi)			
NON-COMMUNITY	C <input type="checkbox"/> D <input type="checkbox"/>	D <input type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/>	B. _____ (mi)			

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☐ A. ONLY SOURCE FOR DRINKING ☐ B. DRINKING (Other sources available) ☐ C. COMMERCIAL, INDUSTRIAL, IRRIGATION ☐ D. NOT USED, UNUSEABLE (Other sources available)

☐ COMMERCIAL, INDUSTRIAL, IRRIGATION (No other water sources available)

02 POPULATION SERVED BY GROUND WATER _____		03 DISTANCE TO NEAREST DRINKING WATER WELL _____ (mi)	
04 DEPTH TO GROUNDWATER _____ (ft)	05 DIRECTION OF GROUNDWATER FLOW _____	06 DEPTH TO AQUIFER OF CONCERN _____ (ft)	07 POTENTIAL YIELD OF AQUIFER _____ (gpd)
		08 SOLE SOURCE AQUIFER <input type="checkbox"/> YES <input type="checkbox"/> NO	

09 DESCRIPTION OF WELLS (Including usage, depth, and location relative to population and buildings)

10 RECHARGE AREA <input type="checkbox"/> YES <input type="checkbox"/> NO		11 DISCHARGE AREA <input type="checkbox"/> YES <input type="checkbox"/> NO	
COMMENTS _____		COMMENTS _____	

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☐ A. RESERVOIR, RECREATION, DRINKING WATER SOURCE ☐ B. IRRIGATION, ECONOMICALLY IMPORTANT RESOURCES ☐ C. COMMERCIAL, INDUSTRIAL ☐ D. NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME	AFFECTED	DISTANCE TO SITE
_____	<input type="checkbox"/>	_____ (mi)
_____	<input type="checkbox"/>	_____ (mi)
_____	<input type="checkbox"/>	_____ (mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN			02 DISTANCE TO NEAREST POPULATION _____ (mi)
ONE (1) MILE OF SITE A. _____ NO. OF PERSONS	TWO (2) MILES OF SITE B. _____ NO. OF PERSONS	THREE (3) MILES OF SITE C. _____ NO. OF PERSONS	

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE _____	04 DISTANCE TO NEAREST OFF-SITE BUILDING _____ (mi)
---	---

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural village, densely populated urban area)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

TN IND. 9805K

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER			
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL			
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN


01 TYPE	02 COMMENTS

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input type="checkbox"/> GROUND <input type="checkbox"/> AERIAL		02 IN CUSTODY OF _____ <small>Name of organization or individual</small>
03 MAPS <input type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS _____	

V. OTHER FIELD DATA COLLECTED Provide narrative description

VI. SOURCES OF INFORMATION Cite specific references, e.g., 12345 Map, 56789 Photos, 101112



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

II. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TN0980515779

II. CURRENT OWNER(S)				PARENT COMPANY			
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
City of Columbia							
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		12 CITY		13 STATE 14 ZIP CODE	
Columbia		TN 38401					
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		12 CITY		13 STATE 14 ZIP CODE	
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		12 CITY		13 STATE 14 ZIP CODE	
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD, etc.)		11 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		12 CITY		13 STATE 14 ZIP CODE	
III. PREVIOUS OWNER(S) (List most recent first)				IV. REALTY OWNER(S) (List most recent first)			
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		05 CITY		06 STATE 07 ZIP CODE	
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		05 CITY		06 STATE 07 ZIP CODE	
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD, etc.)		04 SIC CODE	
05 CITY		06 STATE 07 ZIP CODE		05 CITY		06 STATE 07 ZIP CODE	

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, satellite analysis, reports)

4-5-84 - See Investigation



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TND98056

11/14

II. CURRENT OPERATOR <small>(Provide if different from owner)</small>				OPERATOR'S PARENT COMPANY <small>(If different from owner)</small>			
01 NAME TRI-TECH		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS <small>(P.O. Box, APO, etc.)</small> WALDRON RD		04 SIC CODE		12 STREET ADDRESS <small>(P.O. Box, APO, etc.)</small>		13 SIC CODE	
05 CITY LOVERBONE		06 STATE TN	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER					
III. PREVIOUS OPERATOR(S) <small>(List most recent first; provide only if different from owner)</small>				PREVIOUS OPERATORS' PARENT COMPANIES <small>(If different from owner)</small>			
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS <small>(P.O. Box, APO, etc.)</small>		04 SIC CODE		12 STREET ADDRESS <small>(P.O. Box, APO, etc.)</small>		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS <small>(P.O. Box, APO, etc.)</small>		04 SIC CODE		12 STREET ADDRESS <small>(P.O. Box, APO, etc.)</small>		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS <small>(P.O. Box, APO, etc.)</small>		04 SIC CODE		12 STREET ADDRESS <small>(P.O. Box, APO, etc.)</small>		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, written reports, records)

4-5-84-Site Investigation



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TN0980515779

II. ON-SITE GENERATOR

01 NAME	02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	
05 CITY	06 STATE 07 ZIP CODE	

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

--



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

TN TN09805153

II. PAST RESPONSE ACTIVITIES

01 ☐ A. WATER SUPPLY CLOSED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ D. SPILLED MATERIAL REMOVED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ E. CONTAMINATED SOIL REMOVED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ F. WASTE REPACKAGED
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ G. WASTE DISPOSED ELSEWHERE
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ H. ON SITE BURIAL
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ I. IN SITU CHEMICAL TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ J. IN SITU BIOLOGICAL TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ K. IN SITU PHYSICAL TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ L. ENCAPSULATION
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ M. EMERGENCY WASTE TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ N. CUTOFF WALLS
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ O. EMERGENCY DRINKING/SURFACE WATER DIVERSION
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ P. CUTOFF TRENCHES/SUMP
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Q. SUBSURFACE CUTOFF WALL
04 DESCRIPTION

02 DATE

03 AGENCY



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TN09805157A

II PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ S. CAPPING/COVERING
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ T. BULK TANKAGE REPAIRED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ U. GROUT CURTAIN CONSTRUCTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ V. BOTTOM SEALED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ W. GAS CONTROL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ X. FIRE CONTROL
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ Y. LEACHATE TREATMENT
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ Z. AREA EVACUATED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ 1. ACCESS TO SITE RESTRICTED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ 2. POPULATION RELOCATED
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

01 ☐ 3. OTHER REMEDIAL ACTIVITIES
04 DESCRIPTION

02 DATE _____

03 AGENCY _____

III. SOURCES OF INFORMATION Cite specific references, e.g., state files, sample analysis, reports.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

1. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN TND98C515779


II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☐ YES ☒ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

III. SOURCES OF INFORMATION (Cite reports referenced, e.g., 2000 AED, 2000 AEDS, 2000 AEDS, 2000 AEDS)

4-5-84 - Site Investigation



Site #1 Columbia - Navy Co
Landfill
Bam Webster Property
Godwin Quad (57-NE)


Alexander general
boundaries
only
(see plans)

SCALE 1:24,000

COLUMBIA 0.8 MI.
PULASKI 31 MI.

35° 37' 30"
87° 00'
900000m E.

		POTENTIAL HAZARDOUS WASTE SITE PRELIMINARY ASSESSMENT PART 1 - SITE INFORMATION AND ASSESSMENT				I. IDENTIFICATION 01 STATE 02 SITE NUMBER TN D980515779	
II. SITE NAME AND LOCATION							
01 SITE NAME (Legal, common, or descriptive name of site) Oil Service Co./Treatment Plant				02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 408 Santa Fe Pike			
03 CITY Columbia		04 STATE TN		05 ZIP CODE 38401		06 COUNTY Maury	
07 COUNTY CODE 119		08 CONG DIST 06					
09 COORDINATES LATITUDE 35 37 38. -				LONGITUDE 087 02 15. -			
10 DIRECTIONS TO SITE (Starting from nearest public road)							
III. RESPONSIBLE PARTIES							
01 OWNER (If known) President - Kenneth Harris Oil Services Co.				02 STREET (Business, mailing, residential) Box 1203			
03 CITY Columbia		04 STATE TN		05 ZIP CODE 38401		06 TELEPHONE NUMBER (615) 331-4999	
07 OPERATOR (If known and different from owner)				08 STREET (Business, mailing, residential)			
09 CITY		10 STATE		11 ZIP CODE		12 TELEPHONE NUMBER	
13 TYPE OF OWNERSHIP (Check one): <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL: _____ (Agency name) <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER: _____ (Specify) <input type="checkbox"/> G. UNKNOWN							
14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply): <input type="checkbox"/> A. RCRA 3001 DATE RECEIVED: _____ MONTH DAY YEAR <input type="checkbox"/> B. UNCONTROLLED WASTE SITE (RCRA 103) DATE RECEIVED: _____ MONTH DAY YEAR <input type="checkbox"/> C. NONE							
IV. CHARACTERIZATION OF POTENTIAL HAZARD							
01 ON SITE INSPECTION <input type="checkbox"/> YES DATE _____ MONTH DAY YEAR <input type="checkbox"/> NO				BY (Check all that apply): <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: _____ (Specify) CONTRACTOR NAME(S): _____			
02 SITE STATUS (Check one): <input type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input type="checkbox"/> C. UNKNOWN				03 YEARS OF OPERATION BEGINNING YEAR 1970 ENDING YEAR - <input type="checkbox"/> UNKNOWN			
04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED Water soluble oils							
05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION							
V. PRIORITY ASSESSMENT							
01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste information and Part 3 - Description of Hazardous Conditions and Incidents): <input type="checkbox"/> A. HIGH (Inspection required promptly) <input type="checkbox"/> B. MEDIUM (Inspection required) <input checked="" type="checkbox"/> C. LOW (Inspect on time available basis) <input type="checkbox"/> D. NONE (No further action needed, complete current disposition form)							
VI. INFORMATION AVAILABLE FROM							
01 CONTACT		02 OF (Agency, Organization)				03 TELEPHONE NUMBER	
04 PERSON RESPONSIBLE FOR ASSESSMENT Kenneth R. Harris		05 AGENCY SWM		06 ORGANIZATION THE L.E. of H.E.		07 TELEPHONE NUMBER (615) 74-2357	
						08 DATE 11-17-79 MONTH DAY YEAR	



☐ I HIGHLY VOLATILE
☐ J EXPLOSIVE
☐ K REACTIVE
☐ L INCOMPATIBLE
☐ M NOT APPLICABLE



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 0980515779

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ F. CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: _____ (Acres) 04 NARRATIVE DESCRIPTION

01 ☐ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN D980515779

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include name(s) of species)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ M. UNSTABLE CONTAINMENT OF WASTES
(Spills/runoffs/standing liquids/leaking drums)

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

